

# **DESIGN ANALYSIS**

# U.S. ARMY CRIMINAL INVESTIGATION COMMAND

(CATEGORY CODE 14114)

ADAPT-BUILD BIM PROTOTYPE OF THE
RA 5-9 FIELD OPERATIONS FACILITY FOR THE REGION
REPRESENTED BY FORT STEWART, GEORGIA

Prepared by:

Parsons Brinckerhoff 6161 Kempsville Circle Norfolk, Virginia 23502

# **Table of Contents**

Table of	Contents	2
1 GEI	NERAL DESCRIPTION	4
1.1	FACILITY DESCRIPTION	4
2 DES	SIGN REQUIREMENTS AND PROVISIONS	7
2.1	SITE PLANNING AND CIVIL ENGINEERING	9
2.2	STRUCTURAL ENGINEERING	12
2.3	ARCHITECTURE	16
2.4	COMPREHENSIVE INTERIOR DESIGN (CID)	20
2.5	SUSTAINABLE DESIGN	25
LEED S	corecard	34
2.6	FIRE PROTECTION	35
2.7	PLUMBING	37
2.8	HVAC SYSTEMS	39
2.9	ELECTRICAL	42
2.10	COMMUNICATIONS AND SECURITY SYSTEMS	45

# **EXECUTIVE SUMMARY**

This Design Analysis has been prepared for the U.S. Army Criminal Investigation Command (CIDC) RA 5-9 Adapt Build facility. The RA 5-9 building has been developed for a generic site at Fort Stewart, Georgia. This document presents the design objectives, general information, design criteria and assumptions, and technical calculations for the project.

This Design Analysis has been developed in association with the Building Information Model (BIM) of the RA 5-9 Adapt Build facility. The project drawings are contained as 'sheets' within the BIM, with rare exception. The BIM Execution Plan is an important document which is to be used in conjunction with this Design Analysis.

The Design Analysis and Adapt Build BIM are intended as a guide to an A/E who is designing a CIDC project, and intended to establish a consistent baseline for new facilities. As a design professional the A/E is responsible for designing the project in accordance with all federal requirements and sound architectural and engineering practice. Creative interpretation of this work is encouraged as each future CIDC project will be located at a unique location, and may have some unique requirements and features.

[NOTE to AE: The CIDC Building Design Criteria provides the basic guidelines for evaluation, planning, programming, and designing new and renovated CIDC facilities. The criteria contained in that document establish the baseline level of features to be provided in these facilities. Planning, design, operation and maintenance of CIDC facilities shall comply with Army Military construction (MILCON) requirements, MILCON Best Practices, Corps of engineers, Norfolk District (NAO) Design Guidelines, and the Activity's Installation Design Guide.

Design and construction shall use the latest Unified Facilities Criteria (UFC), Unified Federal Guide Specifications (UFGS) and other applicable codes, regulations, Technical Instructions and Manuals, and criteria. The document is intended to supplement other applicable codes and standards, without repeating the common requirements found in those documents.

Note that the design shall comply with ANSI/ASHRAE 189.1 Standard for the Design of High-Performance Green Buildings. ]

# 1 GENERAL DESCRIPTION

The U.S. Army Criminal Investigation Command (CIDC) is the Army's primary investigative organization and the premier investigative organization of the Department of Defense. The CIDC is responsible for conducting criminal investigations in which the Army is, or may be, a party of interest. Investigations range from death to fraud to computer crime, and can occur both on and off of military installations.

The CIDC deploys highly trained special agents and support personnel, a certified forensic laboratory, protective services units, computer crime specialists, polygraph services, criminal intelligence collection and analysis, and a variety of other services normally associated with law enforcement investigation activities.

The CIDC buildings are Category Code 14114 facilities. A Project Tracking Sheet is in Appendix A.

#### 1.1 FACILITY DESCRIPTION

## 1.1.1 RA 5-9 Field Operations Building

The CIDC RA 5-9 field operations buildings house command, operation and administrative functions assigned to the U.S. Army Criminal Investigation Command. The estimated occupancy of the RA 5-9 facility is 11 people.

The *front* of the facility is designed for visitors, CIDC agents, and administrative staff; the *front* of the facility also includes support areas such as Restrooms, Showers, and a Multipurpose Lounge. The *back* of the facility is designed for suspects (Waiting, Interview Rooms, and Polygraph Areas), Evidence (Collection, Processing, and Storage) and other support areas (Vault, Equipment Storage). The *front* of the facility shall be identified as the administrative area and the *back* of the facility shall be identified as the suspect area.

#### 1.1.2 Vehicle Processing Building

The Vehicle Processing Building shall be located adjacent to the Field Operation Building. This building allows for control and inspection of vehicles in order to collect evidence. This evidence may be retrieved by disassembling and removing parts, taking samples, inspection of the vehicle, and/or draining fluids.

The Vehicle Processing Building is detached from the main building, and shall be located outside of the ATFP stand-off distance.

#### 1.1.3 Building Occupancy

The CIDC RA 5-9 building is classified as a Business Occupancy (Group B). The Vehicle Processing Building is considered a Storage Occupancy – Moderate Hazard (Group S-1; Motor vehicle repair garages complying with the maximum allowable quantities of hazardous materials).

#### 1.1.4 Building Construction

Based on building size, the construction type shall be Type IIB (Non-combustible, Unprotected) as defined by the International Building Code. The Vehicle Processing Building shall also be constructed as

**FACILITY DESCRIPTION** 

Type IIB (Non-combustible, Unprotected). Based on the location of the Vehicle Processing Building relative to the adjacent property line, as shown on the Site Plan, the West exterior wall of the Vehicle Processing Building is required to have a fire rating of 1 hour. (Also see section 2.6 Fire Protection)

#### 1.1.5 Accessibility Requirements

The CIDC RA 5-9 facility is designed and shall be constructed to meet Department of Defense accessibility standards as presented in the ABA/ADA Guidelines.

#### 1.1.6 Site Design and Construction

ABA/ADA compliant access from the parking areas and site walks to the building shall be provided.

Accessible parking stalls and pathways for both staff and visitor parking areas shall be provided.

Accessible vehicle parking signage and pavement markings shall be provided.

Parking areas located within the secure (fenced) government-vehicle parking area shall be used only by able-bodied personnel in government vehicles, and for storage of impounded vehicles retained as evidence, and are not required to meet accessibility requirements.

#### 1.1.7 Facility Design and Construction

The main building entrance and secondary entrances, located outside of the secure (fenced) government vehicle parking area, shall be accessible.

Provide ABA/ADA required clearances and door approach clearances in the building main entrance as well as at secondary entrances located outside of the secure (fenced) government vehicle parking area.

Accessible drinking fountains and Multipurpose Lounge facilities shall be provided.

Accessible public restroom facilities, located near the Main Entrance, shall be provided.

#### 1.1.8 Building Area

The maximum authorized gross building area for the RA 5-9 facility is 10,508 square feet. This area total includes both the RA 5-9 building (9,740 square feet) and the Vehicle Processing Building (768 square feet).

#### 1.1.8.1 Area Definitions

Gross Area: Gross building area is measured to the outside face of exterior enclosure walls. Gross area includes floor areas, penthouses, mezzanines, and other spaces as noted below:

Half Space: Areas calculated as half space. Gross building area shall be calculated in accordance with TI 800-01 Design Criteria – Appendix B, CIDC:

Excluded Space: Some spaces are excluded from the gross area calculations, including roof overhangs used for weather protection, mechanical equipment platforms, and catwalks.

**FACILITY DESCRIPTION** 

Net Area: Net area is measured to the inside face of the room or finish walls.

Net Area Requirements: Net area requirements for programmed spaces are included in this chapter. If net area requirements are not specified, the space shall be sized to accommodate the required function and to comply with code requirements, overall gross area limitations, and any other requirements.

#### 1.1.9 Common Area

Public Restrooms are located adjacent to the Lobby area and shall comply with the ABA/ADA accessibility requirements.

Vestibules are provided as enclosed transition spaces between the outdoor environment and the building interior. A minimum distance of 7 feet is provided between the interior and exterior Vestibule doors.

Mechanical, Electrical, and Telecommunications Rooms: The Mechanical Room is designed to allow space for equipment maintenance and repair access without having to remove other equipment. Mechanical, Electrical and Telecommunications Rooms shall be keyed separately for access by maintenance personnel.

Exterior access only is provided for the Mechanical and Electrical Rooms.

The size of the Telecommunications Room (TR) for the RA 5-9 facility complies with the minimum requirements of I3A (2.5.2) and ANSI/TIA/EIA-569-B.

Recycling Storage: A Recycling Storage area is provided in the building. The Recycling Storage area is sized to accommodate recyclable containers, with adequate circulation space to allow access to move each container in and out of the Recycling Storage area.

Materials to be recycled include paper, corrugated cardboard, glass, plastics, and metals. An area shall be provided for collection and storage of fluorescent and HID lamps and ballasts.

# 2 DESIGN REQUIREMENTS AND PROVISIONS

The CIDC Facilities Building Design Criteria provides the basic guidelines for evaluating, planning, programming, and designing new CIDC facilities. The criteria contained in this document establish the baseline levels of features, spaces and finishes to be provided in these facilities. Planning, design, operation and maintenance of CIDC facilities shall comply with Army Military Construction (MILCON) requirements, MILCON Best Practices (MBP), and Corps of Engineers, Norfolk District (NAO) Design Guidelines. Design and construction shall use the latest Unified Facilities Criteria (UFC), Unified Federal Guide Specifications (UFGS) and other applicable codes, regulations, Technical Instructions and Manuals, and criteria.

- U.S. Army Corps of Engineers Criminal Investigation Command (CIDC) Facilities Building Design Criteria, 12 December 2011
- Architectural Barriers Act (ABA/ADA) Accessibility Standard for Department of Defense (DoD)
   Facilities; as directed by Secretary of Defense Memorandum, 31 October 2008
- Army Regulation (AR) 405-70 Utilization of Real Property
- AR 420-1 Army Facilities Management
- AR 195-5 Evidence Procedures
- AR195-6 Department of the Army Polygraph Activities
- AR 190-11 Physical Security of Arms, Ammunition, and Explosives
- Technical Criteria for the Installation Information Infrastructure Architecture,
- (I3A Technical Criteria), dated February 2010
- Fort Stewart Installation Design Guide
- Technical Guide for the Integration of the Secret Internet Protocol Router Network (SIPRNET) published by USAISEC Criteria
- UFC 1-200-01 Design: General Building Requirements
- UFC 3-120-10 Comprehensive Interior Design
- UFC 3-400-01 Energy Conservation (with 2008 revisions)
- UFC 3-520-01 Interior Electrical Systems
- UFC 3-530-01 Design: Interior and Exterior Lighting and Controls
- UFC 3-550-01 Exterior Electrical Power Distribution
- UFC 3-600-01 Fire Protection Engineering for Facilities
- UFC 3-580-01 Telecommunications Building Cabling Systems Planning/Design
- UFC 4-010-01 Department of Defense Minimum Anti-terrorism Standards for Buildings

# **DESIGN REQUIREMENTS AND PROVISIONS**

- UFC 4-021-01 Design and O & M: Mass Notification Systems
- National Fire Protection Association (NFPA) Codes and Standards

# 2.1 SITE PLANNING AND CIVIL ENGINEERING

#### 2.1.1 Site Planning and Civil Engineering

NOTE to Civil AE site designer from the developers of the Criminal Investigative Command (CIDC) prototype.

The site designer for the CIDC facility must have an understanding of the user's requirements, the governing design criteria requirements and the local requirements. You are responsible for integrating these elements (and more) into the final site design. The design shall be in accordance with CIDC Building Design Criteria, the US Army Corps of Engineers Design Guide, the Base Installation Design Guide, and the pertinent Unified Facilities Criteria.

The Criminal Investigative Command (CIDC) Building Design Criteria contains information specific to the user. Overall design guidance is located in Chapter 1. Site planning and civil engineering criteria are located in Chapter 3.

The USACE Norfolk District Design Guide (NAO DG) provides design criteria requirements for the development and preparation of the contract documents. These include plans, specifications and the design analysis. The NAO DG contains discipline specific sections (e.g. Civil, Architectural, Mechanical, and Electrical). Each section includes a detailed outline of the criteria requirements for the corresponding discipline.

#### **Project Specific Information**

The CIDC Adapt/Build documents were developed to varying levels of design effort. The Architectural component was developed to about 60%. The remaining engineering disciplines, with the exception of Civil, were developed to between 30%-35% design levels. Without a specific site to reference the Civil portion was limited to a 10% design level. The Civil AE is responsible for developing the site design from site selection to final development after a specific site has been selected.

The site plan depicted in the Adapt/Build prototype is a schematic site plan. It indicates the general quantities and relationships of visitor parking, staff parking and secure government vehicle parking as well as antiterrorism/force protection (ATFP) setbacks and unobstructed zones around the building.

The following comments are intended to emphasize and clarify certain design elements for the site designer:

#### 1. Site Geometry:

a. The portion of drive between the staff parking and the visitor parking may be omitted if access to both can be otherwise accommodated (i.e. by virtue of location on a corner lot) and if the Local Authority Having Jurisdiction (AHJ) does not require it for emergency perimeter access.

#### 2. Secure Government Vehicle Area

- a. There are two vehicle access points depicted on the prototype site plan. One is a sliding motor-operated gate. The other is a double swing gate.
  - i. The emergency double swing gate access need not be provided if not required by the AH. The designer is to verify these requirements. The preference is generally to omit this feature if not required by the AHJ.
  - ii. The sliding motor-operated vehicle gate with access control. Site designer to confirm type of security access (key pad, card reader, etc) with user. Coordinate fire department access requirements with the Base Fire Marshall.
- b. The striped area in front of Vehicle Processing Building entrance is intended to provide maneuvering room for tow trucks delivering vehicles for processing.
- c. The location of outdoor mechanical/electrical equipment, including transformer and future mobile generator may only be adjusted in consultation with the CIDC proponent and the USACE CoS District and upon written consent of both. These items must remain within the CIDC secured area.
- d. The fence around this area is to be 8 feet high with no barbed wire on top.
- e. There are two sizes of parking spaces in the secured parking area: government sedan (9'x18') and HUMVEE (12'x18'). The designer is to design for the number of each vehicle type, developed in collaboration with the user.

#### 3. Vehicle Processing Building

a. Note the vehicle lift. The designer should consider this when pursuing a geotechnical investigation of the site.

# 4. Weapons Clearing Barrel

a. Two weapons clearing barrels shall be located on site. One shall be located at the entrance to the building from the secure government vehicle area. The other shall be located at the entrance to the building from the Staff parking area. Confirm the exact location at each entrance with the user.

#### 5. ATFP

a. The building is currently classified as "Inhabited" for Stand-off distance determination in accordance with the definitions provided in UFC 4-010-01 dated 9 February 2012. These plans are based on the prototype. The designer is responsible for confirming building classification based on current version of UFC 4-010-01.01.

#### 2.1.2 Site Lighting

The backlight and glare ratings of building-mounted luminaires and all other luminaires shall comply with ASHRAE 189.1-2009, Table 5.3.3.2B and Table 5.3.3.2A, respectively.

All exterior lighting shall comply with either the maximum uplight ratings of Table 5.3.3.2A or the uplight requirements of Table 5.3.3.3, both of which are found in ASHRAE 189.1-2009.

SITE PLANNING AND CIVIL ENGINEERING

Site lighting sources shall be fluorescent and metal halide with good color rendition. Outdoor lighting levels are in accordance with the Illuminating Engineering Society of North America (IESNA) Lighting Handbook illumination levels.

Site lighting is controlled by photocells, motion sensors, and timers for energy conservation. Coordinate exterior lighting control with the Base (Installation). The main entrance lights and building identification lights shall be on at night. Other exterior lighting shall be controlled by motion sensors.

**STRUCTURAL** 

#### 2.2 STRUCTURAL ENGINEERING

#### 2.2.1 General

CIDC RA 5-9 is a one-story steel framed structure with a spread footing foundation. The building is located at the Army base in Fort Stewart, Georgia, 31.88°N 81.61°W.

The footprint of the building is rectangular in shape and measures approximately 63 ft by 178 ft. The building walls, both interior and exterior, are non-load resisting elements except for wind cladding or designed lateral pressure.

#### 2.2.2 Framing System

The building is a steel framed structure with hollow structural section (HSS) steel columns and wide flange steel beams at the eave elevation. The roof framing to support the green roof system shall be a 5" concrete deck (3" concrete cover over 2" composite steel deck) supported by steel joists and wide flange steel girders.

Braced frames provide lateral load resistance and columns are designed with fully pinned fixity at the base.

A steel frame structural system is selected for the CIDC prototype buildings as it is the most common type of structural system throughout the United States, and common in many parts of the world. Alternative structural systems include cast-in-place reinforced concrete and load bearing masonry. While these systems are used in some geographic areas, they are not common in all areas where a prototype building may be constructed.

A steel frame system has the advantage of allowing relatively flexible interior planning. A steel frame system is also a good structural system for areas subject to hurricanes, such as Fort Stewart, Georgia.

The typical roof form of the prototype buildings is a hip or gable roof form with a slope of 4:12 to 6:12. This roof form is commonly and efficiently constructed with prefabricated light gauge steel trusses.

A precast concrete structural system is not considered a good choice for the prototype, since the CIDC buildings are relatively small (the largest is approximately 16,000 square feet). In addition, the cost effectiveness of this type of system is extremely dependent on the proximity of the site to a precast concrete plant.

Another advantage of a steel frame system is that steel is a commonly recycled product. It is likely that a new CIDC building built with a steel frame would have a high content of recycled material. The American Institute of Steel Construction estimates that structural steel beams and columns produced at U.S. mills has a recycled content above 80%. In addition, when the building is dismantled in the future, 50 or more years from now, the steel structural components can be easily recycled (or reused). Masonry and concrete structures do not have the same environmental advantages.

The Vehicle Processing prototype buildings utilize a load bearing masonry wall as the main structural system, and prefabricated light gauge steel trusses for the roof. This system is selected as the building is small, and the required interior finish is painted concrete block. This is a durable interior finish; if the building were framed in steel providing a durable interior finish would be expensive. The most likely choice would be cement plaster applied to a cement board base installed on steel studs.

#### 2.2.3 Foundation

Gravity load and lateral load are delivered to the columns that are supported by the concrete footings. Typically the top of footing shall be 1.5 ft below finished floor for interior and exterior footings. The design frost line is 0 inches below soil cover.

For gravity loads (Dead and Live Loads), strip and column footings supported on undisturbed native soil stratum or structural fill with proper compaction can be designed for net allowable soil bearing capacities of 2,000 pounds per square foot (psf) for service loads. Allowable soil bearing capacities for transient loads (Wind and Seismic Loads) are permitted to increase by 30% to approximately 2,700 psf.

The ground level slab-on-grade shall be designed to meet the load requirements. The floor slab shall be designed as "floating", ground supported and without rigid connections to columns and perimeter walls. Contraction joints are provided to control shrinkage crack pattern. Although the slab is designed as unreinforced slab, 0.1% of steel reinforcement is provided by either wire mesh or rebar. Vapor barrier shall be provided under the concrete slab.

Final foundation design shall be confirmed based on the findings of the geotechnical report.

#### 2.2.4 Special Features

Although not a structural feature, the green roof does require a more substantial roof structure than a conventional roof system due to its weight. Other than coordination to ensure that the structure conforms to any requirements unique to the green roof system, there are no other special features to the structure.

#### 2.2.5 Force Protection System

The building envelope shall meet the ATFP criteria governed by section B.3 of UFC 4-010-01. Glazed openings on the exterior walls shall be designed for blast pressure. Since the building is within a controlled perimeter and has a standoff distance of 82 feet the structural frames for the glazed openings shall therefore be designed for type II explosive. The design criterion shall be "low level of protection".

#### 2.2.6 Fire Resistance

A Fire Rating of 0.0 hours has been assigned to column and roof elements. (Also see section 2.6Fire Protection)

# 2.2.7 Design Criteria

This building satisfies the design specifications of IBC 2006 and ASCE-7.

**STRUCTURAL** 

#### 2.2.8 Load Assumption

#### **2.2.8.1 Dead Load**

Actual calculated weight of permanent construction per SEI / ASCE-7.

#### **2.2.8.2** Live Load

Minimum live load allowances are determined per IBC and parameters provided by USACE NAO.

#### 2.2.8.3 Snow and Roof Live Load

Design Ground snow load is 0 psf. The roof live load of 20 psf shall control over the Flat Roof Snow Load of 0 psf. Effect of snow drift and unbalanced snow load are not considered due to the geometry of the roof.

#### **2.2.8.4** Wind Load

Basic wind speed shall be 110 mph, based on a 3-second gust, and Importance factor 1.00, Exposure Category "C". Buildings are designed as enclosed structures.

#### 2.2.8.5 Seismic Load

According to the calculation from USGS,  $S_s$ =29.00%g and  $S_1$ =10.00%g for this site. This yields a Seismic Design Category C.

Site Class D has been chosen at this time. Seismic loading shall be confirmed using the findings of the geotechnical report.

# 2.2.9 Material Properties

# 2.2.9.1 Concrete Strength

Design masonry assemblage strength

Footings	f'c = 4,000 psi
Foundation walls and pedestals	f'c = 4,000 psi
Ground floor slab	f'c = 4,000 psi
All concrete not otherwise specified	f'c = 4,000 psi
2.2.9.2 Reinforcing Bars ASTM A 615 Grade 60, Deformed	fy = 60 KSI
2.2.9.3 <b>Masonry</b>	

SEPTEMBER 12, 2012 Page 14

f'm = 1,500 PSI

**STRUCTURAL** 

# 2.2.9.4 Steel

Wide flange shapes - ASTM A 992 fy = 50 KSI

Tube shapes - ASTM A 500 Grade B fy = 46 KSI

All other structural steel - ASTM A 36 fy = 36 KSI

Welding electrodes - AWS D1.1 E70XX

# 2.2.10 Structural Calculations

Structural calculations are contained in Appendix C.

# 2.3 ARCHITECTURE

#### 2.3.1 General

The design shall be in accordance with the current version of the Unified Facilities Criteria UFC 1-200-01 Design: General Building Requirements and other applicable criteria, codes and standards.

# 2.3.2 Goals and Objectives

Overall architectural goals for the facility are to provide a functional, visually appealing facility that is a source of pride for facility users, and the installation, and which meets the functional requirements of the CIDC mission. The RA 5-9 buildings are designed and shall be constructed to be:

- compatible with the surrounding Fort Stewart architecture
- technically sound building components and systems
- a safe and healthy work environment
- durable and easily maintained over a 50 year projected life

# 2.3.3 Exterior Design

The exterior materials, roof forms, and detailing are based on the approved Installation Design Guide and are compatible with the local context and climate. The finish colors match the other buildings in the district.

The proposed design is based on Southern Colonial / Georgian vernacular architecture for a formal and contextual appearance. The vernacular form is adapted to a high-performance 'green' roof and parapet design.

The gable roofs at the entrances compliment the main building in form, material, and color. The regional materials, including brick, stonework, and other exterior elements, reflect Fort Stewart's design theme – "Southern Living Station of Choice".

The exterior materials, finishes, and form of the Vehicle Processing Building shall generally match the materials, finishes, and form of the main building.

#### 2.3.4 Entrances

Building entrances are readily identifiable. Entry materials include standing seam metal roofing and a durable exterior insulation and finish system. Entrances shall be accessible. Secondary entrances are provided with a canopy roof for protection from adverse weather.

#### 2.3.5 Exterior Windows and Doors

Windows shall comply with the requirements of UFC 4-010-01 Design: Minimum Antiterrorism Standards for Buildings. Exterior shading is provided by a series of sunshades. Glazing shall contain special coatings (i.e. Low-E) to meet the energy performance requirements defined in section 2.5. Reflective glass coatings shall not be used.

**ARCHITECTURE** 

#### 2.3.6 Exterior Façade

The exterior envelope shall consist of brick masonry. Cold-formed steel studs and sheathing provide the 'back-up' to the masonry wall.

#### 2.3.7 **Vegetative Green Roof**

The proposed roof system is vegetative green roof. The proposed system is a low growing, easily maintained system classified as an extensive green roof. This roof is suitable for hot, wet climates, suitable for buildings with a high roof area to wall area ratio, and suitable for buildings which are fully conditioned over long hours. The CIDC RA 5-9 building at Fort Stewart meets all of these criteria.

The suitability of a Vegetative Green Roof for this facility has been evaluated, in part, using the criteria presented in the Department of the Air Force Engineering Technical Letter (ETL) 11-8: Decision Criteria for Installing Vegetative Green Roofs. (Appendix D)

The benefits of the vegetative green roof, when compared to a sloped metal roof, include reduced energy consumption and reduced peak cooling load. The life of the roof membrane is extended with a green roof, as it is protected from solar radiation. Additional benefits include storm water quantity and quality control and reduction of heat island effect.

#### 2.3.8 Rain Water Harvesting

The rainwater harvesting system shall employ roof drains and drain piping in order to harvest rain water and convey it to a single point of collection. At the point of collection, rainwater shall be transported through a vortex filter and stored in a below grade storage tank. Harvested rainwater shall be supplied to toilets and urinals, and used for irrigation and other non-potable water uses.

#### 2.3.9 Canopy Roofing

For entrance canopies and roof, standing seam roof panels are used, installed over roof sheathing and cold-formed steel joists. The gable roof form is similar to the roof form of local buildings and accents the rectilinear form of the main building.

#### 2.3.10 Architectural Louvers

Painted aluminum louvers with insect screens shall be used for outdoor supply air and exhaust/relief air. The louvers are designed and shall be located to comply with UFC 4-010-01.

#### 2.3.11 Interior Volume

The common ceiling height throughout the facility is 9 feet above the finished floor (AFF). Larger spaces have higher ceilings; 10 feet or 10 feet 8 inches AFF.

The Vehicle Processing Building ceiling height is set at approximately 16 feet. This allows for a HumVee to be lifted to a height of 64 inches, using a mobile lift. Clearance above the vehicle is approximately 4 feet. All mechanical and electrical systems in the Vehicle Processing Building are below the finished ceiling.

ARCHITECTURE

#### 2.3.12 Interior Doors and Frames

Painted hollow metal frames and stained solid core wood doors shall be provided in most areas. Hollow metal doors shall be provided at service areas. Double doors are provided when convenient for moving equipment.

#### 2.3.13 Door Hardware

A card access is used to restrict access to the facility. Security locks are required for Arms Vault, and the Evidence Processing, Evidence Custodian and Evidence Depository Rooms.

#### **2.3.14 Arms Vault**

The Arms Vault shall be constructed from modular reinforced concrete panels. The Arms Vault shall include a day gate.

#### 2.3.15 Vehicle Lift

A mobile column hydraulic vehicle lift shall be installed in the Vehicle Processing Building. Coordinate capacity of lift with the largest vehicle anticipated by user to be processed.

The ceiling height in the Vehicle Processing Building is approximately 16 feet.

#### 2.3.16 Acoustical Design

The acoustical design of the facility is important considering the sensitive nature of many conversations within the building. These requirements are based on ANSI/ASHRAE Standard 189.1 and the book <a href="https://example.com/Architectural Interior Systems">Architectural Interior Systems</a> by Flynn, Kremers, Segil and Steffy.

To provide for sound privacy between spaces, partition and ceiling construction shall be constructed to meet these specific Sound Transmission Class (STC) ratings.

Administrative Offices	STC 40	
Conference and Interview Rooms	STC 45	
Polygraph Room	STC 50	
SIPRNET	STC 50	
Mechanical Room	STC 50	
Conference Rooms		
when adjacent to Restrooms	STC 53	
Conference Rooms		
when adjacent to Mechanical Room	STC 60	

ARCHITECTURE

Background noise levels are controlled through the selection and placement of equipment and through a variety of other design techniques. An acceptable background noise level (defined by Noise Criteria Curve or NC) shall be provided based on the following criteria:

Conference Rooms	NC 30
Private Administrative Offices	NC 30
Polygraph Exam Room	NC 30
Open Administrative Offices	NC 35
Interview Rooms	NC 35

The Polygraph Exam Room shall be designed in accordance with Department of the Army Polygraph Regulation AR 195-6.

# 2.4 COMPREHENSIVE INTERIOR DESIGN (CID)

#### 2.4.1 General

Comprehensive Interior Design (CID) for the project includes Structural Interior Design (SID) and Furniture, Fixtures and Equipment (FF&E). The SID and FF&E are outlined in this Design Analysis.

There are two separate functions in the RA 5-9 facility. The *front* of the facility shall be for visitors, CIDC agents, and administrative staff; the *front* of the facility also includes support areas including Restrooms, Showers, and a Multipurpose Lounge. The *back* of the facility shall be for suspects (Waiting, Interview Rooms, and Polygraph Areas), Evidence (Collection, Processing, and Storage) and other support areas (Vault, Equipment Storage). The *front* of the facility shall be identified as the administrative area and the *back* of the facility shall be identified as the suspect area.

#### 2.4.2 Structural Interior Design (SID)

Design goals for the finish materials used for ceilings, walls and floors include the following:

- aesthetically pleasing and functional finishes
- durability and ease of maintained
- recycled and sustainable materials
- neutral or medium toned interior colors

# 2.4.3 Interior Environmental Quality

All adhesives and sealants used on the interior of the building, including those used for HVAC systems, shall comply with ASHRAE 189.1 Section 8.4.2.1.1 or 8.4.2.1.2.

Paints and coatings used on the interior of the building shall comply with ASHRAE 189.1 Section 8.4.2.2.1 or 8.4.2.2.2.

Floor covering materials installed in the building interior shall comply with

- Carpet: Carpet shall be tested in accordance with and shown to be compliant with the
  requirements of CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350).
   Products that have been verified and labeled to be in compliance with Section 9 of the
  CA/DHS/EHLB/R-174 comply with this requirement.
- Hard surface flooring in office spaces: Materials shall be tested in accordance with and shown to be compliant with the requirements of CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350).

All office furniture systems and seating installed prior to occupancy shall be tested according to ANSI/BIFMA Standard M7.1 and shall not exceed the limit requirements listed in Normative Appendix E of this standard.

Ceiling and wall system emissions shall be limited. These systems include ceiling and wall insulation, acoustical ceiling panels, tackable wall panels, gypsum wall board and panels, and wall coverings. Emissions for these products shall be determined according to CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350) and shall comply with the limit requirements for either office or classroom spaces.

#### 2.4.4 Interior Wall and Ceiling Finishes

Wall finishes, floor finishes, and ceiling finishes shall conform to the requirements of NFPA 101, U.S. Army Corps of Engineers CIDC Building Design Guide, United facilities Criteria 3.120.10 Interior Design with change 1, and Unified Facilities Criteria 3-600-01 Design: Fire Protection Engineering for Facilities.

Opaque interior surfaces in daylight zones shall have visible light reflectance greater than or equal to 80% for ceilings and 70% for partitions higher than 56 inches (1.54 meters) in daylight zones, when ASHRAE 189.1 Prescriptive Option 8.4 is chosen.

#### 2.4.5 Ceilings

Acoustical ceiling tiles shall be 2 foot square tiles with a minimum recycled content of 60%. Square edge tiles are provided throughout the facility. The ceiling grid shall be a 15/16" wide metal, nonferrous, intermediate-duty system for lay-in acoustical panels. The finish of grid shall be a factory-applied white paint finish.

Moisture resistant gypsum board shall be used for ceilings in the Restrooms, Showers, and Vestibules.

Impact resistant gypsum board is used for the ceilings of suspect area, including Suspect Waiting and the Suspect Toilet Room. Impact resistant gypsum board is used for the ceiling of the Vehicle Processing Building.

The exposed gypsum board ceilings and exposed structure shall be painted with interior oil based semigloss enamel.

#### 2.4.6 Walls

Gypsum drywall, with a minimum recycled content of 60%, shall be the common interior wall material. Impact-resistant gypsum wall board shall be used from floor level to a height of 4 feet in Corridors, Suspect Waiting Areas, Storage Rooms, and Visitor Waiting areas. Fire-rated (type X) gypsum drywall shall be used for fire-rated walls. Cement board shall be used for shower walls.

Interior wall finishes shall be moisture and mildew resistant paint. Gypsum board surfaces shall be finished with a latex primer and two coats of eggshell finish of premium quality professional paint.

Concrete block walls shall receive a finish of one-coat of latex block-filler followed by one-coat of alkyd wall primer/sealer and one finish coat of oil based semi-gloss enamel paint.

Ceramic wall tile is used in toilet/shower areas in the administrative and suspect areas. Although no specific size is stated, where quarry, porcelain and ceramic is required in a design standard, it is

preferred to use larger tiles, such as 8x8 or 12x12 to minimize the grout joints; use when acceptable by the use of the space within the facility. Tile shall be through-color. Colored grout with sealer shall be used. Ceramic tile wainscot shall extend 60 inches above the finished floor (AFF).

Corner Guards shall be provided at outside corners at right angles. Corner guards shall be through-color polycarbonate or rubber.

Chair rail is used in the corridors throughout the administrative areas of the facility. Chair rails shall be solid hardwood, AWI custom grade with molded shaped profile.

# 2.4.7 Flooring

Carpet tile shall be used throughout the administrative areas of the facility which includes Visitor Waiting, administrative areas, Offices, Corridors, Conference Rooms, and Large Interview Rooms. Carpet tile shall have minimum density of 6600 and 26 oz weight with a severe wear rating; carpet tile shall be tufted cut and loop pile multi colored and patterned 100% solution dyed premium branded nylon with high performance backing. Straight rubber base is used with the carpet tile.

Carpet static control shall be provided to permanently control static buildup to less than 3.5 kV when tested at 20% relative humidity and 70 degrees F in accordance with AA TCC 134. The Telecomm Room shall be finished with non-static resilient flooring.

Ceramic floor tile shall be used in toilet and shower areas in the administrative area of the facility. The tile shall be a minimum of  $12'' \times 12''$  through-color and slip resistant. Colored grout with sealer shall be used. Tile base and other pre-manufactured trim pieces shall be used.

Resilient tile flooring shall be used in the Multipurpose Room, Evidence Processing, Evidence Custodian, Evidence Depository, Photo ID and Corridors in the suspect areas of the facility, and in Small Interview Rooms. Resilient vinyl bio-based composition tile (VCT) shall be through-color commercial grade. A rubber cove base shall be used with VCT.

Thresholds of nonferrous materials shall be used where there is a transition of flooring materials. Stone thresholds shall be used where ceramic floor tile adjoins another floor material.

Concrete floors shall be exposed in the Mechanical, Electrical, Arms Vault, and Telecomm Rooms. These floors shall receive a finish of two coats of clear hardener/sealer.

Concrete floors shall be exposed in the Suspect Waiting, Suspect Toilet, TOE, and Vehicle Processing Building. These floors shall have a colored slip-resistant epoxy finish.

#### 2.4.8 Furniture, Fixtures & Equipment

#### 2.4.8.1 Fixed Furnishings

All building entrances employ an entry mat system consisting of a scraper surface, an absorption surface, and a finishing surface. Window treatments shall be provided on every exterior window and at

COMPREHENSIVE INTERIOR DESIGN (CID)

any interior view window where privacy is required. Window treatments are not provided in suspect areas. Blinds shall be one-inch wide horizontal room-darkening commercial grade aluminum blinds with hardware and controls.

FF&E procurement shall be through activity, construction contract, or procuring agency as stated in the project contract/ requirements.

Signage Assemblies consist of three primary elements; a structural rail, removable copy inserts and a wall mounted frame with trim. The signage rails shall be designed to hold injection molded plastic insert strips with integral color and tactile letters, symbols and Grade II Braille, to comply with ADA requirements. The rails and copy insert strips shall be snapped into a molded plastic frame which is secured to the wall surface. There shall be three types of signage: Identification, directional and ADA required.

Dry erase marker board shall be provided for the Multipurpose Room.

Shower area lockers shall be constructed of solid polymer and stacked two high.

Architectural woodwork shall be provided in the Multipurpose Room and Photo ID area. All architectural woodwork shall be Architectural Woodwork Institute (AWI) custom grade; all exposed surfaces are clad with high pressure plastic laminate. Upper and lower cabinets shall be closed; countertops and splashes shall be made of solid surface materials.

# **2.4.8.2** Movable Furnishings

Develop design for FF&E in accordance with activity requirements with all movable furnishings required to produce an optimum functional facility. The design of FF&E package is to include the purchase and installation of collateral equipment. Those items which are considered movable include:

**Wood Casegoods** 

Metal Furniture and Laminate-clad Furniture

Storage and Filing

**Task Seating** 

Lounge Seating, Waiting Area Seating and Guest Seating

Interview Room and Conference Room tables

Waste Receptacles and Recycling Containers

Wall-mounted Clocks, Literature Racks

Small Appliances - Refrigerator and icemaker, microwave oven, commercial coffee makers shall be ENERGY STAR Equipment

COMPREHENSIVE INTERIOR DESIGN (CID)

Flat screen TV and ceiling mounted projectors shall be ENERGY STAR Equipment

#### 2.5 SUSTAINABLE DESIGN

# 2.5.1 Design Criteria

CIDC facilities shall be designed and constructed in accordance with the following Department of Defense policies and directives on energy and resource conservation:

- Army Energy Security Implementation Strategy of 2009
- Department of the Army Memorandum: Sustainable Design and Development Policy Update (Environmental and Energy Performance) October 27, 2010
- ECB 2010-14 and ECB 2011-1
- Energy Independence and Security Act (EISA) of 2007
- Energy Policy Act (EPACT) of 2005
- Executive Order (EO) 13423 Strengthening Federal Environmental, Energy, and Transportation Management, 2007
- Executive Order (EO) 13514 Federal Leadership in Environmental, Energy and Economic Performance, 2009
- Federal Leadership in High Performance and Sustainable buildings, Memorandum of Understanding (HPSBGP/MOU), 2006
- UFC 3-400-01 Energy Conservation (with 2008 revisions)
- USACE Army LEED Implementation Guide

The RA 5-9 facility at Fort Stewart is designed and shall be constructed as a High-Performance Green Building. The sustainable design approach for this facility is based on meeting two standards; compliance with ANSI/ASHRAE Standard 189.1 and LEED Silver Certification. The ASHRAE Standard 189.1 is similar to the LEED-NC v3.0 rating system, but includes more mandatory provisions.

# 2.5.2 ANSI/ASHRAE/USGBC/IES Standard 189.1 – 2009 Standard for the Design of High-Performance Green Buildings

The project shall be designed to comply with Standard 189.1.

#### 2.5.2.1 Sustainable Sites

The site for the building project shall comply with the site selection criteria set by ASHRAE 189.1-2009, 5.3.1 *Site Selection*.

The site hardscapes shall comply with heat island effect mitigation criteria set by ASHRAE 189.1-2009, 5.3.2.1 *Site Hardscape*.

SUSTAINABLE DESIGN

See ASHRAE 189.1-2009, 5.4.1.1 *Effective Pervious Area for All Sites* for site project compliance for pervious surfaces.

The backlight and glare ratings of building-mounted luminaires and all other luminaires shall comply with ASHRAE 189.1-2009, Table 5.3.3.2B and Table 5.3.3.2A, respectively.

All exterior lighting shall comply with either the maximum uplight ratings of Table 5.3.3.2A or the uplight requirements of Table 5.3.3.3, both of which are found in ASHRAE 189.1-2009.

## 2.5.2.2 Water Use Efficiency

#### 2.5.2.2.1 Site Water Use Reduction

A minimum of 60% of the area of the improved landscape is bio-diverse planting of native plants and adapted plants other than turf grass.

A maximum of one-third of the improved landscape is irrigated by potable water.

Irrigation systems are controlled by either a qualifying smart controller that uses evapotranspiration (ET) and weather data to adjust irrigation schedules and complies with the minimum requirements or an on-site rain or moisture sensor that automatically shuts the system off after a predetermined amount of rainfall or sensed moisture in the soil.

Qualifying smart controllers meet the following minimum requirements:

Irrigation adequacy – 80% minimum ET of the plant material

Irrigation excess – not to exceed 10% when tested in accordance with IA SWAT Climatological Based Controllers  $8^{\text{th}}$  Draft Testing Protocol

#### 2.5.2.2.2 Building Water Use Reduction

Plumbing fixtures and fittings comply with the flush and flow rates requirements established in ASHRAE 189.1-2009, 6.3.2.1 *Plumbing Fixtures and Fittings*.

Additional water use requirements are noted in ASHRAE 189.1, 6.3.2.3 HVAC Systems and Equipment and ASHRAE 189.1, 6.4.2.1 Cooling Towers.

Measurement devices with remote communication capability are provided to collect water use data for each of the building subsystems; potable water and harvested rain water.

All building measuring devices, monitoring systems, and sub-meters are configured to the meter data management system. The meter provides, at minimum, daily data and records hourly water consumption. The meter data management system is capable of electronically storing water meter, monitoring systems, and sub-meter data and creating user reports showing calculated hourly, daily, monthly, and annual water consumption of each measurement device and sub-meter. The meter data

SUSTAINABLE DESIGN

management system also provides alarm notification as needed to support requirements set by the Water Use Efficiency Plan for Operation (ASHRAE 189.1-2009, 10.3.2.1.2 Water Use Efficiency).

# 2.5.2.3 Energy Efficiency

To satisfy energy efficiency requirements, the prescriptive path listed in ASHRAE Standards 189.1-2009 and 90.1-2007 is being followed. Building envelope insulation requirements are being increased. Solar hot water heating is utilized as an on-site renewable energy system. To provide "free" cooling in the building a waterside economizer shall be used.

#### 2.5.2.3.1 Climate Zone and Weather Data

Fort Stewart is located in Climate Zone 2-A HOT-WET.

Outdoor design temperatures are derived from ASHRAE 90.1-2007:

99.6% Heating Design Temp	26 degrees F
1% DB Cooling Design Temp	93 degrees F
1% WB Cooling Design Temp	76 degrees F

The full-year weather data used for energy modeling is from the DOE-2 TMY-3 database.

# 2.5.2.3.2 Interior Space Temperatures

Interior design temperatures are 70 degrees F for heating and 75 degrees F for cooling. Temperature drift points are 55 degrees F and 80 degrees F.

#### 2.5.2.3.3 Power or Plug Loads

Plug loads are assumed to be 0.75 watts per square foot, for energy analysis and modeling.

#### 2.5.2.3.4 Electrical Power

ASHRAE 189, 7.4.5.1: The project shall contain automatic systems, such as demand limiting or load shifting, that are capable of reducing electric peak demand of the building by not less than 10% of the projected peak demand.

Feeder conductors shall be sized for a maximum voltage drop of 2% at design load.

Branch circuit conductors shall be sized for a maximum voltage drop of 3% at design load.

#### 2.5.2.3.5 Lighting

The installed interior lighting power includes all power used by the luminaires, including lamps, ballasts, transformers, and control devices. Luminaires that are not included in the calculation are as follows: exit signs and furniture-mounted supplemental task lighting that is controlled by an automatic shut-off switch.

SUSTAINABLE DESIGN

The luminaire wattage incorporated into the installed interior lighting is determined by the operating input wattage of the maximum lamp/auxiliary combination based on values from the auxiliary manufacturers' literature (for luminaires with permanently installed ballasts).

The interior lighting power allowance for the building is 90% of the value determined by using the "Space by Space Method" as described in ASHRAE 90.1.

The interior lighting is controlled by occupancy sensors that turn lighting off within 30 minutes of an occupant leaving a space. These automatic control devices are implemented such that lighting can be shut off in all spaces via "automatic OFF" controls. The occupancy sensors allow "manual OFF" control. In addition, all occupancy sensors allow bi-level "automatic ON" programmed to a low light level combined with multi-level circuitry and "manual ON" switching for higher light levels. Exceptions to the control strategy include the Mechanical, Electrical, and Telecomm Rooms, where the automatic shutoff of lighting could endanger the safety of building occupants.

Corridors, as a means of egress, do not exceed the 0.1 W per square foot lighting power density limit, as defined by ASHRAE 189.1-2009.

The following spaces include controls that automatically reduce lighting power in response to available daylight by a combination of stepped switching and daylight-sensing automatic controls (capable of incrementally reducing the light level in steps automatically and turning the lights off automatically): Large Interview Room, Drug Suppression Team Room, and Admin/OPS Room.

Each space enclosed by ceiling-height partitions shall have a control device that independently controls the general lighting in the space. The location of the manual control device serving each space shall be easily accessible.

Internally illuminated exit signs shall not exceed 5W per face.

Exterior lighting is controlled by a combination of a photo sensor, motion sensors, and a time switch. All time switches are capable of retaining programming and the time setting during loss of power for a period of at least ten hours. Relay shall step down the total lighting power by 50% one hour after normal business closing and turn off outdoor lighting within 30 minutes after sunrise. The photosensors are interconnected with the relay.

Luminaires that are mentioned in the previous paragraph that operate at greater than 100W contain lamps with a minimum efficacy of 60 lumens per watt.

#### 2.5.2.3.6 **Building Orientation**

Preliminary energy studies of the RA 5-9 building indicate that the estimated annual energy consumption is not significantly affected by changes in the building orientation. This is a result of the relatively low solar heat gain through the vertical fenestration, due to shading from the sun shades and the limited area of glazing.

#### 2.5.2.3.7 Thermal Envelope

The building thermal envelope meets the minimum required R-values of insulation in framing cavities and for continuous insulation (c.i.) only.

The building envelope is designed and constructed with a continuous air barrier. All air barrier components of each envelope assembly shall be clearly identified on Construction Documents and the joints, interconnections, and penetrations of the air barrier components shall be detailed.

Opaque Element	Min. R-Value/Max. U-Value	Proposed R-Value
Roof – Attic and Other	R-49	R=60
Walls, Above-Grade – Steel- Framed	R-13 + R-5.0 c.i.	R-21 + R-10 c.i.
Slab-On-Grade Floors – Unheated	F-0.730, Ins NR	
Opaque Doors – Swinging	U-0.60	

The building exterior wall assembly, roof assembly, and fenestration have specific composite STC or OITC rating requirements dependent on building location in proximity to specific noise profiles. See ASHRAE 189.1-2009, Section 8.3.3.1 for this criteria.

#### 2.5.2.3.8 Fenestration

The proposed building includes a sunshade at each window on the East, South, and West facades of the building. These sunshades (or permanent projections) are a requirement of ASHRAE Standard 189.1 Chapter 8, when the prescriptive option is followed. The vertical fenestration area is 6% which does not exceed the limit of 40% of the gross wall area. No skylights are included in the RA 5-9 facility design.

See ASHRAE 189.1-2009, 7.4.2.9 *Fenestration Orientation* for fenestration area versus SHGC compliance for climate zone 3.

See ASHRAE 90.1-2007, 5.8 *Product Information and Installation Requirements* for insulation and fenestration labeling and testing requirements.

Fenestration Element	Max. U-Value/SHGC	Proposed U- Value/SHGC
Vertical Glazing – Nonmetal framing	U-0.45, SHGC-0.25	U-0.45, SHGC-0.25
Vertical Glazing – Metal framing (entrance door)	U-0.80, SHGC-0.25	U-0.45, SHGC-0.25

#### **2.5.2.3.9** Infiltration

The following areas of the building envelope shall be sealed to minimize air leakage:

- Joints around fenestration and door frames
- Junctions between walls and foundations, between walls at building corners, between walls and structural floors or roofs, and between walls and roof or wall panels
- Openings at penetrations of utility services through roofs, walls, and floors
- Joints, seams, and penetrations of vapor retarders
- All other openings in the building envelope

Air leakage for fenestration and doors shall be determined in accordance with NFRC 400. Air leakage shall be determined by a laboratory accredited by a nationally recognized accreditation organization and shall be labeled and certified by the manufacturer. Air leakage shall not exceed 1.0 CFM per square foot for glazed swinging entrance doors. For roll-up doors, air leakage determined by test at standard test conditions in accordance with ANSI/DASMA 105 shall be an acceptable alternate for compliance with air leakage requirements.

Building entrances that separate conditioned space from the exterior are protected with an enclosed vestibule, with all doors opening into and out of the vestibule equipped with self-closing devices. The interior and exterior doors meet the requirement for a minimum distance of 7 feet between the two when in the closed position.

#### 2.5.2.3.10 Roof Materials

The standing seam metal roof, at the canopies and at Vehicle Processing, shall have a Solar Reflectance Index (SRI) value of 30, which satisfies the minimum initial SRI of 29 for a *steep-sloped* roof. The SRI is to be calculated in accordance with ASTM E1980 for medium-speed wind conditions. The SRI is to be based upon solar reflectance as measured in accordance with ASTM E1918 or ASTM C1549, and thermal emittance as measured in accordance with ASTM E408 or ASTM C1371. For roofing products, the values for solar reflectance and thermal emittance shall be determined by a laboratory accredited by a nationally recognized accreditation organization, and shall be certified by the manufacturer.

#### 2.5.2.3.11 Building Equipment

Measurement devices (smart meters) with remote communication capabilities are provided to collect energy consumption data for building electrical loads (consumption and demand), natural gas consumption, and on-site renewable thermal energy. These meters shall automatically communicate with a data acquisition system, and provide daily and hourly energy data. The data acquisition system shall be capable of storing data for a minimum of 36 months and creating user reports showing hourly, daily, monthly, and annual energy consumption.

SUSTAINABLE DESIGN

HVAC equipment efficiencies shall comply with ASHRAE 189, 7.4.3.1.

Fan system power limitations are noted in ASHRAE 189.1, 6.5.3.

Domestic hot water equipment efficiencies are listed in ASHRAE 189, Table C-12.

Electric motors shall comply with the requirements of the Energy Policy Act where applicable, as shown in ASHRAE 189.1-2009, Table C-13. Motors not included in the scope of the Energy Policy Act of 1992 have no performance requirements in ASHRAE 90.1-2007, Section 10 Other Equipment.

See ASHRAE 189.1-2009, 7.4.7.3 *ENERGY STAR Equipment* for equipment requirements within the scope of applicable ENERGY STAR program.

#### 2.5.2.3.12 Control Strategies - HVAC

The cooling system is designed to distribute cooling at the zone level, therefore, the thermostatic controls for the equipment conveying cool air is set at the zone level. The heating system is controlled at the room level.

Automatic shutdown, temperature setback control and optimum start time control shall be provided by the Energy Management and Control System (EMCS).

Ventilation outdoor air dampers automatically shut during preoccupancy building warm-up, cool down, and setback, except when ventilation reduces energy costs (e.g. night purge).

All HVAC equipment shall be monitored and/or controlled through the energy management and control system.

#### 2.5.2.3.13 Control Strategies - Service Hot Water

Temperature controls are provided that allow for storage temperature adjustment from 120°F or lower to a maximum temperature compatible with the intended use.

The recirculation pump for the hot water system is equipped with an automatic time switch set to switch off the water heaters when the facility is unoccupied.

Temperature control means are provided to limit the maximum temperature of water delivered from lavatory faucets in the restrooms to 110 degrees F.

# 2.5.2.4 Renewable Energy

The RA 5-9 building shall include an on-site renewable energy system. An on-site wind generation system and an active solar water heating system shall be evaluated. The system annual output shall meet the minimum requirement of 6.0 KBtu per square foot.

#### 2.5.3 LEED (Leadership in Energy and Environmental Design)

The RA 5-9 facility is designed to achieve LEED Silver Certification under the USGBC 2009 rating system. The Vehicle Processing Building does not meet LEED minimum requirements, so it cannot be certified. However, the building shall be designed with a sustainable approach similar to the main building.

As presented on the LEED scorecard included at the end of this section there are 76 points that may be achievable. For Silver Certification, a minimum of 50 points are required; an additional 10 points are included (a 20% contingency) in the 'Y' column of the scorecard since the project is currently at the concept design level.

The LEED credits which are being pursued include the following key items:

SS C4.2: Alternative Transportation – Bicycle Storage and Changing Room

Bicycle racks shall be located within 200 yards of building entrance with storage for 5% of building users and shower and changing facilities for 0.5% of full time equivalent occupants.

SS C4.4: Alternative Transportation – Parking Capacity

This project shall utilize Option 1 – non-residential with new parking. Preferred parking for carpools or vanpools for 5% of the total provided parking spaces.

SS C5.2: Site Development – Maximize Open Space

This project is for a military base, therefore there are no local zoning requirements in place. Option 2 shall be used in order to promote biodiversity by providing a high ratio of open space to development footprint.

SS C6.1: Stormwater Design – Quantity Control

Reduce the quantity of natural hydrology by reducing impervious cover, increasing on-site infiltration, reducing or eliminating pollution from storm water runoff and eliminating contaminants.

SS C6.2: Stormwater Design - Quality Control

The project shall include a storm water management plan to control the quality of storm water.

SS C7.1: Heat Island Effect – Non-roof

To minimize the heat island effect 50% of the site hardscape shall be selected in

SS C8: Light Pollution Reduction

Project shall reduce input power, by automatic device, for interior lighting. The project shall minimize light trespass from the building and site, reduce sky-glow, improve nighttime visibility and reduce development impact from lighting on nocturnal environments.

SUSTAINABLE DESIGN

WE C1: Water Efficient Landscaping

Landscaping is designed to reduce the use of potable water for irrigation

WE C3: Water Use Reduction

Water conserving fixtures are used to reduce potable water use for building sewage conveyance by 50%. A rain water harvesting system is used.

EA C1: Optimize Energy Performance

To estimate building energy performance a full year energy model shall be used.

EA C2: On-site Renewable Energy

Solar collectors and a hot water storage system shall be used to provide on-site renewable energy.

EA C3: Enhanced Commissioning

Energy-related building systems shall be commissioned in accordance with LEED requirements for both Fundamental Commissioning and Enhanced Commissioning. Commissioning process activities shall be completed for the following energy-related systems:

Heating, ventilating, air conditioning, and refrigeration (HVAC) systems, both active and passive, and associated controls

Lighting and daylighting controls

Domestic hot water systems

Renewable energy systems

**Building Envelope** 



# LEED 2009 for New Construction and Major Renovations

Project Checklist

CIDC Det 5-9 - Fort Stewart, GA

22-Jun

11 10 1 Sustainable Sites Possible Poir	nts: <b>26</b>	Materials and Resources, Continued	
Y ? N		Y ? N	
Y Prereq 1 Construction Activity Pollution Prevention			1 to 2
Credit 1 Site Selection	1		1 to 2
1 Credit 2 Development Density and Community Connectivity	5	1 Credit 6 Rapidly Renewable Materials	1
1 Credit 3 Brownfield Redevelopment	1	Credit 7 Certified Wood	1
6 Credit 4.1 Alternative Transportation—Public Transportation Access	6		
Credit 4.2 Alternative Transportation—Bicycle Storage and Changing Room		12 3 Indoor Environmental Quality Possible Points:	15
3 Credit 4.3 Alternative Transportation—Low-Emitting and Fuel-Efficient Ve			
Credit 4.4 Alternative Transportation—Parking Capacity	2	Y Prereq 1 Minimum Indoor Air Quality Performance	
Credit 5.1 Site Development—Protect or Restore Habitat	1	Y Prereg 2 Environmental Tobacco Smoke (ETS) Control	
1 Credit 5.2 Site Development—Maximize Open Space	1	Credit 1 Outdoor Air Delivery Monitoring	1
Credit 6.1 Stormwater Design—Quantity Control	1	1 Credit 2 Increased Ventilation	1
Credit 6.2 Stormwater Design—Quality Control	1	1 Credit 3.1 Construction IAQ Management Plan—During Construction	1
1 Credit 7.1 Heat Island Effect—Non-roof	1	1 Credit 3.2 Construction IAQ Management Plan—Before Occupancy	1
Credit 7.2 Heat Island Effect—Roof	1	1 Credit 4.1 Low-Emitting Materials—Adhesives and Sealants	1
Credit 8 Light Pollution Reduction	1	1 Credit 4.2 Low-Emitting Materials—Paints and Coatings	1
		1 Credit 4.3 Low-Emitting Materials—Flooring Systems	1
6 3 Water Efficiency Possible Poir	nts: 10	1 Credit 4.4 Low-Emitting Materials—Composite Wood and Agrifiber Products	1
		1 Credit 5 Indoor Chemical and Pollutant Source Control	1
Y Prereq 1 Water Use Reduction—20% Reduction		Credit 6.1 Controllability of Systems—Lighting	1
Credit 1 Water Efficient Landscaping	2 to 4	1 Credit 6.2 Controllability of Systems—Thermal Comfort	1
2 Credit 2 Innovative Wastewater Technologies	2	1 Credit 7.1 Thermal Comfort—Design	1
3 1 Credit 3 Water Use Reduction	2 to 4	Credit 7.2 Thermal Comfort—Verification	1
		1 Credit 8.1 Daylight and Views—Daylight	1
19 7 Energy and Atmosphere Possible Poir	nts: <b>35</b>	Credit 8.2 Daylight and Views—Views	1
Y Prereg 1 Fundamental Commissioning of Building Energy Systems		1 3 2 Innovation and Design Process Possible Points:	6
Y Prereq 2 Minimum Energy Performance		<u> </u>	
Y Prereg 3 Fundamental Refrigerant Management		1 Credit 1.1 Innovation in Design: Specific Title	1
8 5 Credit 1 Optimize Energy Performance	1 to 19	1 Credit 1.2 Innovation in Design: Specific Title	1
4 Credit 2 On-Site Renewable Energy	1 to 7	1 Credit 1.3 Innovation in Design: Specific Title	1
2 Credit 3 Enhanced Commissioning	2	1 Credit 1.4 Innovation in Design: Specific Title	1
Credit 4 Enhanced Refrigerant Management	2	1 Credit 1.5 Innovation in Design: Specific Title	1
3 Credit 5 Measurement and Verification	3	1 Credit 2 LEED Accredited Professional	1
2 Credit 6 Green Power	2		
		3 Regional Priority Credits Possible Points:	4
8 2 4 Materials and Resources Possible Poir	nts: 14	D 1 1D 1 1 FA 04 (04041)	
		1 Credit 1.1 Regional Priority: EA C1 (31314)	1
Y Prereq 1 Storage and Collection of Recyclables		Credit 1.2 Regional Priority: IEQ C7.1 (31314)	1
3 Credit 1.1 Building Reuse—Maintain Existing Walls, Floors, and Roof	1 to 3	1 Credit 1.3 Regional Priority: SS C6.1 (31314)	1
1 Credit 1.2 Building Reuse—Maintain 50% of Interior Non-Structural Elemen		Credit 1.4 Regional Priority:	1
2 Credit 2 Construction Waste Management	1 to 2	(ol or an Total	110
Credit 3 Materials Reuse	1 to 2		110
		Certified 40 to 49 points Silver 50 to 59 points Gold 60 to 79 points Platinum 80 to 110	

# 2.6 FIRE PROTECTION

#### 2.6.1 General

The fire protection design criteria for this facility include the current versions of the Unified Facilities Criteria 3-600-01 Fire Protection Engineering for Facilities, the International Building Code and the referenced National Fire Protection Association (NFPA) Codes and Standards.

A detailed Building Code analysis is provided on Drawing G-101. A number of assumptions were made in the completion of the Code Analysis. These assumptions include the following:

- The building shall be placed on a site with the minimum distances to the property lines (or assumed property lines) as indicated. In the event that the building is placed closer to a property line or another building than indicated in these documents, the exterior wall ratings shall need to be re-evaluated.
- An increase of 300% in allowable building area was included for automatic sprinkler protection. No allowable increase was taken for the increased access around the building.
- Based on the building size, occupancy type, and installation of automatic sprinkler protection, the allowable construction type could be any type other than Type V-B. The most cost effective construction type that does not require protected construction (i.e. fireproofing) is Type II-B.
   This construction type also offers the most flexibility for possible future expansion.
- There are no special locking arrangements (no locked doors) in the means of egress.

#### 2.6.2 **Building Occupancy**

The CIDC RA 5-9 building is classified as a Business Occupancy (Group B). The Vehicle Processing Building is considered a Storage Occupancy – Moderate Hazard (Group S-1 Motor Vehicle Repair Garage complying with the maximum allowable quantities of hazardous materials).

#### 2.6.3 Fire Protection

Fire protection shall be provided by a wet pipe sprinkler system in both the Main RA 5-9 Building and the Vehicle Processing Building. The system shall meet the requirements of UFC 3-600-01 and NFPA 13: Standard for the Installation of Sprinkler Systems. All sprinklers shall be quick response type.

Based on a single story building and Light/ Ordinary Hazard occupancy, it is likely that this building shall not require a fire booster pump. However, the floor plan does include space for a fire pump in the event that the water supply cannot provide the required pressure.

#### 2.6.4 Fire Extinguishers and Cabinets

Portable fire extinguishers are provided in accordance with NFPA 10.

#### 2.6.5 Interior Wall and Ceiling Finishes

Wall and ceiling finishes and movable partitions shall conform to the requirements of NFPA 101.

FIRE PROTECTION

#### 2.6.6 Fire Alarm/ Mass Notification System

The fire alarm system shall conform to requirements of UFC 3-600-01 and NFPA 101 throughout each structure. Fire alarm system shall consist of pull stations, audio and visual devices, control/annunciation panel and tamper and/or flow connection/supervision to the sprinkler system. Installation of Fire alarm system shall be in accordance with NFPA 72.

A combined Fire Alarm/Mass Notification system shall be provided in accordance with UFC 4-021-01, Mass Notification Systems. A voice evacuation system shall be used for the audible notification appliances. The speakers used for the fire alarm voice evacuation system also serve as the audible Mass Notification System. Dual clear lens / amber lens strobe lights (clear for "Fire" and amber "Mass Notification") shall be provided for visual notification and must be installed in accordance with NFPA 72 and ADA guidelines. A micro-phone for voice announcements (local operating console) shall be provided at the main entrance and at the side entry (most remote from the main entry).

**PLUMBING** 

#### 2.7 PLUMBING

#### 2.7.1 General

The plumbing design of the RA 5-9 CIDC building at Fort Stewart complies with Unified Facilities Criteria (UFC) documents, the ABA/ADA Accessibility Standards for Federal Facilities, LEED – NC for New Construction Reference Guide 2009, and ASHRAE 189.1-2009 Standard for the Design of High-Performance Green Buildings.

The Suspect Toilet Room shall have a wall-hung stainless steel lavatory, wall-hung stainless steel water closet, and a non-breakable mirror. Accessories within this room shall be vandal resistant design.

#### 2.7.2 Building Water Use Reduction

Low-flow plumbing fixtures are used to maximize water efficiency. Public lavatory faucets shall have a maximum flow rate of 0.5 GPM. Dual flush water closets shall be used with an effective flush volume of 1.28 gallons; and urinals shall have a maximum flush volume of 0.5 gallons.

#### 2.7.3 Domestic Water Heating

An active solar hot water system is utilized to satisfy the domestic hot water load. The domestic hot water demand is approximately 560 gallons per day. This equates to a maximum domestic hot water load of approximately 280,000 Btu/day. For design an assumption is made that 60% of the maximum load is considered the consumption in a typical day. This is approximately 2,168,000 Btu/day.

The solar collectors are sized for the month of January, when the solar radiation intensity is the lowest, in order to estimate solar collector area. This yields a solar collector area of about 200 ft<sup>2</sup>. These collectors are placed on a parking cover for the parking spaces closest to the project building on the north side of the site. The parking shade is sloped to give the panels a south-facing orientation.

The solar storage tank is 250 gallons and includes a double wall heat exchanger. The solar hot water system is supplemented by a natural gas-fired condensing boiler, one of the two boilers used for space heating. This equipment is located in the Mechanical Room.

#### 2.7.4 Vehicle Processing Building

The domestic hot water system for this facility is separate from the main building. An instantaneous natural gas fired water heater shall be the source of domestic hot water.

Plumbing items include a continuous trench drain with continuous grating at the inside of the overhead door, and an emergency eye wash and shower.

A lavatory and a water closet are not required for the Vehicle Processing Building since the path of travel to the nearest restroom facility does not exceed 500 feet.

#### 2.7.5 Metering

Smart Meters shall be used to monitor the energy and resource use of the facility. Smart Meters capture complex energy or resource use information and transmit this information on a real-time (or near real-time) basis.

U.S. Army Criminal Investigation Command RA 5-9 Field Operations Building Adapt-Build Fort Stewart, Georgia

**PLUMBING** 

#### 2.7.6 Water Meters

Provide metering and sub metering of water use including separate metering of potable and harvested rain water systems.

#### 2.7.7 Natural Gas Meter and Pressure Regulator

A gas meter and pressure regulator shall be provided. The gas meter shall be a 'Smart Meter' and report to the Energy Management Control System.

#### 2.8 HVAC SYSTEMS

#### 2.8.1 General

The mechanical design for all CIDC facilities shall be in accordance with the current version of the Unified Facilities Criteria (UFC) documents and all applicable codes and standards, including the ABA/ADA Accessibility Standards for Federal Facilities, LEED – NC for New Construction Reference Guide 2009, and ASHRAE 189.1-2009 Standard for the Design of High-Performance Green Buildings.

#### 2.8.2 Facility Energy Conservation Requirements

Comply with ASHRAE 189.1 Chapter 7 Energy Efficiency using either the Prescription Option Section 7.4 or the Performance Option 7.5.

Plug loads shall be included in building energy modeling but shall be subtracted in the final calculation of energy performance.

#### 2.8.3 HVAC Systems

Ventilation rates shall meet the minimum requirements of the International Mechanical Code, and the current ASHRAE Standard 62.1. The HVAC system shall provide filtered outdoor air to all occupied spaces at air volumes that meet these minimum rates. A Demand Controlled Ventilation system shall be evaluated.

Provide permanent equipment to measure the outdoor air flow rate for each ventilation system, as required by ASHRAE 189.1

Outdoor air intake louvers or grilles shall be placed at least 10 feet above finished grade to meet the requirements of UFC 4-010-01 Minimum Antiterrorism Standards for Buildings.

Chlorofluorocarbon (CFC) based refrigerants shall not be used in HVAC and refrigeration systems.

Cooling towers shall be equipped with efficient draft eliminators in compliance with ASHRAE 189.1.

The HVAC systems shall be designed in accordance with the noise criteria (NC) ratings required for the RA 5-9 facility.

#### 2.8.4 HVAC System Evaluations and Selection

The Baseline HVAC system, as defined by ASHRAE Standard 90.1 and used for energy modeling, is a packaged single zone constant volume system with direct expansion (DX) cooling and a fossil fuel furnace.

#### 2.8.4.1 Proposed System 1

A HVAC system, consisting of an air-cooled chiller and interior fan coil units, shall be evaluated. The air-cooled chiller shall be located on-site; waste heat recovery from the condenser shall be evaluated as an option.

**HVAC SYSTEMS** 

#### 2.8.4.2 Proposed System 2

A ground-source heat pump system shall also be evaluated.

#### 2.8.5 Space Heating

A hot water heating system shall be evaluated for space heating including perimeter radiation at Vestibules and similar spaces, and copper coils at fan-powered VAV boxes. The heating system shall also include two natural gas hot water condensing boilers and pumps, located in the Mechanical Room.

#### 2.8.6 Energy Management and Control System (EMCS)

The EMCS shall be a complete non-proprietary direct digital control (DDC) system for monitoring and control of the heating, ventilating, and air conditioning (HVAC) systems, lighting systems, and other building systems.

The EMCS system is designed as an Open system; the system can be repaired, upgraded, and/or expanded without dependence on the original system supplier.

The EMCS monitors and controls site lighting fixtures, the main RA 5-9 Building and the Vehicle Processing Building.

#### 2.8.7 Emergency Shut-down

An air distribution system emergency shutoff switch, as required under UFC 4-010-01, shall be provided. This emergency switch is located near the main building entrance. Shut down shall also occur upon fire alarm activation.

#### 2.8.8 Evidence Depository

The Evidence Depository Room of the CIDC building shall be provided with a separate HVAC system in order to provide 24/7 space conditioning without operating the main HVAC systems. The separate HVAC system is also intended to contain fumes and odors within Evidence Depository.

#### 2.8.9 Telecommunication Room

The Telecommunication Room is served by an independent and dedicated air-handling air-conditioning system. The nominal cooling capacity is 1-1/2 ton. The room shall be conditioned 24 hours per day, 7 days per week to a temperature of 72 degrees F (dry bulb) and to a relative humidity of 50%.

#### 2.8.10 Arms Vault

The independent system for the Vault shall include a dehumidifier. The system shall be located outside of the caged area of the Vault.

#### 2.8.11 Mechanical Room

The Mechanical Room shall be provided with a combustible gas detector and carbon monoxide detectors.

U.S. Army Criminal Investigation Command RA 5-9 Field Operations Building Adapt-Build Fort Stewart, Georgia

**HVAC SYSTEMS** 

#### 2.8.12 HVAC Systems for the Vehicle Processing Building

Ventilation rates shall meet or exceed the minimum requirements of the International Mechanical Code, and the current version of ASHRAE Standard 62.1.

Provide permanent equipment to measure the minimum outdoor air flow rate for the ventilation system, as required by ASHRAE 189.1 Exhaust rates shall be in accordance with the current edition of the International Mechanical Code and the current edition of ASHRAE Standard 62.1.

For heating, the indoor design temperature shall be 60 degrees F db. For cooling; the indoor design conditions shall be 80 degrees F db and 60% relative humidity.

The space heating system shall be an overhead natural gas fired infrared radiant heating system. For comparison, a fan coil system using a natural gas fired boiler shall be modeled.

The Vehicle Processing Building shall also have both a combustible gas detector and carbon monoxide detectors.

**ELECTRICAL** 

#### 2.9 ELECTRICAL

#### 2.9.1 Lighting

The interior and exterior lighting is compliant to IESNA Standards and meets ASHRAE Standards 90.1-2007 and 189.1-2009. The lighting design was done using the software AGI32 v2.21 instead of the built-in REVIT lighting calculation software. Differences between the two programs are the method of calculation. AGI32 uses the point-by-point method as supposed to the zonal cavity method used by REVIT. The zonal cavity method is less accurate because it uses a ratio to find the foot-candles as opposed to the average of all the points, used in the point-by-point method.

The lighting design for individual rooms includes a task light in order to better meet the occupier's needs. The illumination levels (measured in foot candles) achieved with general purpose lighting and task lighting are as follows:

Private Office	50fc
Lobbies, Lounges, Reception	10fc
Toilet	5fc
Corridor	5fc

Offices are provided with a recessed troffer direct fluorescent lighting system. The conceptual design analysis showed this to be the most efficient scheme. A troffer was chosen in order to meet the lighting power density ratio stipulated in ASHRAE 90.1 and 189.1. Transitional areas have recessed downlights. The Mechanical, Electrical, Telecommunication and TOE Storage Rooms shall consist of linear industrial fluorescent fixtures. The Restrooms shall feature wet location downlights to deal with the high levels of moisture in the room. Light switches and occupancy sensors shall be provided on the basis of ASHRAE 90.1 and 189.1.

The lighting for the corridors, open offices, and the exterior of the RA 5-9 Field Operations building, including site light fixtures associated with the building, shall be controlled by a digital, IP-addressable, microprocessor-based, programmable lighting control system. The system shall contain an accurate time-based astronomical digital clock, network graphical user interface, and local overrides. The exterior fixtures associated with parking areas shall contain photoelectric cells and controllers, so that the total amount of site lighting can be reduced to minimal levels during non-business hours. Lighting associated with site security shall be controlled manually and shall be kept to minimal levels.

The Observation Room lighting fixtures shall include dimming controls.

The "space-by-space" method was used for the lighting power density (LPD) calculation for the building. LPD using this method is found by determining the interior power allowance (AHSRAE 90.1- 2007, table 9.6.1). Then multiply the floor area(s) of the space(s) times the allowed LPD for the space type. The

U.S. Army Criminal Investigation Command RA 5-9 Field Operations Building Adapt-Build Fort Stewart, Georgia

**ELECTRICAL** 

interior lighting power allowance is the sum of the light power allowances of all spaces. Calculations can be found in the Revit model.

#### 2.9.2 Emergency and Exit Lighting

All areas of the building shall be provided with LED emergency and exit lighting and shall comply with NFPA 101. General purpose lighting fixtures, in the path of egress, include battery packs and lamps for emergency lighting. An emergency generator is not included in this facility.

#### 2.9.3 Electrical Power

The electrical transformer for the RA 5-9 facility shall be an 112.5kVA, 12.47kV – 480Y/277V, liquid-filled pad mount transformer. A 480Y/277V – 3P, 4W secondary service shall be run underground from the transformer to the main distribution panel located in the Main Electrical Room, utilizing one(1) set of four (4) #2/0 AWG plus one (1) #6 AWG 600V 90°C copper conductor in EB Type-20 concrete encased ductbank. The primary service to the transformer shall be one(1) set of #2 AWG 15-kV 133% EPR copper conductor with one (1) 100% ground. Primary protection for the transformer shall be provided in accordance with the National Electrical Code (NEC). The size of the service transformer estimate was based on the requirement of UFC 3-501-01 3-2.3.1. This requirement states that "For building design no service transformer can exceed 12VA/ft²". However, since the calculated size was 127-kVA, the closest commercially available size of 112.5kVA was chosen

Power distribution for the facility shall emanate from the building's Main Electrical Room. Surge suppression shall be provided for the 480Y/277V main electrical service and the main 208Y/120V panel. 480Y/277V power shall be provided for lighting and large mechanical loads. It is anticipated that there shall be one (1) 250A main service panel, with a 175A main circuit breaker, plus one (1) 100A MLO panel for lighting and one (1) 480Y/277V-3P, 4W, 225A MLO panels for mechanical loads. From the 480Y/277V, the power shall be transformed down to 208Y/120V for general convenience power receptacles and small mechanical loads via a 45kVA k-rated transformer (k-4). It is estimated that there shall be one (1) 208Y/120V-3P, 4W, 150A MCB MDP panel. There shall be a separate 208Y/120V-40A MCB panel for the vehicle processing building. The Telecommunication Room shall receive one (1) 208Y/120V-100A MLO panel and there shall be one (1) 208Y/120V-100A MLO panel for general receptacle loads. 600V 90°C copper feeders for sub-panels shall be provided as required.

The facility shall contain one (1) 208Y/120V-3P, 60A twist-lock water-proof receptacle, one (1) 208Y/120V-3P manual transfer switch, and one (1) 208Y/120V-3P 60A main circuit breaker panel for the estimated mission essential power requirements. Mission essential power shall be provided by a portable electrical generator, which shall be rented or leased. This portable generator is a future item and is intended for, per the program requirements, the mission essential power and not for any life safety systems. It is estimated that mission essential load is about 15-kW. CIDC requires one refrigerator and one freezer to be included with this mission essential power system.

U.S. Army Criminal Investigation Command RA 5-9 Field Operations Building Adapt-Build Fort Stewart, Georgia

**ELECTRICAL** 

#### 2.9.4 Grounding

The building structure shall be grounded in accordance with UFC requirements. A complete copper grounding system shall be provided. A ground ring shall be installed, connected to the building structure at each steel column. Neutrals of the electrical distribution system shall be bonded at the main distribution panels.

The Vehicle Processing Building shall have a separate grounding system.

#### 2.9.5 Lighting and Electrical Power for Vehicle Processing Building

Lighting fixtures for the Vehicle Processing Building shall include overhead and wall mounted fixtures, in order to illuminate the sides and underside of vehicles when on the lift.

The Vehicle Processing Building shall have a separate electrical distribution panel, fed from the main distribution panel. This panel provides power to lighting fixtures, receptacles, special items, and mechanical equipment. The panel shall be recessed mounted on the interior of the building and shall contain a main circuit breaker.

#### 2.10 COMMUNICATIONS AND SECURITY SYSTEMS

#### 2.10.1 Information Systems

Information systems shall consist of a complete end-to-end voice, data cable based functional design accomplished in accordance with the I3A Technical Criteria. Information system equipment provided to satisfy the service requirements of this facility shall meet the technical specifications and planning guidance found in ANSI/TIA/EIA-568-B and 569-A, as appropriate.

System provisions shall be compliant with the requirements of the Department of Defense (DoD) ABA/ADA Standards for accessibility.

Metallic separation is provided between telecommunication and power wiring in power poles, under floor conduit systems, and systems furniture raceways.

#### 2.10.2 Telecommunications Systems

Telephone and data communications for the facility shall be distributed throughout the building from the Telecomm Room. Punch down blocks, Cat-6 4-pair cable, 50 μm multimode fiber optic cable, and telephone jacks shall be provided for the horizontal distribution as part of this project. For data communication, patch panels, Cat-6 4-pair cable and data jacks shall be provided. All cables shall be numbered by room and jack for both telephone and jack. Data cables shall be color-coded. Two (2) 8P8C, 568B type, shall be used for voice and data with appropriate label. Fiber optic adapters and connectors shall be TIA/EIA "SC" type (568SC). CATV and CCTV connections shall be provided through 75 ohm coaxial cable.

#### 2.10.3 Data System

Data jacks shall be terminated on Category 6 110 RJ-45 termination panels located on racks in the Telecomm Room.

#### 2.10.4 Telecommunication Requirements for Vehicle Processing Building

The system design includes two phone and two data lines, routed from the Main Building underground to the Vehicle Processing Building.

#### 2.10.5 Information System Equipment

All equipment provided for the facility shall meet the functional standards found in the I3A Technical Criteria. The building's interior copper cabling shall be EIA/TIA 568B.

#### 2.10.6 Protected Distribution System (PDS) Infrastructure

The PDS is designed and shall be installed in accordance with the I3A Technical Criteria. All PDS cable distribution and telecommunications systems comply with the I3A Technical Criteria (for design and allocations) and with the latest versions of ANSI/TIA/EIA 568B (for technical implementation).

The installation shall follow the requirements of ANSI/TIA/EIA-569-A for telecommunications paths and Equipment Room spaces. Provide dedicated PDS raceway space and Equipment Room space for the purpose of future fiber optic cable installation to each outlet location initially served only by copper

cable(s). Provide space for future data and communication cabling. Provide I3A standard dual-jack voice/data outlets throughout core areas and the supply/administration areas; use I3A functional area outlet-densities to determine the outlet quantities. Provide data outlets for all planned computer equipped desktops. Use of multiple-jack outlets to serve desktop locations, (i.e., up to four 8P8C RJ-45 type jacks) is typical.

#### 2.10.7 Paging Systems

A zoned paging system shall be provided throughout the main RA 5-9 Building and the Vehicle Processing Building, and integrated with the telephone system. The system shall allow paging to individual rooms and to all building areas. Select outdoor spaces shall be on the public area system.

#### 2.10.8 Audio/Visual System

Audio/Visual systems are designed and shall be installed to comply with I3A Technical Criteria and the program requirements. Provisions (consisting of a power receptacle and conduit for signal wiring) for a GFGI projector shall be provided in each Conference Room. CATV shall be provided in Conference Rooms. The cable television system shall consist of cabling, pathways, and outlets.

RA 5-9 building CATV systems shall conform to applicable criteria including I3A Technical Criteria and UFC 3-580-01 Telecommunications Building Cabling Systems Planning/Design. A camera and microphone for audio/video recording shall be provided at each Interview Room.

#### 2.10.9 Electronic Security System (ESS)

The security infrastructure shall be designed and installed to support Government-furnished equipment including ICIDS systems, CCTV surveillance systems, and restricted access systems. Provisions shall include dedicated power circuits, communications connections, raceways, and signal wiring for user installed devices.

Design of security systems shall also be coordinated with the Mandatory Center of Expertise (MCX) Electronic Security Center, U.S. Army Installation Support Center, Huntsville, Alabama.

All unclassified telecommunications systems and associated infrastructure shall be electrically and physically isolated from all classified telecommunications systems in accordance with NSTISSAM requirements. TEMPEST requirements shall be met on a per site basis dependent on the facility zone type and the equipment NSTISSAM level.

An alarm and closed circuit television (CCTV) system shall be provided. An alarm shall be placed at each exterior door and CCTV cameras shall be installed in corridors and at building entrances.

#### 2.10.10 Security Locks

Security locks are required for Arms Vault and the Evidence Processing, Evidence Custodian and Evidence Depository Rooms.

#### **2.10.11 Clock System**

Clocks shall be provided in Conference Rooms and in Visitor Waiting Areas.

U.S. Army Criminal Investigation Command RA 5-9 Field Operations Building Adapt-Build Fort Stewart, Georgia

**COMMUNICATIONS AND SECURITY SYSTEMS** 

#### 2.10.12 Mass Notification System

Provide a mass notification system conforming to UFC 4-010-01 and UFC 4-021-01 for the purpose of providing real-time announcements in the immediate vicinity of the building during emergency situations. Coordinate specific system requirements with the user and the Installation.

The mass notification control panel shall be located in the office of the Duty Agent.

See section 2.6 FIRE PROTECTION

**End of Section** 

U.S. Army Criminal Investigation Command RA 5-9 Adapt-Build Fort Stewart, Georgia

## APPENDIX A PROJECT TRACKING SHEET

#### Facility Type Compliance Documentation:

#### PROJECT TRACKING SHEET

Item		Component	Min.	Proposed/Designed
			Requirements	to
	Project ID	Category Code Building Code used and year	14114	N/A
		Facility Type (i.e. 1300	Criminal	N/A
		PP, DFAC, 1300 Trainee)	Investigation	,
		Building Gross Area	Command	
		2424218 61 655 111 64	Field	
			Operations	
			Building	
			RA 5-9	
			Ft Stewart, GA 9475 f <sup>2</sup>	
		Design/Construction	Adapt-Build	N/A
		Method (i.e. Design-		•
		Build, Design-Bid-Build,		
		Adapt-Build, Unique)		
		Number of building	1	N/A
		stories		
1.	Roof	Insulation (R-Value)	R-49	R-60
		Surface reflectance	Note 1	
	Walls	Insulation (R-Value)	R-13 + R-5 ci	R-21 + R-10 ci
	Floors	Insulation (R-Value)	NR	
	Doors	Assembly (U-Value)	U-0.600	
	Infiltration	Bldg Envelope Air Leakage		
6.	Vertical Glazing	Window to Gross Wall (Percentage)	40%	≈5 <b>.</b> 4%
		Thermal transmittance	U-0.450	
		Solar heat gain coefficient	SHGC-0.25	
7.	Interior Lighting	Lighting Power Density	LPD-0.9	
		Ballast Type	Electronic	
8.	HVAC	Air Conditioning	See Mechanical	
		(Cooling)	Design	
		Haatina	Narrative	
٥	Renewable Energy	Heating	See Energy	
۶.	Kellewabie Ellergy		Narrative	
10	.Energy Model	Energy Analysis Tools	TRACE 700	
	.Outdoor Design	Dry-bulb and Wet-bulb	99.6% - 26°F	
	Temperatures	Temperatures	1% DB - 93°F	
	. cper a car es	. cpc. a car es	1% WB - 76°F	
12	.Indoor Design	Dry-bulb and Wet-bulb	H - 70°F DB	
	Temperatures	Temperatures	H - 58.5°F WB	
	•	•	C - 75°F DB	
			C - 62.5°F SB	
13	.Climatic Zone		3A	
14	.Building Energy	kBTU/SQFT*year	Approx 40	
	Density		kBTU/SQFT*year	•

Item	Component	Min. Requirements	Proposed/Designed to
15.Peak Energy Usage Electrical Gas Other	KWh		
16.Annual Energy Usage Electrical Gas Other	e KWh		
17.Tons of Annual Carbon Emission	Tons		
18.LEED Version and Rating	LEED v3.0 LEED Silver	50 points	60 points
19.LEED credits earned, with percentage in Water and Energy- Gross percentage of anticipated energy savings versus baseline- Gross percentage of anticipated water savings versus baseline-	F		

#### Notes:

- 1. List applicable criteria, minimum requirements, and actual provided requirements.
- 2. Provide detailed design narrative of system and approach to meeting energy and sustainable goals in design analysis, including all energy consuming equipment, components, and energy reduction features utilized to meet energy reduction goals. On tracking sheet provide Tons of Cooling and MBH of heating. Provide energy reduction due to use of renewable energy.
- 3. Provide values based on applicable criteria
- 4. Provide two baseline values for minimum as determined by EPACT 2005 and ASHREA 90.1 calculation methodologies. Proposed column shall reflect design values proposed.
- 5. Energy Analysis is to be performed using Trane Trace 700. All associated Trace data files ".TRC" files are to be provided on CD or DVD. Trane trace has an archive feature by which files can be bundled and restored for use by other's review and use. Other energy analysis programs are not acceptable.

# APPENDIX B ARCHITECTURAL CALCULATIONS

## PARSONS BRINCKERHOFF COMPUTATION SHEET

Subject: ENVELOPE U-FACTORS - RA 5-9 (Ft. Stewart)

Made by:
Date:

Checked by:
Date:

#### **ROOF**

- 1. 4" Soil
- 2. Filter Membrane
- 3. 4" Gravel
- 4. Waterproof Membrane
- 5. 1/2" Cement Board
- 6. 2" Polyiso
- 7. Vapor Control Layer
- 8. 4" Concrete
- 9. 9-1/2" Batt Insulation
- 10. 9-1/2" Batt Insulation

$R_1 := 0.33$	$R_6 := 10$
$R_2 := 0$	$R_7 := 0$
$R_3 := 0.4$	$R_8 := 3.2$
$R_4 := 0$	$R_9 := 30$
$R_5 := 0.4$	$R_{10} := 30$

#### **Assumptions**

The vegetative roof system will be classified as "Attic and Other" according to ASHRAE 189.1-2009.

Credit is not taken for "polyiso" above deck to satisfy minimum insulation requirements.

$$U := \frac{1}{R_1 + R_2 + R_3 + R_4 + R_5 + R_6 + R_7 + R_8 + R_9 + R_{10}}$$

U = 0.013

#### WALL

- 1. Exterior Air Film
- 2. 4" Brick
- 3. 1-1/2" Airspace
- 4. 2" Polyiso
- 5. 1/2" Gyp Sheathing
- 6. 6" Batt Insulation
- 7. 5/8" Gyp Board
- 8. Interior Air Film

- $R_1 := 0.17$   $R_5 := 0.3$   $R_2 := 0.75$   $R_6 := 21$   $R_3 := 2$   $R_7 := 0.56$
- $R_4 := 10$   $R_8 := 0.68$

$$\label{eq:U} \begin{aligned} \textbf{U} &:= \frac{1}{R_1 + R_2 + R_3 + R_4 + R_5 + R_6 + R_7 + R_8} \\ \textbf{U} &= 0.028 \end{aligned}$$

#### FLOOR

- 1. Concrete Slab on Grade
- 2. Insulation NR

#### **PARSONS BRINCKERHOFF COMPUTATION SHEET**

Subject: ENVELOPE U-FACTORS - RA 5-9 Vehicle Processing

JPB Made by: 01/30/12 Date: Checked by: Date:

#### **ROOF**

- 1. Exterior Air Film
- 2. Standing Seam Metal Roof
- 3. EPDM
- 4. 3" Insulation
- 5. Metal Deck
- 6. Interior Air Film

- $R_1 := 0.17$   $R_5 := 0$
- $R_2 := 0$
- $R_6 := 0.61$
- $R_3 := 0$
- $R_4 := 15$

$$U := \frac{1}{R_1 + R_2 + R_3 + R_4 + R_5 + R_6}$$

$$U = 0.063$$

#### WALL

- 1. Exterior Air Film
- 2. 4" Brick
- 3. 2" Airspace
- 4. 2" Polyiso
- 5. 8" CMU
- 6. 4" Insulation
- 7. 5/8" Gyp Board
- 8. Interior Air Film

- $R_1 := 0.17$   $R_5 := 1.11$
- $R_2 := 0.75$   $R_6 := 14$
- $R_3 := 2$   $R_7 := 0.56$
- $R_4 := 10$  $R_8 := 0.68$

$$U := \frac{1}{R_1 + R_2 + R_3 + R_4 + R_5 + R_6 + R_7 + R_8}$$

$$U = 0.034$$

#### **FLOOR**

- 1. Concrete Slab on Grade
- 2. Insulation NR

ROOM DATA				oco	CCUPANCY DATA	
NUMBER	NAME	AREA	VOLUME	TYPE	LOAD FACTOR	LOAD TOTAL
001	ENTRY VESTIBULE	79 SF	708 CF	NA		
002	VESTIBULE WEST	67 SF	605 CF	NA		
003	VESTIBULE NORTH	78 SF	702 CF	NA		
101	VISITOR WAITING AREA	236 SF	2121 CF	A-3	15	16
102	CORRIDOR	131 SF	1176 CF	NA		
103	MEN	145 SF	1308 CF	В	100	2
104	WOMEN	147 SF	1322 CF	В	100	2
105	CORRIDOR	317 SF	2851 CF	NA		
106	MULTI-PURPOSE LOUNGE	556 SF	5007 CF	A-3	15	38
107	SPECIAL AGENT IN CHARGE OFFICE	192 SF	1731 CF	В	100	2
108	LARGE INTERVIEW ROOM	231 SF	2080 CF	В	100	3
109	SMALL INTERVIEW ROOM #2	144 SF	1295 CF	В	100	2
110	SMALL INTERVIEW ROOM #1	139 SF	1248 CF	В	100	2
111	PHOTO ID ROOM	125 SF	1127 CF	В	100	2
112	POLYGRAPH OFFICE	110 SF	990 CF	В	100	2
113	POLYGRAPH EXAM ROOM	116 SF	1043 CF	В	100	2
114	OBSERVATION ROOM	120 SF	1078 CF	В	100	2
115	SUSPECT WAITING ROOM	150 SF	1349 CF	В	100	2
116	SUSPECT TOILET	65 SF	584 CF	В	100	1
117	CORRIDOR	522 SF	4694 CF	NA		
118	EVIDENCE CUSTODIAN OFFICE	166 SF	1496 CF	В	100	2
119	EVIDENCE DEPOSITORY ROOM	423 SF	3811 CF	S	300	2
120	EVIDENCE PROCESSING ROOM	160 SF	1437 CF	В	100	2
121	DUTY AGENT OFFICE	166 SF	1496 CF	В	100	2
122	TABLE OF ORGANIZATION AND EQUIPMENT STORAGE	505 SF	7075 CF	S	300	2
123	ARMS VAULT	80 SF	721 CF	S	300	1
124	TELECOM ROOM	156 SF	1407 CF	В	100	2
125	ELECTRICAL ROOM	140 SF	1962 CF	M/E	300	1
126	MECHANICAL ROOM	404 SF	5654 CF	M/E	300	2
127	CORRIDOR	673 SF	6059 CF	NA		
128	RESIDENT AGENT CRIMINAL INTELLIGENCE CENTER OFFICE	157 SF	1411 CF	В	100	2
129	TEAM CHIEF OFFICE	152 SF	1365 CF	В	100	2
130	INVESTIGATIVE OPS TECH OFFICE	138 SF	1240 CF	В	100	2
131	DRUG SUPPRESSION TEAM OFFICE	151 SF	1360 CF	В	100	2
132	SPECIAL AGENTS OFFICE	158 SF	1424 CF	В	100	2
133	SPECIAL AGENTS OFFICE	310 SF	2793 CF	В	100	4
134	RECYCLE CLOSET	84 SF	753 CF	S	300	1
135	ADMINISTRATIVE/ OPERATIONS ROOM	514 SF	4630 CF	В	100	6
136	SHOWER	116 SF	1040 CF	В	100	2
137	JANITOR	40 SF	358 CF	NA		

8363 SF 80511 CF

## PARSONS BRINCKERHOFF COMPUTATION SHEET

Prepared by: JPB
Date: 1/30/2011

SUBJECT: Minimum Plumbing Fixture Requirements

per IPC 2009

			I	14/	ATER					
					DSETS	LAVA	TORIES			
PROJECT BUILDING	CLASS	OCCUPANCY TYPE	NO. OF PEOPLE	MALE	FEMALE	MALE	FEMALE	SHOWERS	DRINKING FOUNTAINS	OTHER
RA 5-9	Business	В	11		1	1	1	-	-	1 service sink
RA 10-15	Business	В	19	1	1	1	1	-	1	1 service sink
Detachment 24	Business	В	30	1	1	1	1	-	1	1 service sink
Battalion HQ	Business	В	50 + 50 transient	2	2	2	2	-	1	1 service sink
Vehicle Processing	Storage	S-1	2		1		1	See Section 411 of IPC	-	1 service sink


NOTE: Separate facilites are not required for structures with a total occupant load of 15 or less. This applies to the RA 5-9. This also applies to drinking fountain requirements.

U.S. Army Criminal Investigation Command RA 5-9 Adapt-Build Fort Stewart, Georgia

# APPENDIX C STRUCTURAL CALCULATIONS

### **CIC - RA 5-9**

### Ft. Stewart, Georgia



Structural Calculations for 30% Design Development 24-Apr-2012

Prepared for ACOE By:



6161 Kempsville Circle Suite 110 Norfolk, VA 23502 +1.757.466.1732

#### Table of Contents

1.	Code Search	. 0:
2.	Building Frame Analysis	. 23
	RISA Model	
4.	Drift and Member Size Selection	. 48
5.	Base Load Reactions	. 84
6.	Foundation Design	. 96

### Code Search

CIC – RA 5-9; Ft. Stewart, Georgia

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

Ver 9.07.03 <u>www.struware.com</u>

#### STRUCTURAL CALCULATIONS

FOR

**CIC Detachment 5-9 Building** 

Ft. Stewart, GA

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

www.struware.com

#### **Code Search**

I. Code: International Building Code 2006

II. Occupancy:

Occupancy Group = B Business

III. Type of Construction:

Fire Rating:

Roof = 0.0 hrFloor = 0.0 hr

IV. Live Loads:

Roof angle  $\,$  ( $\theta$ )  $\,$  0.00 / 12  $\,$  0.0 deg

**Roof** 0 to 200 sf: 20 psf

200 to 600 sf: 24 - 0.02Area, but not less than 12 psf

over 600 sf: 12 psf

Floor 100 psf
Stairs & Exitways 100 psf
Balcony / Deck 100 psf
Mechanical 125 psf
Partitions N/A

#### V. Wind Loads: ASCE 7 - 05

Importance Factor	1.00
Basic Wind speed	110 mph
Directionality (Kd)	0.85
Mean Roof Ht (h)	18.0 ft
Parapet ht above grd	0.0 ft
Minimum parapet ht	0.0 ft
Exposure Category	C
Enclosure Classif.	<b>Enclosed Building</b>
Internal pressure	+/-0.18
Type of roof	Hip
Building length (L)	161.7 ft
Least width (B)	61.3 ft
Kh case 1	0.882
Kh case 2	0.882

	Topograp.	hic Facto	or (Kzt)
--	-----------	-----------	----------


Topography		Flat
Hill Height	(H)	0.0 ft
Half Hill Leng	0.0 ft	
Actual H/Lh	=	0.00
Use H/Lh	=	0.00
Modified Lh	=	0.0 ft
From top of cro	est: x=	0.0 ft
Bldg up/down wind?		downwind


H/Lh=0.00	$K_1 =$	0.000
x/Lh = 0.00	$K_2 =$	0.000
z/Lh = 0.00	$K_3 =$	1.000

At Mean Roof Ht:

 $Kzt = (1+K_1K_2K_3)^2 = 1.000$ 

H< 15ft;exp C ∴ Kzt=1.0





2D RIDGE or 3D AXISYMMETRICAL HILL

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

#### V. Wind Loads - cont.:

<b>Gust Effect Factor</b>	Flexible structure if natural frequency $< 1$ Hz (T $> 1$ second).
h = 18.0 ft	However, rule of thumb if building is if $h/B < 4$ then rigid structure.
use this h: 18.0 ft	h/B = 0.29 Therefore, probably rigid structure
D (1.2.2	

B = 61.3 ftCalculated /z = 15.0 ft

Use this z: 15.0 ft G = 0.85 Using rigid structure default

Rigid S	Structure	Flexible or D	ynamically S	ensitive St	ructure	
= 3	0.20	Natural Frequency $(n_1) =$	0.0 Hz			
1 =	500 ft	Damping ratio $(\beta)$ =	0			
$z_{min} =$	15 ft	/b =	0.65			
c =	0.20	$/\alpha =$	0.15			
$g_Q, g_v =$	3.4	$V_Z =$	92.9			
$L_z =$	427.1 ft	$N_1 =$	0.00			
Q =	0.91	$R_n =$	0.000			
$I_z =$	0.23	$R_h =$	28.282	$\eta =$	0.000	h = 18.0  ft
G =	0.88  use  G = 0.85	$R_{B} =$	28.282	$\eta =$	0.000	
		$R_L =$	28.282	$\eta =$	0.000	
		$g_R =$	0.000			
		R =	0.000			
		G =	0.000			

#### **Enclosure Classification**

Test for Enclosed Building: A building that does not qualify as open or partially enclosed.

<u>Test for Open Building:</u> All walls are at least 80% open.

 $Ao \ge 0.8Ag$ 

#### **Test for Partially Enclosed Building:**

	Input		Test	
Ao	0.0 sf	Ao ≥ 1.1Aoi	YES	7
Ag	0.0 sf	Ao > 4' / 0.01Ag	NO	
Ag Aoi	0.0 sf	$Aoi / Agi \leq 0.20$	NO	Building is NOT Partially Enclosed.
Agi	0.0 sf			<u>-</u>

Conditions to qualify as Partially Enclosed Building. Must satisfy all of the following:

Ao >= 1.1Aoi Ao > smaller of 4' or 0.01 Ag Aoi / Agi <= 0.20

Where:

Ao = the total area of openings in a wall that receives positive external pressure.

Ag = the gross area of that wall in which Ao is identified.

Aoi = the sum of the areas of openings in the building envelope (walls and roof) not including Ao.

Agi = the sum of the gross surface areas of the building envelope (walls and roof) not including Ag.

#### Reduction Factor for large volume partially enclosed buildings (Ri):

If the partially enclosed building contains a single room that is unpartitioned, the internal pressure coefficient may be multiplied by the reduction factor Ri.

Total area of all wall & roof openings (Aog): 0 sf Unpartitioned internal volume (Vi): 0 cf Ri = 1.00

#### Altitude adjustment to constant 0.00256:

Altitude = 0 feet Average Air Density =  $0.0765 \text{ lbm/ft}^3$ Constant = 0.00256


6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE 5/2/12	2
CHECKED BY	DATE	

6.1 ft 12.3 ft 30.7 ft

#### V. Wind Loads - MWFRS h≤60' (Low-rise Buildings) Enclosed/partially enclosed only



#### **Transverse Direction**

#### **Longitudinal Direction**

Kz = Kh (case 1) =	0.88	Edge Strip (	(a)
Base pressure (qh) =	23.2 psf	End Zone (2	a)
GCpi =	+/-0.18	Zone 2 length =	=

	Transv	erse Direct	ion	Longi	tudinal Di	irection
	Perpendicular $\theta = 0.0 \text{ deg}$		0.0 deg	Paral	$lel \theta = 0.0$	deg
Surface	GCpf	w/-GCpi	w/+GCpi	GCpf	w/-GCpi	w/+GCpi
1	0.40	0.58	0.22	0.40	0.58	0.22
2	-0.69	-0.51	-0.87	-0.69	-0.51	-0.87
3	-0.37	-0.19	-0.55	-0.37	-0.19	-0.55
4	-0.29	-0.11	-0.47	-0.29	-0.11	-0.47
5	-0.45	-0.27	-0.63	-0.45	-0.27	-0.63
6	-0.45	-0.27	-0.63	-0.45	-0.27	-0.63
1E	0.61	0.79	0.43	0.61	0.79	0.43
2E	-1.07	-0.89	-1.25	-1.07	-0.89	-1.25
3E	-0.53	-0.35	-0.71	-0.53	-0.35	-0.71
4E	-0.43	-0.25	-0.61	-0.43	-0.25	-0.61

	Wind Surface pressu	res (psf)			
1	13.5	5.1	13.5	5.1	
2	-11.8	-20.2	-11.8	-20.2	
3	-4.4	-12.8	-4.4	-12.8	
4	-2.6	-10.9	-2.6	-10.9	
5	-6.3	-14.6	-6.3	-14.6	
6	-6.3	-14.6	-6.3	-14.6	
1E	18.3	10.0	18.3	10.0	
2E	-20.7	-29.0	-20.7	-29.0	
3E	-8.1	-16.5	-8.1	-16.5	
4E	-5.8	-14.2	-5.8	-14.2	

Windward roof overhangs: 15.8 psf (upward) add to windward roof pressure

**Parapet** 

Windward parapet:  $0.0 \text{ psf} \quad (GCpn = +1.5)$ Leeward parapet:  $0.0 \text{ psf} \quad (GCpn = -1.0)$ 


#### Horizontal MWFRS Simple Diaphragm Pressures (psf)

#### Transverse direction (normal to L)

Interior Zone: Wall 16.0 psf
Roof -7.4 psf
End Zone: Wall 24.2 psf
Roof -12.5 psf

#### Longitudinal direction (parallel to L)

Interior Zone: Wall 16.0 psf End Zone: Wall 24.2 psf



LONGITUDINAL ELEVATION

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	


#### V. Wind Loads - MWFRS all h (Enclosed/partially enclosed only)

Kh (case 2) =	0.88		h =	18.0 ft	GCpi =	+/-0.18
Base pressure $(q_h) =$	23.2 psf		ridge ht =	18.0 ft	G =	0.85
Roof Angle =	0.0 deg		L =	161.7 ft	qi = qh	
Roof tributary area	- (h/2)*L:	1455 sf	B =	61.3 ft		
	(h/2)*B:	552 sf				

Surface Pressures (psf)	Win	Wind Normal to Ridge (psf)				Wind Pa	arallel to F	Ridge (psf)		
	B/L =	0.38	h/L = 0.29			L/B =	2.64	h/L =	0.11	
Surface	Ср	$q_hGC_p$	$w/+q_iGC_{pi}$	w/-q <sub>h</sub> GCpi	Dist.*	Cp	$q_hGC_p$	$W/+q_iGC_{pi}$	$w/$ - $q_hGC_{pi}$	
Windward Wall (WW)	0.80	15.8	see tabl	e below		0.80	15.8	see tab	le below	
Leeward Wall (LW)	-0.50	-9.9	-14.1	-5.7		-0.27	-5.3	-9.5	-1.1	
Side Wall (SW)	-0.70	-13.8	-18.0	-9.6		-0.70	-13.8	-18.0	-9.6	
Leeward Roof (LR)		**				Incl	luded in wi	ndward roof		
Windward Roof: 0 to h/2*	-0.90	-17.8	-21.9	-13.6	0 to h/2*	-0.90	-17.8	-21.9	-13.6	
h/2 to h*	-0.90	-17.8	-21.9	-13.6	h/2 to h*	-0.90	-17.8	-21.9	-13.6	
h to 2h*	-0.50	-9.87	-14.05	-5.69	h to 2h*	-0.50	-9.9	-14.1	-5.7	
> 2h*	-0.30	-5.92	-10.10	-1.74	> 2h*	-0.30	-5.9	-10.1	-1.7	

<sup>\*\*</sup>Roof angle < 10 degrees. Therefore, leeward roof is included in windward roof pressure zones.

Windward Wall Pressures at "z" (psf) Combined WW + LW Windward Wall Normal Parallel Kz Kzt  $q_zGC_p$  $w/+q_iGC_{pi}$ w/-qhGCpi to Ridge to Ridge 11.0 psf 19.4 psf 0 to 15' 0.85 1.00 15.2 psf 25.1 psf 20.5 psf 18.0 ft 0.88 1.00 15.8 20.0 25.7 21.1 11.6




WR WR LW SW LW SW DIRECTION

NOTE: See figure 6-9 of ASCE7 for the application of full and partial loading of the above wind pressures. There are 4 different loading cases.

Parapet			
Z	Kz	Kzt	qp (psf)
0.0 ft	0.85	1.00	0.0

Windward parapet: 0.0 psf (GCpn = +1.5) Leeward parapet: 0.0 psf (GCpn = -1.0)



<sup>\*</sup>Horizontal distance from windward edge

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO.	173133C	SHEET NO.	
CALCULATED BY	T.Corwith	DATE	
CHECKED BY		DATE	

#### V. Wind Loads - Components & Cladding: Buildings h≤60' & Alternate design 60'<h<90'

Kz = Kh (case 1) = 0.88 GCpi = +/-0.18 NOTE: If tributary area is greater than Base pressure (qh) = 23.2 psf a = 6.1 ft 700sf, MWFRS pressure may be used. Roof Angle = 0.0 deg

Type of roof = Hip

Code doesn't provide data for hip roofs with angles

<=7 deg or > 27 deg. Gable values shown.

Roof GCp +/- GCpi		i	Surface Pressure (psf)			User input		
Area	10 sf	50 sf	100 sf	10 sf	50 sf	100 sf	20 sf	250 sf
Negative Zone 1	-1.18	-1.11	-1.08	-27.4 psf	-25.8 psf	-25.1 psf	-26.7 psf	-25.1 psf
Negative Zone 2	-1.98	-1.49	-1.28	-46.0 psf	-34.6 psf	-29.7 psf	-41.1 psf	-29.7 psf
Negative Zone 3	-2.98	-1.79	-1.28	-69.2 psf	-41.6 psf	-29.7 psf	-57.3 psf	-29.7 psf
Positive All Zones	0.48	0.41	0.38	11.1 psf	10.0 psf	10.0 psf	10.4 psf	10.0 psf
Overhang Zone 1&2	-1.70	-1.63	-1.60	-39.5 psf	-37.9 psf	-37.2 psf	-38.8 psf	-37.2 psf
Overhang Zone 3	-2.80	-1.40	-0.80	-65.0 psf	-32.6 psf	-18.6 psf	-51.0 psf	-18.6 psf

Walls GCp +/- GCpi		Surf	ace Pressure (	User input				
Area	10 sf	100 sf	500 sf	10 sf	100 sf	500 sf	50 sf	200 sf
Negative Zone 4	-1.17	-1.01	-0.90	-27.2 psf	-23.5 psf	-20.9 psf	-24.6 psf	-22.4 psf
Negative Zone 5	-1.44	-1.12	-0.90	-33.4 psf	-26.1 psf	-20.9 psf	-28.3 psf	-23.8 psf
Positive Zone 4 & 5	1.08	0.92	0.81	25.1 psf	21.4 psf	18.8 psf	22.5 psf	20.3 psf

Note: GCp reduced by 10% due to roof angle <= 10 deg.

qp = 0.0 psf

CASE A = pressure towards building CASE B = pressure away from building

	Sur	User input		
Solid Parapet Pressure	10 sf	100 sf	500 sf	40 sf
CASE A: Interior zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf
Corner zone :	0.0 psf	0.0 psf	0.0 psf	0.0 psf
CASE B: Interior zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf
Corner zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf

#### **Rooftop Structures & Equipment**

Dist from mean roof height to centroid of Af = 0.0 ft Gust Effect Factor (G) = 0.85Height of equipment (he) = 0.0 ft Base pressure (qz) = 27.3 Kd psf

Cross-Section Square
Directionality (Kd) 0.90

Width (D) 10.0 ft h/D = 0.00

Type of Surface N/A

 $\begin{array}{ccc} \underline{\text{Square (wind along diagonal)}} & \underline{\text{Square (wind normal to face)}} \\ Cf = & 1.00 & C_f = & 1.30 \\ Af = & 10.0 \text{ sf} & A_f = & 10.0 \text{ sf} \end{array}$ 

Adjustment Factor (Adj) = 1.90 Adjustment Factor (Adj) = 1.900  $F = qz G Cf Af Adj = 39.7 Af F = q_z G C_f A_f Adj = 51.6 Af$ 


F = 397 lbs F = 516 lbs

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732


#### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 17	3133C	SHEET NO.	
CALCULATED BY T.O	Corwith	DATE	
CHECKED BY		DATE	


#### **Location of Wind Pressure Zones**




Gable  $\theta \le 7$  degrees and Monoslope  $\le 3$  degrees




Monoslope roofs  $3^{\circ} < \theta \le 10^{\circ}$ 






Monoslope roofs  $10^{\circ} < \theta \le 30^{\circ}$ 



Gable  $7 < \theta \le 45$  degrees



Hip  $7 < \theta < 27$  degrees

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

#### V. Wind Loads - Components & Cladding : h > 60'

Kh (case 1) = 0.88 h = 18.0 ft h<= 60', use C&C<90 pressures

Roof Angle = 0.0 deg qi = qh = 23.2 psf

Type of roof = Hip Code doesn't provide data for hip roofs with angles


<=7 deg or > 27 deg. Gable values shown.

Roof	GCp			Surface Pressure (psf)			User input	
Area	10 sf	100 sf	500 sf	10 sf	100 sf	500 sf	20 sf	250 sf
Negative Zone 1	-1.40	-1.11	-0.90	-36.7 psf	-29.9 psf	-25.1 psf	-34.6 psf	-27.1 psf
Negative Zone 2	-2.30	-1.89	-1.60	-57.6 psf	-48.0 psf	-41.3 psf	-54.7 psf	-44.2 psf
Negative Zone 3	-3.20	-2.67	-2.30	-78.5 psf	-66.2 psf	-57.6 psf	-74.8 psf	-61.3 psf
Positive Zones 1-3	-	-	-	10.0 psf	10.0 psf	10.0 psf	10.0 psf	10.0 psf

Walls	GCp			Surface Pressure at "h"			User input	
Area	20 sf	100 sf	500 sf	20 sf	100 sf	500 sf	20 sf	200 sf
Negative Zone 4	-0.90	-0.80	-0.70	-25.1 psf	-22.8 psf	-20.4 psf	-25.1 psf	-21.8 psf
Negative Zone 5	-1.80	-1.40	-1.00	-46.0 psf	-36.7 psf	-27.4 psf	-46.0 psf	-32.7 psf
Positive Zone 4 & 5	0.90	0.75	0.60	25.1 psf	21.6 psf	18.1 psf	25.1 psf	20.1 psf

NOTE: Negative zones 4 & 5 pressures apply to all heights. Positive pressures vary with height, see below.

	Wall surfa	ce pressure	e at "z"	Positive zone 4 & 5 (psf)			
	Z	Kz	Kzt	qz (psf)	20 sf	100 sf	500 sf
	0 to 15'	0.85	1.00	22.4	24.3	20.9	17.6
h=	18.0 ft	0.88	1.00	23.2	25.1	21.6	18.1



Parapet			
Z	Kz	Kzt	qp
0.0 ft	0.85	1.00	0.0 psf

CASE A = pressure towards building CASE B = pressure away from building

	Surf	User input		
Solid Parapet Pressure	10 sf	100 sf	500 sf	40 sf
CASE A: Interior zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf
Corner zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf
CASE B : Interior zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf
Corner zone:	0.0 psf	0.0 psf	0.0 psf	0.0 psf

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO.	173133C	SHEET NO.	
CALCULATED BY	T.Corwith	DATE	5/2/12
CHECKED BY		DATE	

#### V. Wind Loads - Open Buildings (per ASCE7-05): 0.25 ≤ h/L ≤ 1.0

Type of roof = Monoslope Free Roofs
Wind Flow = Obstructed

G = 0.85Roof Angle = 0.0 deg

#### **Main Wind Force Resisting System**

Kz = Kh (case 2) = 0.88

Base pressure (qh) = 23.2 psf

#### Roof pressures - Wind Normal to Ridge

Noor pressures while normal to Ruge						
Wind Load Flow Case	Load		Wind Direction			
			$\gamma = 0 \& 180 \deg$			
Flow	Case		Cnw	Cnl		
	<b>A</b>	Cn =	-0.50	-1.20		
Obstructed	A	p =	-9.9 psf	-23.7 psf		
Wind Flow	В	Cn =	-1.10	-0.60		
		p =	-21.7 psf	-11.8 psf		

NOTE: 1). Cnw and Cnl denote combined pressures from top and bottom roof surfaces.

- 2). Cnw is pressure on windward half of roof. Cnl is pressure on leeward half of roof.
- 3). Positive pressures act toward the roof. Negative pressures act away from the roof.

#### Roof pressures - Wind Parallel to Ridge, $\gamma = 90 \text{ deg}$

Wind	Load		Horizontal	Distance from Edge	Windward
Flow	Case		$\leq$ h	>h ≤ 2h	> 2h
Obstructed Wind Flow B	Cn =	-1.20	-0.90	-0.60	
	A	p =	-23.7 psf	-17.8 psf	-11.8 psf
	В	Cn =	0.50	0.50	0.30
		p =	9.9 psf	9.9 psf	5.9 psf

h = 18.0 ft2h = 36.0 ft

#### Fascia Panels -Horizontal pressures

qp = 23.2 psf Windward fascia: 34.8 psf (GCpn = +1.5)

Leeward fascia: -23.2 psf (GCpn = -1.0)

#### Components & Cladding - roof pressures


Kz = Kh (case 1) = 0.88 a = 6.1 ft  $a^2 = 37.6 \text{ sf}$ Base pressure (qh) = 23.2 psf  $4a^2 = 150.5 \text{ sf}$ G = 0.85

		Obstructed Wind Flow					
	Effective Wind Area	zone 3		zone 2		zone 1	
		positive	negative	positive	negative	positive	negative
	≤ 37.6 sf	1.00	-3.60	0.80	-1.80	0.50	-1.20
$C_N$	>37.6, ≤ 150.5 sf	0.80	-1.80	0.80	-1.80	0.50	-1.20
	> 150.5 sf	0.50	-1.20	0.50	-1.20	0.50	-1.20
****	≤37.6 sf	19.7 psf	-71.1 psf	15.8 psf	-35.5 psf	9.9 psf	-23.7 psf
Wind	>37.6, ≤ 150.5 sf	15.8 psf	-35.5 psf	15.8 psf	-35.5 psf	9.9 psf	-23.7 psf
pressure	> 150.5 sf	9.9 psf	-23.7 psf	9.9 psf	-23.7 psf	9.9 psf	-23.7 psf


6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

<b>JOB NO.</b> 173133C	SHEET NO.
CALCULATED BY T.Corwith	DATE 5/2/12
CHECKED BY	DATE

#### **Location of Wind Pressure Zones**





WIND DIRECTION  $\gamma = 0^{\circ}$ , 180°




WIND DIRECTION  $\gamma = 90^{\circ}$ 

#### **MAIN WIND FORCE RESISTING SYSTEM**







⊖ < 10°

⊖ ≥ 10°

PITCHED OR TROUGHED ROOF

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

>10s

0.44

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

8.4 **As** 

#### V. Wind Loads - Other Structures:

Importance Factor =	1.00		
Gust Effect Factor (G) =	0.85	Wind Speed	110 mph
Kzt =	1.00	Exposure	C

#### A. Solid Freestanding Walls & Solid Signs (& open signs with less than 30% open)

		s/h =	1.00	Case A & B	
Dist to sign top (h)	8.0 ft	B/s =	25.00	$C_{\mathrm{f}} =$	1.30
Height (s)	8.0 ft	Lr/s =	0.00	F = qz G Cf As =	24.7 As
Width (B)	200.0 ft	Kz =	0.849	$A_S =$	10.0 sf
Wall Return (Lr)	0.0 ft	qz =	22.4 psf	F =	247 lbs
Directionality (Kd)	0.85				
Percent of open area		Open reduction		<u>CaseC</u>	

to gross area	0.0%	factor =	1.00	Horiz dist from		
				windward edge	$\underline{\mathrm{Cf}}$	F=qzGCfAs (psf)
	Case C	reduction factors		0 to s	3.29	62.5 <b>As</b>
	Fac	ctor if $s/h > 0.8 =$	0.80	s to 2s	2.07	39.2 <b>As</b>
	Wall re	turn factor		2s to 3s	1.59	30.1 <b>As</b>
	f	For Cf at 0 to $s =$	1.00	3s to 4s	1.31	24.8 <b>As</b>
				4s to 5s	1.23	23.4 <b>As</b>
				5s to 10s	0.78	14.8 <b>As</b>

#### B. Open Signs & Lattice Frameworks (openings 30% or more of gross area)

Height to centroid of Af (z)	15.0 ft			Kz = Base pressure (qz) =	0.849 22.4 psf
Width (zero if round)	2.0 ft	Either width or diameter	must be zero		
Diameter (zero if rect)	2.0 ft	$D(qz)^{.5} =$	9.46	$F = q_z G C_f A_f =$	0.0 Af
Percent of open area		∈ =	0.65	Solid Area: $A_f =$	10.0 sf
to gross area	35.0%	$C_f =$	0	F =	0 lbs
Directionality (Kd)	0.85				

#### C. Chimneys, Tanks & Similar Structures

Height to centroid of Af (z	) 15.0 ft	Kz =	0.849
Cross-Section	Square	Base pressure $(qz) =$	23.7 psf
Directionality (Kd)	0.90		h/D = 15.00
Height (h)	15.0 ft		
Width (D)	1.0 ft		
Type of Surface	N/A		

Square (wind along diagon	<u>al)</u>	Square (wind:	normal to face)
Cf =	1.28	$C_f =$	1.67
F = qz G Cf Af =	25.7 Af	$F = q_z G C_f A_f =$	33.5 Af
Af =	10.0 sf	$A_f =$	10.0 sf
F =	257 lbs	F =	335 lbs

#### D. Trussed Towers

Height to centroid of Af (z)	15.0 ft	Kz =	0.849
€ =	0.27	Base pressure $(qz) =$	26.3 psf
Tower Cross Section	square		
Member Shape	flat	Diagonal wind factor =	1.2
Directionality (Kd)	1.00	Round member factor =	1.000

Square (wind along tower of	diagonal)	Square (wind	normal to face)
Cf =	3.24	$C_{ m f} =$	2.70
F = qz G Cf Af =	72.4 Af	$F = q_z G C_f A_f =$	60.3 Af
Solid Area: Af =	10.0 sf	Solid Area: $A_f =$	10.0 sf
F =	724 lbs	F =	603 lbs

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

#### VII. Snow Loads:

Roof slope = 0.0 degHoriz. eave to ridge dist (W) = 35.0 ftRoof length parallel to ridge (L) = 161.7 ft

Type of Roof Hip and gable w/ trussed systems

TJP OT TOOT	P	arra gacre .
Ground Snow Load	Pg =	0.0 psf
Importance Category	=	II
Importance Factor	I =	1.0
Thermal Factor	Ct =	1.00
Exposure Factor	Ce =	1.0

Pf = 0.7\*Ce\*Ct\*I\*Pg = 0.0 psf Pf min = 0.0 psf

Flat Roof Snow Load Pf = 0.0 psf
Rain on Snow Surcharge Angle = 0.70 deg
Code Maximum Rain Surcharge 5.0 psf
Rain on Snow Surcharge = 0.0 psf
Unobstructed Slippery

Design Roof Snow Load (Ps) = **0.0 psf** ("balanced" snow load)

Building Official Minimum = 0.0 psf

Exposure Factor, Ce				
	1	Exposure of roof		
Terrain	Fully	Fully Partially Sheltered		
A	n/a	1.1	1.3	
В	0.9	1.0	1.2	
С	0.9	1.0	1.1	
D	0.8	0.9	1.0	
Above treeline	0.7	0.8	n/a	
Alaska-no trees	0.7	0.8	n/a	

NOTE: Alternate spans of continuous beams and other areas shall be loaded with half the design roof snow load so as to produce the greatest possible effect - see code.

#### Unbalanced Snow Loads - for Hip & Gable roofs only

Larger of 2.38 degrees or 70/W + 0.5 = 2.5 deg Unbalanced snow loads are not required

Windward snow load = 0.0 psf Leeward snow load = 0.0 psf

#### Leeward Snow Drifts - from adjacent higher roof

0.0 ft Upper roof length 1u = Projection height h =0.0 ft Building separation 0.0 ft Adjacent structure factor 1.00 Snow density  $\gamma =$ 14.0 pcf Balanced snow height hb = 0.00 ft0.00 ft hc = #DIV/0! #DIV/0! #DIV/0!


Drift height hd = #DIV/0!Drift width w = #DIV/0!

Drift width w = #DIV/0!Surcharge load: pd = g\*hd = #DIV/0!

#### Windward Snow Drifts - Against walls, parapets, etc more than 15' long

#DIV/0! #DIV/0! #**DIV/0!** 

 $\begin{array}{llll} \text{Drift height} & \text{hd} = & \# \text{DIV}/0! \\ \text{Drift width} & \text{w} = & \# \text{DIV}/0! \\ \text{Surcharge load:} & \text{pd} = \text{g*hd} = & \# \text{DIV}/0! \end{array}$ 



6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

#### VII. Snow Loads - from adjacent building or roof:

	Higher Roof	Lower Roof
Roof slope =	0.0 deg	0.0 deg
Horiz. eave to ridge dist (W) =	30.7 ft	0.0 ft
Roof length parallel to ridge (L) =	161.7 ft	0.0 ft

Type of Roof	Hip and gable w/ trus	ssed systems	Hip and gable w/ truss	sed systems
Ground Snow Load	Pg =	0.0 psf	0.0 psf	
Importance Category	=	III	III	
Importance Factor	I =	1.1	1.1	
Thermal Factor	Ct =	1.00	1.00	
Exposure Factor	Ce =	1.0	1.0	
Pf = 0.7*Ce*Ct*I*Pg Pf min	= =	0.0 psf 0.0 psf	0.0 psf 0.0 psf	Terr
Flat Roof Snow Load	Pf = Surcharge Angle =	0.0 psf 0.61 deg	0.0 psf 0.00 deg	
Code Maximum Rain	0 0	5.0 psf	5.0 psf	
Rain on Snow Surchar Unobstructed Slippery	C	0.0 psf	0.0 psf	Abov Alask
11 ,	(per Section 7.4) =	no	no	Alask
Sloped-roof Factor	Cs =	1.00	1.00	

Exposure Factor, Ce				
	Exposure of roof			
Terrain	Fully	Partially	Sheltered	
A	n/a	1.1	1.3	
В	0.9	1.0	1.2	
C	0.9	1.0	1.1	
D	0.8	0.9	1.0	
Above treeline	0.7	0.8	n/a	
Alaska-no trees	0.7	0.8	n/a	

Design Roof Snow Load (Ps) = **0.0 psf** 

Building Official Minimum = 0.0 psf

0.0 psf ("balanced" snow load)

NOTE: Alternate spans of continuous beams and other areas shall be loaded with half the design roof snow load so as to produce the greatest possible effect - see code.

#### High Roof Unbalanced Snow Loads - for Hip & Gable roofs only

Larger of 2.38 degrees or 70/W + 0.5 = 2.8 deg Windward snow load = 0.0 psf

Leeward snow load =

0.0 psf

2.8 deg Unbalanced snow loads are not required

0.0 psf

#### Leeward Snow Drifts - from adjacent higher roof


Upper roof length	lu =	0.0 ft
Projection height	h =	0.0 ft
Building separation	s =	0.0 ft
Adjacent structure factor	=	1.00
Snow density	γ =	14.0 pcf
Balanced snow height	hb =	0.00 ft
	hc =	0.00 ft
#DIV/0! #DIV/0!	#DIV/0!	


Drift height	hd =	#DIV/0!
Drift width	w =	#DIV/0!
Surcharge load:	pd = g*hd =	<b>#DIV/0!</b>
Balanced Snow load:	=	0.0 psf

#### Sliding Snow - onto lower roof

 $\begin{array}{ccc} Sliding \ snow = 0.4 \ Pf \ W = & 0.0 \ plf \\ Distributed \ over \ 15 \ feet = & 0.0 \ psf \\ Balanced \ snow \ load = & \underline{0.0 \ psf} \\ Total \ snow \ load \ within \ 15' \ of \ higher \ roof = & \textbf{0.0 \ psf} \\ \end{array}$ 

Not required since upper roof slope is 1/4 in 12 or less





6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

#### VI. Seismic Loads: ASCE 7-05

Occupancy Category: II Importance Factor (I): 1.00

Site Class: D

Ss (0.2 sec) = 29.00 %gS1 (1.0 sec) = 10.00 %g

Fa = 1.568 Sms =0.455  $S_{DS} =$ 0.303 Design Category = В Fv = C 2.400 Design Category = Sm1 =0.240  $S_{D1} =$ 0.160

Seismic Design Category = C

Number of Stories: 1

Structure Type: Not applicable

Horizontal Struct Irregularities: No plan Irregularity Vertical Structural Irregularities: No vertical Irregularity

Flexible Diaphragms: No

Building System: Building Frame Systems

Seismic resisting system: Ordinary steel concentrically braced frames

System Building Height Limit: Height not limited

Actual Building Height (hn) = 18.0 ft

#### DESIGN COEFFICIENTS AND FACTORS

Response Modification Factor (R) = 3

System Over-Strength Factor ( $\Omega$ o) = 2 Deflection Amplification Factor (Cd) = 3.25

> $S_{DS} = 0.303$  $S_{D1} = 0.160$

 $\rho$  = redundancy coefficient

Seismic Load Effect (E) =  $\rho Q_E + -0.2S_{DS}D$  =  $\rho Q_E + -0.061D$   $Q_E = \text{horizontal seismic force}$ 

### PERMITTED ANALYTICAL PROCEDURES

Index Force Analysis (Seismic Category A only)

Method Not Permitted

Simplified Analysis Use Equivalent Lateral Force Analysis

Equivalent Lateral-Force Analysis - Permitted

Building period coef. ( $C_T$ ) = 0.020  $C_U$  = 1.58 Approx fundamental period ( $T_A$ ) =  $C_T h_n^x$  = 0.175 sec x=0.75  $T_{MA}$  = 0.276

User calculated fundamental period (T) = 0.175 sec x = 0.75 x = 0.175 sec x = 0.175 User T = 0.175 sec x = 0.175

Long Period Transition Period (TL) = ASCE7 map = 8Seismic response coef. (Cs) = SdsI/R = 0.101

need not exceed Cs = Sd1 I/RT = 0.305 but not less than Cs = 0.044Sds = 0.013 USE Cs = 0.101

Design Base Shear V = 0.101W

Model & Seismic Response Analysis - Permitted (see code for procedure)

#### **ALLOWABLE STORY DRIFT**

Structure Type: All other structures

Allowable story drift = 0.020hsx where hsx is the story height below level x

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

### VI. Seismic Loads - cont. :

Seismic Design Category (SDC)= C

### CONNECTIONS

### Force to connect smaller portions of structure to remainder of structure

$$\begin{split} Fp &= 0.133 S_{DS} w_p = & 0.04 \ w_p \\ \text{or} \ Fp &= 0.5 w_p = & 0.05 \ w_p & \text{Use Fp} = & 0.05 \ w_p & \text{w}_p = \text{weight of smaller portion} \end{split}$$

### Beam, girder or truss connection for resisting horizontal force parallel to member

 $F_P$  = no less than 0.05 times dead plus live load vertical reaction

### Anchorage of Concrete or Masonry Walls to elements providing lateral support

$$\begin{aligned} Fp = &0.8IeSdsWw = &0.243 \ w_w \\ or \ Fp = &0.1w_w = &0.10 \ w_w \end{aligned} \quad Use \ Fp = &0.24 \ w_w \\ Connection \ force \ given \ is \ for \ flexible \ diaphragms \ (use \ architectural \ components \ for \ ridgid \ diaphrams) \end{aligned}$$

#### **MEMBER DESIGN**

### Bearing Walls and Shear Walls (out of plane force)

$$\begin{aligned} Fp &= 0.40 IeS_{DS} w_w = & & & 0.121 \ w_w \\ or \ Fp &= 0.1 w_w = & & & 0.10 \ w_w \end{aligned} \qquad \text{Use Fp} = & & 0.12 \ w_w \end{aligned}$$

#### **Diaphragms**

$$Fp = 0.2IeSdsWp + Vpx = 0.061 Wp + Vpx$$

### ARCHITECTURAL COMPONENTS SEISMIC COEFFICIENTS

Architectural Component: 5. Veneer

a. Limited deformability elements and attachments

Importance Factor (Ip): 1.0

Component Amplification Factor  $(a_p) = 1$  h= 18.0 feet

Comp Response Modification Factor  $(R_p) = 2.5$  z = 20.0 feet z/h = 1.00

 $Fp = 0.4a_p SdsIpWp(1+2z/h)/Rp = 0.146 Wp$ not greater than Fp = 1.6SdsIpWp = 0.485 Wp

but not less than Fp = 0.3SdsIpWp = 0.091 Wp use Fp = 0.146 Wp

### MECH AND ELEC COMPONENTS SEISMIC COEFFICIENTS

Seismic Design Category C & Ip=1.0, therefore Not required

Mech or Electrical Component: Other mechanical or electrical components.

Importance Factor (Ip): 1.0

Component Amplification Factor  $(a_p) = 1$  h= 18.0 feet

Comp Response Modification Factor  $(R_p) = 1.5$  z = 20.0 feet z/h = 1.00

 $Fp = 0.4a_p SdsIpWp(1+2z/h)/Rp = 0.243 Wp$ not greater than Fp = 1.6SdsIpWp = 0.485 Wp

but not less than Fp = 0.3 SdsIpWp = 0.091 Wp use Fp = 0.243 Wp

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

### JOB TITLE CIC Detachment 5-9 Building

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

### **Roof Design Loads**

Items	Description	Multiple	psf (max)	psf (min)
Partitions	None		0.0	0.0
Decking	Floor Deck and Concrete		51.0	51.0
Framing	Steel roof beams & girders		5.0	3.0
Decking	None	x 0.0"	0.0	0.0
Ceiling	Suspended acoustical tile	x 1 ply(s)	1.8	1.0
Mech & Elec	Mech. & Elec.		2.0	0.0
Sprinklers	Sprinklers		2.0	0.0
Other	Green Roof		80.0	80.0
	Ac	tual Dead Load	• 141.8	• 135.0
	Use	this DL instead	O 20.0	9.0
		Live Load	20.0	0.0
		Snow Load	0.0	0.0
	Win	d (zone 2 - 100sf)	10.0	-29.7
ASD Loading	I	161.8	-	
	Dead + 0.75(W	Vind + Live) Load	164.3	-
	0.6*D	ead + Wind Load	-	51.3
LRFD Loading	1.2D	+ 1.6 Lr + 0.8W	210.2	-
	1.2Γ	0 + 1.6W + 0.5Lr	196.2	-
		0.9D + 1.6W	-	73.9

**Roof Live Load Reduction** 

Roof angle 0.00 / 12 0.0 deg

0 to 200 sf: 20.0 psf

200 to 600 sf: 24 - 0.02Area, but not less than 12 psf

over 600 sf: 12.0 psf

 $\begin{array}{ccc} & 300 \text{ sf} & 18.00 \\ & 400 \text{ sf} & 16.00 \\ & 500 \text{ sf} & 14.00 \\ \text{User Input:} & 450 \text{ psf} & 15.00 \\ \end{array}$ 

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

IOD TITI	CIC	Data alama and	5 0	Davildin a
JOB TITL	E CIC	Detachment	5-9	Building

JOB NO. 17.	3133C	SHEET NO.	
CALCULATED BY T.O	Corwith	DATE	5/2/12
CHECKED BY		DATE	

### Floor Design Loads

Items	Description	Multiple	psf (max)	psf (min)
Roofing	None		0.0	0.0
Insulation	None	x 0.00"	0.0	0.0
0	None		0.0	0.0
Other	None		0.0	0.0
Ceiling	None	x 0.00"	0.0	0.0
Other	None	x 0 ply(s)	0.0	0.0
Other	None		0.0	8.0
Other	None		0.0	10.0
Partitions	None		0.0	0.0
Partitions	None		0.0	0.0
		Actual Dead Load	0.0	• 18.0
		Use this DL instead	) 100.0	O 50.0
		Partitions	N/A	0.0
		Live Load	100.0	0.0
		Total Live Load	#VALUE!	0.0
		Total Load	#VALUE!	18.0

### FLOOR LIVE LOAD REDUCTION (not including partitions)

NOTE: Not allowed for assembly occupancy or LL>100psf or passenger car garages, except may reduce columns 20% if 2 or more floors & non-assembly

garages, except may reduce columns 20% if 2 or more floors & non-assembly		
	R=.08%(SF - 150)	
100 psf	R = 23.1(1+D/L) =	23.1%
	R= 40% beams; 60% columns	
2		
432 sf	R =	22.6%
76.0 psf	Reduced live load: $L =$	77.4 psf
4		
864 sf	R =	23.1%
50.5 psf	Reduced live load: L=	76.9 psf
	100 psf  2 432 sf 76.0 psf  4 864 sf	Smallest of: R= .08%(SF - 150) R= 23.1(1+D/L) = R= 40% beams; 60% columns  2 432 sf R = 76.0 psf Reduced live load: L =  4 864 sf R =

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

#### JOB TITLE CIC Detachment 5-9 Building

JOB NO. 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

www.struware.com

### **CODE SUMMARY**

Code: International Building Code 2006

#### **Live Loads:**

Roof 0 to 200 sf: 20 psf

200 to 600 sf: 24 - 0.02Area, but not less than 12 psf

over 600 sf: 12 psf

 Floor
 100 psf

 Stairs & Exitways
 100 psf

 Balcony / Deck
 100 psf

 Mechanical
 125 psf

 Partitions
 N/A

### **Dead Loads:**

Floor 0.0 psf Roof 141.8 psf

### **Roof Snow Loads:**

Design Roof Snow load 0.0 psf Pf =Flat Roof Snow Load 0.0 psf 0.0 psf Ground Snow Load Pg = Rain on Snow Surcharge 0.0 psf Snow Exposure Factor Ce = 1.00 1.00 Importance Factor I = Thermal Factor Ct =1.00 Sloped-roof Factor  $C_S =$ 1.00

#### Wind Design Data:

Basic Wind speed 110 mph Mean Roof Ht (h) 18.0 ft **Building Category** II Importance Factor 1.00 **Exposure Category**  $\mathbf{C}$ **Enclosed Building** Enclosure Classif. Internal pressure Coef. +/-0.180.85 Directionality (Kd)

#### Earthquake Design Data:

Occupancy Category:  $\Pi$ 1.00 Importance Factor I = 29.00 %g Mapped spectral response  $S_S =$ 10.00 %g accelerations S1 =Site Class D 0.303 Spectral Response Coef. Sds =Sd1 =0.160 Seismic Design Category  $\mathbf{C}$ 

Basic Structural System = Building Frame Systems

Seismic Resisting System = Ordinary steel concentrically braced frames

Analysis Procedure = Equivalent Lateral-Force Analysis

6161 Kemspville Cir, Suite 110 Norfolk, VA 757-466-1732

JOB TITLE CIC Detachment 5-9 Building	JOB TITLE	CIC	Detachment	5-9	Building
---------------------------------------	-----------	-----	------------	-----	----------

<b>JOB NO.</b> 173133C	SHEET NO.	
CALCULATED BY T.Corwith	DATE	5/2/12
CHECKED BY	DATE	

www.struware.com

### **CODE SUMMARY- continued**

### Component and cladding wind pressures

h>60 feet

 $h \le 60'$  - can't use procedure.

Roof		Surf	ace Pressure	(psf)
	Area	10 sf	100 sf	500 sf
	Negative Zone 1	-36.7	-29.9	-25.1
	Negative Zone 2	-57.6	-48.0	-41.3
	Negative Zone 3	-78.5	-66.2	-57.6
	Positive Zones 1-3	10.0	10.0	10.0

Wall	Surface Pressure (psf)		
Area	20 sf	100 sf	500 sf
Negative Zone 4	-25.1	-22.8	-20.4
Negative Zone 5	-46.0	-36.7	-27.4
Positive Zone 4 & 5			
0 to 15'	24.3	20.9	17.6
18 ft	25.1	21.6	18.1

Parapet	Solid Parapet Pressure (psf)		
Area	10 sf	100 sf	500 sf
CASE A: Interior zone	0.0	0.0	0.0
Corner zone	0.0	0.0	0.0
CASE B: Interior zone	0.0	0.0	0.0
Corner zone	0.0	0.0	0.0

# **Building Frame Analysis**

CIC – RA 5-9; Ft. Stewart, Georgia



		Date: 10	)-Apr-2012
Subject:	CIC Detachment 5-9 - Ft. Stewart GA	Checked by	:
	Ruilding Frame Analysis	Date:	

Page:

Made by:

of

Corwith, Travis

173133C

#### Loads:

The loads given below are a summary of the loads calculated within the  $\it code\ search\ spreadsheet$ . Designed in accordance with IBC 2006/ ASCE 7-05

### **Live Loads**

20.0 psf Roof Live Load

### **Dead Loads**

141.8 psf Roof Self Weight and Superimposed Dead Load

### **Seismic Loads**

Equivalent Lateral Force Method is Permitted

C SDC

0.020hsx Allowable drift0.1010W Design Base shear

#### **Wind Loads**

	Main Wine	d Force Resist	ing System	
		Wind Surface Pressure		
Zone	Transvers	e Direction	Longitudin	al Direction
1	13.47 psf	5.11 psf	13.47 psf	5.11 psf
2	-11.84 psf	-20.21 psf	-11.84 psf	-20.21 psf
3	-4.41 psf	-12.77 psf	-4.41 psf	-12.77 psf
4	-2.55 psf	-10.92 psf	-2.55 psf	-10.92 psf
5	-6.27 psf	-14.63 psf	-6.27 psf	-14.63 psf
6	-6.27 psf	-14.63 psf	-6.27 psf	-14.63 psf
1E	18.35 psf	9.99 psf	18.35 psf	9.99 psf
2E	-20.67 psf	-29.03 psf	-20.67 psf	-29.03 psf
3E	-8.13 psf	-16.49 psf	-8.13 psf	-16.49 psf
4E	-5.81 psf	-14.17 psf	-5.81 psf	-14.17 psf

6.13 ft Dimension a

Zone diagrams follow


# PARSONS BRINCKERHOFF

Subject: CIC Detachment 5-9 - Ft. Stewart GA

**Building Frame Analysis** 

Page:	of	173133C
Made by	y: Corwith, Travis	
Date:	10-Apr-2012	
Checked	l by:	
Date:		

### **Main Wind Force Resisting System Zones**



### Strength Design Load Combinations for member size design

16-2 
$$1.2(D) + 1.6(L) + 0.5(Lr \text{ or S})$$

16-4 
$$1.2(D) + 1.6(W) + L + 0.5(Lr \text{ or S})$$

Roof live load controls over snow load. The "S" Load will be omitted

Allowable Stress Design load combinations are used for footing size check and building deflection checks.

The above load combinations are plugged into the analysis model and used to check the design of the structure



BRING	KERHOFF	Widde by. Corwitti, Itavis
		Date: 10-Apr-2012
Subject:	CIC Detachment 5-9 - Ft. Stewart GA	Checked by:
	Load Calc. for RISA Input	Date:

173133C

Corwith Travis

### **Roof Gravity Load:**

Auto Structural Dead Load (Self Weight)

141.8 psf SI DL \*Note: The SI-DL includes an allowance for the joist and steel deck weight which are not

20.0 psf RLL included in the self weight for the RISA model

#### Seismic Load:

14.50 ft Eave Ht

7.25 ft Wall half Height

10.0 psf Wall Weight (CFS studs, wall board, stucco, and paint)

72.5 plf Load around perimeter

1453.5 plf DL (exterior Beam - Lines A, D) 2894.8 plf DL (Interior Beam - Lines B, C) 205.0 plf LL (exterior Beam - Lines A, D) 408.3 plf LL (Interior Beam - Lines B, C)

### **Building Dimensions:**

161.67 ft Length

61.33 ft Width

9,915 ft<sup>2</sup> Area

445.99 ft Perimeter

14.50 ft Eave Elevation

18.00 ft Average Roof Elevation

### **Total Seismic Loading:**

80.00 k Superstructure Self Weight (From RISA)

1405.95 k SI DL Weight (used to calculate seismic load)

32.33 k Wall Weight

1518.28 k Sum of Seismic Dead Load0.1010W Seismic Base Shear Factor

153.42 k Seismic Load (applied at eave elevation as approximate center of mass of the roof level)

Since the diaphragm is rigid, the inherent torsion and accidental torsion (ASCE 7-05 12.8.4.1-12.8.4.3) shall be considered; the geometric location of the applied seismic load will be adjusted to include these effects

In accordance with ASCE 7-05 12.5.3 seismic loading shall follow the orthogonal combination procedure.

## PARSONS BRINCKERHOFF

Subject:	CIC Detachment 5-9 - Ft. Stewart GA
----------	-------------------------------------

Load Calc. for RISA Input


Page:	of	173133C
Made by	: Corwith, Travis	
Date:	10-Apr-2012	
Checked	by:	
Date:		

#### Wind Load

1 The vertical component of the wind load is considered negligible compared to the superimposed dead load and is omitted

### Transverse Wind Loading (Zone 1 + 4; Longitudinal Case)

i alloverse v	villa Lodding (Lone 1 , 4) Longitualian case)
61.33 ft	Width
7.25 ft	Height (Wall only)
6.13 ft	Edge Length
12.27 ft	Edge Width
49.06 ft	Non-Edge Width
24.2 psf	Edge Load (Sum of each face)
16.0 psf	Non-Edge Load (Sum of each face)
89 ft <sup>2</sup>	Edge Area
356 ft <sup>2</sup>	Non-Edge Area
7.85 k	Total Transverse Wind Load
61.33 ft	Building Transverse Width



Longitudinal Wind Loading (Zone 1 + 4; Transverse Case)

Uniform Load applied at the eave normal to Grid 1 or 9

161.67 ft Width

0.13 klf

7.25 ft Height (Wall only)

6.13 ft Edge Length

12.27 ft Edge Width

149.40 ft Non-Edge Width

24.2 psf Edge Load (Sum of each face)

16.0 psf Non-Edge Load (Sum of each face)

89 ft<sup>2</sup> Edge Area

1,083 ft<sup>2</sup> Non-Edge Area

19.51 k Total Longitudinal Wind Load

161.67 ft Building Longitudinal Width

0.12 klf Uniform Load applied at the eave normal to Grid A or D

# **RISA Model**

CIC – RA 5-9; Ft. Stewart, Georgia

May 23, 2012 2:00 PM Checked By:\_ : Parsons Brinckerhoff: Paul Oh: 173133C Company Designer Job Number CIC Det 5-9

# Global

Display Sections for Member Calcs	10
Max Internal Sections for Member Calcs	100
Include Shear Deformation	Yes
Include Warping	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Vertical Axis	Z
Global Member Orientation Plane	XY
Global Welliber Offentation Flame	XI

Hot Rolled Steel Code	AISC 13th(360-05): LRFD (Direct Analysis	Method)
Cold Formed Steel Code	AISI NAS-07: ASD	
Wood Code	AF&PA NDS-05/08: ASD	
Wood Temperature	< 100F	
Concrete Code	ACI 318-05	
Masonry Code	ACI 530-05/08: ASD	
Aluminum Code	AA ADM1-05: ASD	

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parme Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections	Yes
Bad Framing Warnings	No
Unused Force Warnings	Yes

	,
Seismic Code	ASCE 7-05
Seismic Base Elevation (ft)	Not Entered
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
TZ (sec)	Not Entered
RX	3
RZ	3
Ct Exp. X	.75
Ct Exp. Z	.75
Ca	.36
Cv	.54
Nv	1
SD1	1
SDS	1
S1	1
TL (sec)	Not Entered
Occupancy Code	4
Seismic Zone	3
Occupancy Cat	I or II
Use Gravity Self Wt in Diaphragm Mass	Yes
Use Deck Self Wt in Diaphragm Mass	Yes
Use Lateral Self Wt in Diaphragm Mass	Yes
Seismic Detailing Code	None
Om X	2
Om Z	2
Rho X	1
Rho Z	1

Company : Parsons Bri Designer : Paul Oh Job Number : 173133C CIC Det 5-9 Checked By:

## Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (\1E	.Density[k/ft	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1

### Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Туре	Design List	Material	Design Rules
1	M5	N58	N57			W24X62	Beam	Wide Flange	A992	Typical
2	M6	N57	N56			W24X62	Beam	Wide Flange	A992	Typical
3	M7	N56	N55			W24X62	Beam	Wide Flange	A992	Typical
4	M8	N54	N53			W24X62	Beam	Wide Flange	A992	Typical
5	M9	N53	N52			W24X62	Beam	Wide Flange	A992	Typical
6	M10	N52	N51			W24X62	Beam	Wide Flange	A992	Typical
7	M11	N50	N49			W24X62	Beam	Wide Flange	A992	Typical
8	M12	N49	N48			W24X62	Beam	Wide Flange		Typical
9	M13	N48	N47			W24X62	Beam	Wide Flange		Typical
10	M14	N46	N45			W24X62	Beam	Wide Flange		Typical
11	M15	N45	N44			W24X62	Beam	Wide Flange		Typical
12	M16	N44	N43			W24X62	Beam	Wide Flange	A992	Typical
13	M17	N42	N41			W24X62	Beam	Wide Flange	A992	Typical
14	M18	N41	N40			W24X62	Beam	Wide Flange		Typical
15	M19	N40	N39			W24X62	Beam	Wide Flange		Typical
16	M20	N38	N37			W24X62	Beam	Wide Flange		Typical
17	M21	N37	N36			W24X62	Beam	Wide Flange	A992	Typical
18	M22	N36	N35			W24X62	Beam	Wide Flange		Typical
19	M23	N34	N33			W24X62	Beam	Wide Flange		Typical
20	M24	N33	N32			W24X62	Beam	Wide Flange		Typical
21	M25	N32	N31			W24X62	Beam	Wide Flange		Typical
22	M26	N4	N34			HSS6X6X4	Column		A500 Gr.46	Typical
23	M27	N3	N33			HSS6X6X4	Column		A500 Gr.46	Typical
24	M28	N2	N32			HSS6X6X4			A500 Gr.46	
25	M29	N1	N31			HSS6X6X4			A500 Gr.46	
26	M30	N8	N38			HSS6X6X4			A500 Gr.46	
27	M31	N7	N37				Column		A500 Gr.46	Typical
28	M32	N6	N36				Column		A500 Gr.46	
		N5							A500 Gr.46	7 0
29	M33		N35			HSS6X6X4			A500 Gr.46	. /
30	M34	N12	N42			HSS6X6X4			A500 Gr.46	7 5 1 5 5 1
31	M35	N11	N41			HSS6X6X4			A500 Gr.46	. , ,
32	M36	N10	N40				Column		A500 Gr.46	Typical
33	M37	N9	N39			HSS6X6X4	Column			Typical
34	M38	N16	N46			HSS6X6X4			A500 Gr.46	7
35	M39	N15	N45			HSS6X6X4			A500 Gr.46	7 10 1 0 0 11
36	M40	N14	N44			HSS6X6X4			A500 Gr.46	/
37	M41	N13	N43				Column		A500 Gr.46	. /  0
38	M42	N20	N50				Column		A500 Gr.46	J 1
39	M43	N19	N49						A500 Gr.46	. /
40	M44	N18	N48			HSS6X6X4			A500 Gr.46	- 7   0.00.
41	<u>M45</u>	N17	N47			HSS6X6X4			A500 Gr.46	Typical
42	M46	N21	N51			HSS6X6X4			A500 Gr.46	
43	M47	N22	N52			HSS6X6X4			A500 Gr.46	. , ,
44	M48	N23	N53			HSS6X6X4			A500 Gr.46	7
45	M49	N24	N54			HSS6X6X4			A500 Gr.46	7 10 1 0 0 11
46	M50	N28	N58			HSS6X6X4			A500 Gr.46	. ,
47	M51	N27	N57			HSS6X6X4	Column	Tube	A500 Gr.46	Typical

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

# Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
48	M52	N26	N56			HSS6X6X4	Column		A500 Gr.46	Typical
49	M53	N25	N55			HSS6X6X4	Column	Tube	A500 Gr.46	Typical
50	M54	N4	N63			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
51	M55	N63	N8			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
52	M56	N2	N33			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
53	M57	N5	N64			HSS6X6X4	<b>VBrace</b>	Tube	A500 Gr.46	Typical
54	M58	N9	N64			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
55	M59	N15	N46			HSS6X6X4	<b>VBrace</b>	Tube	A500 Gr.46	Typical
56	M60	N27	N53			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
57	M61	N26	N52			HSS6X6X4	<b>VBrace</b>	Tube	A500 Gr.46	Typical
58	M62	N25	N56			HSS6X6X4	VBrace	Tube	A500 Gr.46	Typical
59	M59A	N31	N35			W24X62	Beam	Wide Flange	A992	Typical
60	M60A	N35	N39			W24X62	Beam	Wide Flange		Typical
61	M61A	N39	N43			W24X62	Beam	Wide Flange	A992	Typical
62	M62A	N43	N47			W24X62	Beam	Wide Flange		Typical
63	M63	N47	N51			W24X62	Beam	Wide Flange		Typical
64	M64	N51	N55			W24X62	Beam	Wide Flange		Typical
65	M65	N32	N36			W24X84	Beam	Wide Flange		Typical
66	M66	N36	N40			W24X62	Beam	Wide Flange		Typical
67	M67	N40	N44			W24X62	Beam	Wide Flange		Typical
68	M68	N44	N48			W24X62	Beam	Wide Flange		Typical
69	M69	N48	N52			W24X62	Beam	Wide Flange		Typical
70	M70	N52	N56			W24X62	Beam	Wide Flange		Typical
71	M71	N33	N37			W24X84	Beam	Wide Flange		Typical
72	M72	N37	N41			W24X62	Beam	Wide Flange		Typical
73	M73	N41	N45			W24X62	Beam	Wide Flange		Typical
74	M74	N45	N49			W24X62	Beam	Wide Flange		Typical
75	M75	N49	N53			W24X62	Beam	Wide Flange		Typical
76	M76	N53	N57			W24X62	Beam	Wide Flange		Typical
77	M77	N34	N38			W24X62	Beam	Wide Flange		Typical
78	M78	N38	N42			W24X62	Beam	Wide Flange		Typical
79	M79	N42	N46			W24X62	Beam	Wide Flange		Typical
80	M80	N46	N50			W24X62	Beam	Wide Flange		Typical
81	M81	N50	N54			W24X62	Beam	Wide Flange		Typical
82	M82	N54	N58			W24X62	Beam	Wide Flange		Typical

## **Member Advanced Data**

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	TOM	Inactive	Seismic Design
1	M5	BenPIN	BenPIN				Yes			None
2	M6	BenPIN	BenPIN				Yes			None
3	M7	BenPIN	BenPIN				Yes			None
4	M8	BenPIN	BenPIN				Yes			None
5	M9	BenPIN	BenPIN				Yes			None
6	M10	BenPIN	BenPIN				Yes			None
7	M11	BenPIN	BenPIN				Yes			None
8	M12	BenPIN	BenPIN				Yes			None
9	M13	BenPIN	BenPIN				Yes			None
10	M14	BenPIN	BenPIN				Yes			None
11	M15	BenPIN	BenPIN				Yes			None
12	M16	BenPIN	BenPIN				Yes			None
13	M17	BenPIN	BenPIN				Yes			None
14	M18	BenPIN	BenPIN				Yes			None
15	M19	BenPIN	BenPIN				Yes			None
16	M20	BenPIN	BenPIN				Yes			None
17	M21	BenPIN	BenPIN				Yes			None
18	M22	BenPIN	BenPIN				Yes			None

Company : Parsons Bri Designer : Paul Oh Job Number : 173133C CIC Det 5-9 Checked By:

### **Member Advanced Data (Continued)**

19	Label M23	I Release BenPIN	J Release BenPIN	I Offset[in]	J Offset[in]	T/C Only	Physical Yes	TOM	Inactive	Seismic Design None
20	M24	BenPIN	BenPIN				Yes			None
21	M25	BenPIN	BenPIN				Yes			None
22	M26	DCIII IIV	DCIII IIV				Yes			None
23	M27						Yes			None
24	M28						Yes			None
25	M29						Yes			None
26	M30						Yes			None
27	M31						Yes			None
28	M32						Yes			None
29	M33						Yes			None
30	M34						Yes			None
31	M35						Yes			None
32	M36						Yes			None
33	M37						Yes			None
34	M38						Yes			None
35	M39						Yes			None
36	M40						Yes			None
37	M41						Yes			None
38	M42						Yes			None
39	M43						Yes			None
40	M44						Yes			None
41	M45						Yes			None
42	M46						Yes			None
43	M47						Yes			None
44	M48						Yes			None
45	M49						Yes			None
46	M50						Yes			None
47	M51						Yes			None
48	M52						Yes			None
49	M53						Yes			None
50	M54	BenPIN	AIIPIN				Yes			None
51	M55	BenPIN	AliPIN				Yes			None
52	M56	BenPIN	AllPIN				Yes			None
53	M57	BenPIN	AliPIN				Yes			None
54	M58	BenPIN	AliPIN				Yes			None
55	M59	BenPIN	AliPiN				Yes			None
56	M60	BenPIN	AliPIN				Yes			None
57	M61	BenPIN	AliPIN				Yes			None
58	M62	BenPIN	AliPIN				Yes			None
59	M59A	BenPIN	BenPIN				Yes			None
60	M60A	BenPIN	BenPIN				Yes			None
61	M61A	BenPIN	BenPIN				Yes			None
62	M62A	BenPIN	BenPIN				Yes			None
63	M63	BenPIN	BenPIN				Yes			None
64	M64	BenPIN	BenPIN				Yes			None
65	M65	BenPIN	BenPIN				Yes			None
66	M66	BenPIN	BenPIN				Yes			None
67	M67	BenPIN	BenPIN				Yes			None
68	M68	BenPIN	BenPIN				Yes			None
69	M69	BenPIN	BenPIN				Yes			None
70	M70	BenPIN	BenPIN				Yes			None
71	M71	BenPIN	BenPIN				Yes			None
72	M72	BenPIN	BenPIN				Yes			None
73	M73	BenPIN	BenPIN				Yes			None
74	M74	BenPIN	BenPIN				Yes			None
75	M75	BenPIN	BenPIN				Yes			None

Company Designer Job Number : Parsons Brinckerhoff: Paul Oh May 23, 2012 2:00 PM

: 173133C CIC Det 5-9 Checked By:

# Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	TOM	Inactive	Seismic Design
76	M76	BenPIN	BenPIN				Yes			None
77	M77	BenPIN	BenPIN				Yes			None
78	M78	BenPIN	BenPIN				Yes			None
79	M79	BenPIN	BenPIN				Yes			None
80	M80	BenPIN	BenPIN				Yes			None
81	M81	BenPIN	BenPIN				Yes			None
82	M82	BenPIN	BenPIN				Yes			None

**Joint Coordinates and Temperatures** 

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap
1	N1	0	0	0	0	·
2	N2	20.5	0	0	0	
3	N3	40.83	0	0	0	
4	N4	61.33	0	0	0	
5	N5	0	30	0	0	
6	N6	20.5	30	0	0	
7	N7	40.83	30	0	0	
8	N8	61.33	30	0	0	
9	N9	0	52.83	0	0	
10	N10	20.5	52.83	0	0	
11	N11	40.83	52.83	0	0	
12	N12	61.33	52.83	0	0	
13	N13	0	75.67	0	0	
14	N14	20.5	75.67	0	0	
15	N15	40.83	75.67	0	0	
16	N16	61.33	75.67	0	0	
17	N17	0	98.5	0	0	
18	N18	20.5	98.5	0	0	
19	N19	40.83	98.5	0	0	
20	N20	61.33	98.5	0	0	
21	N21	0	121.33	0	0	
22	N22	20.5	121.33	0	0	
23	N23	40.83	121.33	0	0	
24	N24	61.33	121.33	0	0	
25	N25	0	143.33	0	0	
26	N26	20.5	143.33	0	0	
27	N27	40.83	143.33	0	0	
28	N28	61.33	143.33	0	0	
29	N31	01.33	0	14.5	0	
30	N32	20.5	0	14.5	0	
31	N33	40.83	0	14.5	0	
32			0			
	N34	61.33		14.5	0	
33	N35	20.5	30	14.5	0	
34	N36		30	14.5	0	
35	N37	40.83	30	14.5	0	
36	N38	61.33	30	14.5	0	
37	N39	0	52.83	14.5	0	
38	N40	20.5	52.83	14.5	0	
39	N41	40.83	52.83	14.5	0	
40	N42	61.33	52.83	14.5	0	
41	N43	0	75.67	14.5	0	
42	N44	20.5	75.67	14.5	0	
43	N45	40.83	75.67	14.5	0	
44	N46	61.33	75.67	14.5	0	
45	N47	0	98.5	14.5	0	
46	N48	20.5	98.5	14.5	0	

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

## Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap
47	N49	40.83	98.5	14.5	0	
48	N50	61.33	98.5	14.5	0	
49	N51	0	121.33	14.5	0	
50	N52	20.5	121.33	14.5	0	
51	N53	40.83	121.33	14.5	0	
52	N54	61.33	121.33	14.5	0	
53	N55	0	143.33	14.5	0	
54	N56	20.5	143.33	14.5	0	
55	N57	40.83	143.33	14.5	0	
56	N58	61.33	143.33	14.5	0	
57	N63	61.33	15	14.5	0	
58	N64	0	41.42	14.5	0	
59	N1000	30.67	75.17	14.5	0	
60	N1001	32.17	71.67	14.5	0	

# Hot Rolled Steel Design Parameters

11001	tonca	oteer Design i	urumct	<u> </u>										
	Label		Lbyy[ft]	Lbzz[ft]	Lcomp to	Lcomp b	Kyy	Kzz	Cm-yy	Cm-zz	Cb	y sway	z sway	Function
1	M5	W24X62 20.5			3									Lateral
2	M6	W24X62 20.33			3									Lateral
3	M7	W24X62 20.5			3									Lateral
4	M8	W24X62 20.5			3									Lateral
5	M9	W24X62 20.33			3									Lateral
6	M10	W24X62 20.5			3									Lateral
7	M11	W24X62 20.5			3									Lateral
8	M12	W24X62 20.33			3									Lateral
9	M13	W24X62 20.5			3									Lateral
10	M14	W24X62 20.5			3									Lateral
11	M15	W24X62 20.33			3									Lateral
12	M16	W24X62 20.5			3									Lateral
13	M17	W24X62 20.5			3									Lateral
14	M18	W24X62 20.33			3									Lateral
15	M19	W24X62 20.5			3									Lateral
16	M20	W24X62 20.5			3									Lateral
17	M21	W24X62 20.33			3									Lateral
18	M22	W24X62 20.5			3									Lateral
19	M23	W24X62 20.5			3									Lateral
20	M24	W24X62 20.33			3									Lateral
21	M25	W24X62 20.5			3									Lateral
22	M26	HSS6X6 14.5												Lateral
23	M27	HSS6X6 14.5												Lateral
24	M28	HSS6X6 14.5												Lateral
25	M29	HSS6X6 14.5												Lateral
26	M30	HSS6X6 14.5												Lateral
27	M31	HSS6X6 14.5												Lateral
28	M32	HSS6X6 14.5												Lateral
29	M33	HSS6X6 14.5												Lateral
30	M34	HSS6X6 14.5												Lateral
31	M35	HSS6X6 14.5												Lateral
32	M36	HSS6X6 14.5												Lateral
33	M37	HSS6X6 14.5												Lateral
34	M38	HSS6X6 14.5												Lateral
35	M39	HSS6X6 14.5												Lateral
36	M40	HSS6X6 14.5												Lateral
37	M41	HSS6X6 14.5												Lateral
38	M42	HSS6X6 14.5												Lateral
39	M43	HSS6X6 14.5												Lateral

: Parsons Brinckerhoff May 23, 2012 2:00 PM Company Designer : Paul Oh

Job Number : 173133C CIC Det 5-9 Checked By:

### Hot Rolled Steel Design Parameters (Continued)

	Label	Shape	Lenath	. Lbvv[ft]	Lbzz[ft]	Lcomp to	Lcomp b	Kvv	Kzz	Cm-vv	Cm-zz	Cb	v swav	z sway Function
40	M44	HSS6X6												Lateral
41	M45	HSS6X6												Lateral
42	M46	HSS6X6												Lateral
43	M47	HSS6X6												Lateral
44	M48	HSS6X6	14.5											Lateral
45	M49	HSS6X6												Lateral
46	M50	HSS6X6												Lateral
47	M51	HSS6X6	14.5											Lateral
48	M52	HSS6X6												Lateral
49	M53	HSS6X6												Lateral
50	M54	HSS6X6												Lateral
51	M55	HSS6X6	20.863											Lateral
52	M56	HSS6X6	24.971											Lateral
53	M57	HSS6X6	18.457											Lateral
54	M58	HSS6X6	18.451											Lateral
55	M59	HSS6X6	25.11											Lateral
56	M60	HSS6X6												Lateral
57	M61	HSS6X6	26.349											Lateral
58	M62	HSS6X6	25.11											Lateral
59	M59A	W24X62				3								Lateral
60	M60A	W24X62	22.83			3								Lateral
61	M61A	W24X62				3								Lateral
62	M62A	W24X62	22.83			3								Lateral
63	M63	W24X62	22.83			3								Lateral
64	M64	W24X62				3								Lateral
65	M65	W24X84				3								Lateral
66	M66	W24X62	22.83			3								Lateral
67	M67	W24X62	22.84			3								Lateral
68	M68	W24X62	22.83			3								Lateral
69	M69	W24X62				3								Lateral
70	M70	W24X62	22			3								Lateral
71	M71	W24X84				3								Lateral
72	M72	W24X62	22.83			3								Lateral
73	M73	W24X62				3								Lateral
74	M74	W24X62	22.83			3								Lateral
75	M75	W24X62				3								Lateral
76	M76	W24X62				3								Lateral
77	M77	W24X62				3								Lateral
78	M78	W24X62	22.83			3								Lateral
79	M79	W24X62				3								Lateral
80	M80	W24X62	22.83			3								Lateral
81	M81	W24X62				3								Lateral
82	M82	W24X62	22			3								Lateral

Joint Loads and Enforced Displacements (BLC 6 : Seismic Trans)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/f
1	N1001	L	Υ	153.42

# Joint Loads and Enforced Displacements (BLC 7: Seismic Long)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/f
1	N1000	L	X	153.42

Company: Parsons BrinckerhoffMay 23, 2012Designer: Paul Oh2:00 PMJob Number: 173133CCIC Det 5-9Checked By:\_

Member Distributed Loads (BLC 2 : Roof Live)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft	End Location[ft,
1	M59A	Z	205	205	0	0
2	M60A	Z	205	205	0	0
3	M61A	Z	205	205	0	0
4	M62A	Z	205	205	0	0
5	M63	Z	205	205	0	0
6	M64	Z	205	205	0	0
7	M77	Ζ	205	205	0	0
8	M78	Z	205	205	0	0
9	M79	Z	205	205	0	0
10	M80	Z	205	205	0	0
11	M81	Z	205	205	0	0
12	M82	Z	205	205	0	0
13	M65	Z	408	408	0	0
14	M66	Z	408	408	0	0
15	M67	Z	408	408	0	0
16	M68	Z	408	408	0	0
17	M69	Z	408	408	0	0
18	M70	Z	408	408	0	0
19	M76	Z	408	408	0	0
20	M75	Z	408	408	0	0
21	M74	Z	408	408	0	0
22	M73	Z	408	408	0	0
23	M71	Z	408	408	0	0
24	M72	Z	408	408	0	0

# Member Distributed Loads (BLC 3 : Superimposed DL)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft	End Location[ft,
1	M59A	Z	-1.454	-1.454	0	0
2	M60A	Z	-1.454	-1.454	0	0
3	M61A	Z	-1.454	-1.454	0	0
4	M62A	Z	-1.454	-1.454	0	0
5	M63	Z	-1.454	-1.454	0	0
6	M64	Z	-1.454	-1.454	0	0
7	M77	Z	-1.454	-1.454	0	0
8	M78	Z	-1.454	-1.454	0	0
9	M79	Z	-1.454	-1.454	0	0
10	M80	Z	-1.454	-1.454	0	0
11	M81	Z	-1.454	-1.454	0	0
12	M82	Z	-1.454	-1.454	0	0
13	M65	Z	-2.895	-2.895	0	0
14	M66	Z	-2.895	-2.895	0	0
15	M67	Z	-2.895	-2.895	0	0
16	M68	Z	-2.895	-2.895	0	0
17	M69	Z	-2.895	-2.895	0	0
18	M70	Z	-2.895	-2.895	0	0
19	M76	Z	-2.895	-2.895	0	0
20	M75	Z	-2.895	-2.895	0	0
21	M74	Z	-2.895	-2.895	0	0
22	M73	Z	-2.895	-2.895	0	0
23	M72	Z	-2.895	-2.895	0	0
24	M71	Z	-2.895	-2.895	0	0

# Member Distributed Loads (BLC 4: Wind Trans)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft	.End Location[ft,
1	M25	Υ	.13	.13	0	0
2	M24	Υ	.13	.13	0	0

Company Designer : Parsons Brinckerhoff May 23, 2012 2:00 PM : Paul Oh

Job Number : 173133C CIC Det 5-9 Checked By:

# Member Distributed Loads (BLC 4: Wind Trans) (Continued)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft	.End Location[ft,
3	M23	Υ	.13	.13	0	0

### Member Distributed Loads (BLC 5: Wind Long)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft	.End Location[ft,
1	M59A	X	.12	.12	0	0
2	M60A	X	.12	.12	0	0
3	M61A	X	.12	.12	0	0
4	M62A	X	.12	.12	0	0
5	M63	X	.12	.12	0	0
6	M64	X	.12	.12	0	0

### **Basic Load Cases**

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(M	Surface
1	Self Weight	DĹ			-1				,	
2	Roof Live	RLL						24		
3	Superimposed DL	DL						24		
4	Wind Trans	WL						3		
5	Wind Long	WL						6		
6	Seismic Trans	EL				1				
7	Seismic Long	EL				1				

### **Load Combinations**


	Description	Sol	PDelta	SRSSBL	C Fact	orBLC	Facto	rBLC	Factor	BLC	Factor	rBLC	Facto	rBLC	Facto	rBLC	Factor	rBLC	Factor
1	LRFD 16-1	Yes	Υ	D	_ 1.4														
2	LRFD 16-2	Yes	Υ	D	_ 1.2	RLL	.5												
3	LRFD 16-3a	Yes	Υ	D	_ 1.2	RLL	1.6	4	.8										
4	LRFD 16-3b	Yes	Υ	D	_ 1.2	RLL	1.6	5	.8										
5	LRFD 16-4a	Yes	Υ	D	_ 1.2	4	1.6	RLL	.5										
6	LRFD 16-4b	Yes	Υ	D	_ 1.2	5	1.6	RLL	.5										
7	LRFD 16-5a	Yes	Υ	D	_ 1.2	6	1												
8	LRFD 16-5b	Yes	Υ	D	_ 1.2	7	1												
9	LRFD 16-6a	Yes	Υ	D	_   .9	4	1.6												
10	LRFD 16-6b	Yes	Υ	D	.9	5	1.6												
11	LRFD 16-7a	Yes	Υ	D	9	6	1												
12	LRFD 16-7b	Yes	Υ	D	9	7	1												
13	ASD 16-10	Yes		D	_ 1	RLL	1												
14	ASD 16-12a.1	Yes		D	_ 1	4	1												
15	ASD 16-12a.2	Yes		D	_ 1	5	1												
16	ASD 16- 12b.1	Yes		D	_ 1	6	.7												
17	ASD 16-12b.2	Yes		D	_ 1	7	.7												
18	ASD 16-13a.1	Yes		D	_ 1	6	.525	RLL	.75										
19	ASD 16-13a.2	Yes		D	_ 1	7	.525	RLL	.75										
20	ASD 16-13b.1	Yes		D	_ 1	4	.75	RLL	.75										
21	ASD 16-13b.2	Yes		D	_ 1	5	.75	RLL	.75										
22	ASD 16-14a	Yes		D	.6	4	1												
23	ASD 16-14b	Yes		D	_   .6	5	1												
24	ASD 16-15a	Yes		D	6	6	.7												
25	ASD 16-15b	Yes		D	.6	7	.7												
26	Self Weight	Yes	Υ	1	1														
27	Roof Live	Yes	Υ	2	1														
28	Superimposed Dead	Yes	Υ	3	1														
29	Wind Trans	Yes	Υ	4	1														
30	Wind Long	Yes	Υ	5	1														
31	Seismic Trans	Yes	Υ	6	1														


May 23, 2012 2:00 PM : Parsons Brinckerhoff : Paul Oh


Company Designer Job Number : 173133C CIC Det 5-9 Checked By:


# **Load Combinations (Continued)**


	Description	Sol	.PDelta	SRSS	BLC	Factor	BLC	Factor	<u>BLC</u>	Factor	BLC	<u>Factor</u>								
32	Seismic Long	Yes	Υ		7	1														
























# Drift and Member Size Check


CIC – RA 5-9; Ft. Stewart, Georgia

## Maximum Gravity Sample




# AISC 13th(360-05): LRFD Code Check Direct Analysis Method

Location		0.566 14.848 ft H1-1b		Max S Location Max D	on		0.187 (y) 0 ft L/257	
_	ending Flange Compact ending Web Compact			Compr Compr		Non-Slender Slender	Qs=1 Qa=1	
Fy phi*Pnc phi*Pnt phi*Mny phi*Mnz phi*Vny phi*Vnz	50 ksi 164.553 k 1111.5 k 122.25 k-f 840 k-ft 339.81 k 375.052 k	ť	Lb KL/r Sway L Comp Torque I	_	3 ft NC	z-z 30 ft 36.752 No		
Cb	1		Tau_b		1			



# AISC 13th(360-05): LRFD Code Check Direct Analysis Method


Max Bendi Location Equation	ing Check	0.656 0 ft H1-1a		Location	hear Check on efl Ratio	0.000 (y) 0 ft L/10000
Bending F Bending W		Compact Compact			ression Flange ression Web	Non-Slender Non-Slender
Fy phi*Pnc phi*Pnt phi*Mny phi*Mnz	46 ksi 149.039 k 216.297 k 38.625 k-fi 38.625 k-fi		Lb KL/r Sway	y-y 14.5 ft 74.409 No	z-z 14.5 ft 74.409 No	
phi*Vny phi*Vnz phi*Tn Cb	61.247 k 61.247 k 31.918 k-fi		L Comp Torque L Tau_b	_	14.5 ft NC 1	



# AISC 13th(360-05): LRFD Code Check Direct Analysis Method

Direct	ilalysis wieli	iou				
Location	Max Bending Check Location 10.747 ft Equation H1-1a			Location	hear Check on efl Ratio	0.003 (y) 0 ft L/3173
Bending Bending		Compact Compact			ression Flange ression Web	Non-Slender Non-Slender
Fy phi*Pnc phi*Pnt phi*Mny phi*Mnz phi*Vny phi*Vnz phi*Tn Cb	38.625 k- 61.247 k	ft ft	Lb KL/r Sway L Comp Torque I Tau_b	_	z-z t 20.863 f 107.06 No 20.863 ft NC 1	t

# **Deflection Check Example**




AISC 13th(360-05): LRFD Code Check Direct Analysis Method

- P-Delta analysis required for all AISC 360-05 Load Combinations -

Max Defl Ratio L/321 Deflection is ok

#### **Deflection Check Example**



Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC         Member         Shape         UC Max         Loc[ft]         Shear UC         Loc[ft]         Dir phi*Pnc[k]         phi*Pnt[k]         phi*Mnyphi*Mnz           1         1         M5         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           2         1         M6         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           3         1         M7         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           4         1         M8         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           5         1         M9         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         8	Cb Eqn  1 H1-1b  1 H1-1b
3         1         M7         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           4         1         M8         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           5         1         M9         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.	1 H1-1b
3         1         M7         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           4         1         M8         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           5         1         M9         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.	1 H1-1b 1 H1-1b
4         1         M8         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           5         1         M9         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y	1 H1-1b
5         1         M9         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.146         .003         20.5         y <t< td=""><td>1 H1-1b 1 H1-1b</td></t<>	1 H1-1b
6         1         M10         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           12         1         M16         W24X62         .008         10.146         .003         20.5         y	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
7         1         M11         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           8         1         M12         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           12         1         M16         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           13         1         M17         W24X62         .008         10.062         .003         20.5         y	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
8         1         M12         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           12         1         M16         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           13         1         M17         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           14         1         M18         W24X62         .008         10.062         .003         20.5         y	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
9         1         M13         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           12         1         M16         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           13         1         M17         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           14         1         M18         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           15         1         M19         W24X62         .008         10.146         .003         20.5         y	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
10         1         M14         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           11         1         M15         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           12         1         M16         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           13         1         M17         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           14         1         M18         W24X62         .008         10.062         .003         20.33         y         130.955         819         58.807         573.75           15         1         M19         W24X62         .008         10.146         .003         20.5         y         128.792         819         58.807         573.75           16         1         M20         W24X62         .008         10.146         .003         20.5         y	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
11       1       M15       W24X62       .008       10.062       .003       20.33       y       130.955       819       58.807       573.75         12       1       M16       W24X62       .008       10.146       .003       20.5       y       128.792       819       58.807       573.75         13       1       M17       W24X62       .008       10.146       .003       20.5       y       128.792       819       58.807       573.75         14       1       M18       W24X62       .008       10.062       .003       20.33       y       130.955       819       58.807       573.75         15       1       M19       W24X62       .008       10.146       .003       20.5       y       128.792       819       58.807       573.75         16       1       M20       W24X62       .008       10.146       .003       20.5       y       128.792       819       58.807       573.75         17       1       M21       W24X62       .008       10.062       .003       20.33       y       130.955       819       58.807       573.75	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
12     1     M16     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       13     1     M17     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       14     1     M18     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75       15     1     M19     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       16     1     M20     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       17     1     M21     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75	1 H1-1b 1 H1-1b 1 H1-1b 1 H1-1b
13     1     M17     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       14     1     M18     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75       15     1     M19     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       16     1     M20     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       17     1     M21     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75	1 H1-1b 1 H1-1b 1 H1-1b
14     1     M18     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75       15     1     M19     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       16     1     M20     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       17     1     M21     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75	1 H1-1b 1 H1-1b
15     1     M19     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       16     1     M20     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       17     1     M21     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75	1 H1-1b
16     1     M20     W24X62     .008     10.146     .003     20.5     y     128.792     819     58.807     573.75       17     1     M21     W24X62     .008     10.062     .003     20.33     y     130.955     819     58.807     573.75	1 1 1 1 1 1
17 1 M21 W24X62 .008 10.062 .003 20.33 y 130.955 819 58.807 573.75	
	1 H1-1b
	1 H1-1b
19 1 M23 W24X62 .008 10.146 .003 20.5 y 128.792 819 58.807 573.75	1 H1-1b
20 1 M24 W24X62 .008 10.062 .003 20.33 y 130.955 819 58.807 573.75	1 H1-1b
21 1 M25 W24X62 .008 10.146 .003 20.5 y 128.792 819 58.807 573.75	1 H1-1b
22 1 M26 HSS6X6X4 .047 0 .000 0 z 149.039 216.297 38.625 38.625	1.678 H1-1b
23 1 M27 HSS6X6X4 .434 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
24 1 M28 HSS6X6X4 .434 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
25 1 M29 HSS6X6X4 .222 0 .000 0 z 149.039 216.297 38.625 38.625	1.678 H1-1a
26 1 M30 HSS6X6X4 .256 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
27 1 M31 HSS6X6X4 .751 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
28 1 M32 HSS6X6X4 .751 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
29 1 M33 HSS6X6X4 .281 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
30 1 M34 HSS6X6X4 .333 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
31 1 M35 HSS6X6X4 .649 0 .000 0 y 149.039 216.297 38.625 38.625	1 H1-1a
32 1 M36 HSS6X6X4 .649 0 .000 0 y 149.039 216.297 38.625 38.625	1 H1-1a
33 1 M37 HSS6X6X4 .230 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
34 1 M38 HSS6X6X4 .341 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
35 1 M39 HSS6X6X4 .649 0 .000 0 y 149.039 216.297 38.625 38.625	1 H1-1a
36 1 M40 HSS6X6X4 .649 0 .000 0 y 149.039 216.297 38.625 38.625	1 H1-1a
37 1 M41 HSS6X6X4 .333 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
38 1 M42 HSS6X6X4 .333 0 .000 0 y 149.039 216.297 38.625 38.625	1.678 H1-1a
39   1   M43   HSS6X6X4   .648   0   .000   0   y   149.039   216.297   38.625   38.625	1 H1-1a
40   1   M44   HSS6X6X4   .648   0   .000   0   y   149.039   216.297   38.625   38.625	1 H1-1a
41 1 M45 HSS6X6X4 .333 0 .000 0 y 149.039 216.297 38.625 38.625	
42 1 M46 HSS6X6X4 .327 0 .000 0 y 149.039 216.297 38.625 38.625	
43 1 M47 HSS6X6X4 .580 0 .000 0 y 149.039 216.297 38.625 38.625	1 H1-1a
44   1   M48   HSS6X6X4   .578   0   .000   0   y   149.039   216.297   38.625   38.625	1 H1-1a
45 1 M49 HSS6X6X4 .327 0 .000 0 y 149.039 216.297 38.625 38.625	
46 1 M50 HSS6X6X4 .082 0 .000 0 z 149.039 216.297 38.625 38.625	
47 1 M51 HSS6X6X4 .320 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
48 1 M52 HSS6X6X4 .321 0 .000 0 z 149.039 216.297 38.625 38.625	1 H1-1a
49 1 M53 HSS6X6X4 .082 0 .000 0 z 149.039 216.297 38.625 38.625	1.678 H1-1b
50 1 M54 HSS6X6X4 .394 10.115 .003 20.863 y 100.047 216.297 38.625 38.625	
51 1 M55 HSS6X6X4 .118 10.537 .003 0 y 100.047 216.297 38.625 38.625	
52   1   M56   HSS6X6X4   .045   12.359   .004   24.971   y   71.878   216.297   38.625   38.625	
53   1   M57   HSS6X6X4   .281   8.762   .002   18.457   y   118.296   216.297   38.625   38.625	1.14 H1-1a
54 1 M58 HSS6X6X4 .053 8.946 .002 0 y 118.344 216.297 38.625 38.625	1.14 H1-1b
55 1 M59 HSS6X6X4 .045 12.682 .004 25.11 y 71.087 216.297 38.625 38.625	
56   1   M60   HSS6X6X4   .300   12.775   .004   0   y   64.559   216.297   38.625   38.625	

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Eqn
57	1	M61	HSS6X6X4	.290	12.775	.004	26.349	У	64.559	216.297	38.625	38.625		H1-1a
58	1	M62	HSS6X6X4	.043	12.428	.004	25.11	٧	71.087	216.297	38.625	38.625	1.14	H1-1b
59	1	M59A	W24X62	.416	14.848	.104	0	y	60.139	819	58.807	573.75	1	H1-1b
60	1	M60A	W24X62	.161	11.53	.050	11.53	У	103.845	819	58.807	227.459	1.38	H1-1b
61	1	M61A	W24X62	.241	11.535	.079	22.84	У	103.754	819	58.807	573.75	1	H1-1b
62	1	M62A	W24X62	.241	11.53	.079	22.83	У	103.845	819	58.807	573.75	1	H1-1b
63	1	M63	W24X62	.241	11.53	.079	22.83	У	103.845	819	58.807	573.75	1	H1-1b
64	1	M64	W24X62	.224	10.889	.076	0	٧	111.828	819	58.807	573.75	1	H1-1b
65	1	M65	W24X84	.558	14.848	.184	0	ý	164.553	1111.5	122.25	840	1	H1-1b
66	1	M66	W24X62	.470	11.3	.154	22.83	У	103.845	819	58.807	573.75	1	H1-1b
67	1	M67	W24X62	.470	11.305	.154	22.84	У	103.754	819	58.807	573.75	1	H1-1b
68	1	M68	W24X62	.470	11.3	.154	22.83	У	103.845	819	58.807	573.75	1	H1-1b
69	1	M69	W24X62	.470	11.3	.154	22.83	٧	103.845	819	58.807	573.75	1	H1-1b
70	1	M70	W24X62	.436	10.889	.149	0	У	111.828	819	58.807	573.75	1	H1-1b
71	1	M71	W24X84	.558	14.848	.184	0	У	164.553	1111.5	122.25	840	1	H1-1b
72	1	M72	W24X62	.470	11.3	.154	22.83	У	103.845	819	58.807	573.75	1	H1-1b
73	1	M73	W24X62	.470	11.305	.154	22.84	У	103.754	819	58.807	573.75	1	H1-1b
74	1	M74	W24X62	.470	11.3	.154	22.83	У	103.845	819	58.807	573.75	1	H1-1b
75	1	M75	W24X62	.470	11.3	.154	22.83	У	103.845	819	58.807	573.75	1	H1-1b
76	1	M76	W24X62	.436	10.889	.149	0	У	111.828	819	58.807	573.75	1	H1-1b
_ 77	1	M77	W24X62	.362	14.848	.061	15.152	У	60.139	819	58.807	123.18	1.099	H1-1b
78	1	M78	W24X62	.241	11.53	.079	22.83	У	103.845	819	58.807	573.75	1	H1-1b
79	1	<u>M79</u>	W24X62	.241	11.535	.079	22.84	٧	103.754	819	58.807	573.75	1	H1-1b
80	1	M80	W24X62	.241	11.53	.079	22.83	У	103.845	819	58.807	573.75	1	H1-1b
81	1	M81	W24X62	.241	11.53	.079	22.83	У	103.845	819	58.807	573.75	1	H1-1b
82	1	M82	W24X62	.224	10.889	.076	0	У	111.828	819	58.807	573.75	1	H1-1b
83	2	M5	W24X62	.007	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
84	2	<u>M6</u>	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
85	2	<u>M7</u>	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
86	2	<u>M8</u>	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
87	2	M9	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
88	2	M10	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
89	2	M11	W24X62	.007	10.354	.002	20.5	V	128.792 130.955	819	58.807	573.75 573.75	1	H1-1b
90	2	M12	W24X62	.007	10.002	.002	20.5	У		819 819	58.807	573.75	1	H1-1b
92		M13	W24X62 W24X62	.007	10.354			У	128.792 128.792		58.807 58.807		1	H1-1b
93	2	M14 M15	W24X62	.007	10.062	.002	20.5	y V		819 819	58.807	573.75 573.75	1	H1-1b
94	2	M16	W24X62	.007	10.354	.002	20.5	V	130.955 128.792	819	58.807	573.75	1	H1-1b
95	2	M17	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
96	2	M18	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
97	2	M19	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
98	2	M20	W24X62	.007	10.354	.002	20.5	У		819	58.807	573.75	1	H1-1b
99	2	M21	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
100	2	M22	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
101	2	M23	W24X62	.007	10.146	.002	20.5	y	128.792	819	58.807	573.75	1	H1-1b
102		M24	W24X62	.007	10.062	.002	20.33			819	58.807	573.75	1	H1-1b
103		M25	W24X62	.007	10.354	.002	20.5	y		819	58.807	573.75	1	H1-1b
104		M26	HSS6X6X4	.042	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
105		M27	HSS6X6X4	.392	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
106		M28	HSS6X6X4	.393	0	.000	0	z		216.297	38.625	38.625	1	H1-1a
107	2	M29	HSS6X6X4	.201	0	.000	0	z	149.039	216.297	38.625			
108		M30	HSS6X6X4	.232	0	.000	0	У	149.039	216.297				
109		M31	HSS6X6X4	.680	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
110		M32	HSS6X6X4	.680	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
111	2	M33	HSS6X6X4	.254	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
112		M34	HSS6X6X4	.302	0	.000	0	ý		216.297		38.625		
113		M35	HSS6X6X4	.587	0	.000	0	ý		216.297		38.625	1	H1-1a
								-						

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Locifti	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mnv	. phi*Mnz	Cb	Egn
114	2	M36	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
115	2	M37	HSS6X6X4	.208	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
116	2	M38	HSS6X6X4	.308	0	.000	0	٧	149.039	216.297	38.625	38.625	1.678	H1-1a
117	2	M39	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
118	2	M40	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
119	2	M41	HSS6X6X4	.302	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
120	2	M42	HSS6X6X4	.301	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
121	2	M43	HSS6X6X4	.587	0	.000	0	y	149.039	216.297	38.625	38.625	1	H1-1a
122	2	M44	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
123	2	M45	HSS6X6X4	.301	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
124	2	M46	HSS6X6X4	.296	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
125	2	M47	HSS6X6X4	.525	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
126	2	M48	HSS6X6X4	.523	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
127	2	M49	HSS6X6X4	.296	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
128	2	M50	HSS6X6X4	.074	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
129	2	M51	HSS6X6X4	.289	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
130	2	M52	HSS6X6X4	.290	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
131	2	M53	HSS6X6X4	.074	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
132	2	M54	HSS6X6X4	.355	10.115	.003	0	У	100.047	216.297	38.625	38.625	1.14	H1-1a
133	2	M55	HSS6X6X4	.105	10.537	.003	0	У	100.047	216.297	38.625	38.625	1.14	H1-1b
134	2	M56	HSS6X6X4	.039	12.359	.004	24.971	У	71.878	216.297	38.625	38.625	1.14	H1-1b
135	2	M57	HSS6X6X4	.253	8.762	.002	18.457	У	118.296	216.297	38.625	38.625	1.14	H1-1a
136	2	M58	HSS6X6X4	.047	8.946	.002	0	У	118.344	216.297	38.625	38.625	1.14	H1-1b
137	2	M59	HSS6X6X4	.038	12.682	.004	25.11	ý	71.087	216.297	38.625	38.625	1.14	H1-1b
138	2	M60	HSS6X6X4	.269	12.775	.004	0	У	64.559	216.297	38.625	38.625	1.14	H1-1a
139	2	M61	HSS6X6X4	.260	12.775	.004	26.349	У	64.559	216.297	38.625	38.625	1.14	H1-1a
140	2	M62	HSS6X6X4	.037	12.428	.004	25.11	У	71.087	216.297	38.625	38.625	1.14	H1-1b
141	2	M59A	W24X62	.377	15.152	.094	0	У	60.139	819	58.807	573.75	1	H1-1b
142	2	M60A	W24X62	.145	11.53	.045	11.53	У	103.845	819	58.807	227.392	1.38	H1-1b
143	2	M61A	W24X62	.218	11.305	.072	22.84	У	103.754	819	58.807	573.75	11	H1-1b
144	2	M62A	W24X62	.218	11.53	.072	22.83	У	103.845	819	58.807	573.75	1	H1-1b
145	2	M63	W24X62	.218	11.53	.072	22.83	У	103.845	819	58.807	573.75	11	H1-1b
146	2	M64	W24X62	.203	10.889	.069	0	У	111.828	819	58.807	573.75	1	H1-1b
147	2	M65	W24X84	.506	14.848	.167	0	У	164.553	1111.5	122.25	840	1	H1-1b
148	2	M66	W24X62	.426	11.3	.140	22.83	У	103.845	819	58.807	573.75	1	H1-1b
149	2	M67	W24X62	.426	11.305	.140	22.84	У	103.754	819	58.807	573.75	1	H1-1b
150	2	M68	W24X62	.426	11.3	.140	22.83	У	103.845	819	58.807	573.75	1	H1-1b
151	2	M69	W24X62	.426	11.3	.140	22.83	У	103.845	819	58.807	573.75	1	H1-1b
152	2	M70	W24X62	.396	11.111	.135	0	У	111.828	819	58.807	573.75	1	H1-1b
153	2	<u>M71</u>	W24X84	.506	14.848	.167	0	У	164.553	1111.5	122.25	840	1	H1-1b
154		M72	W24X62	.426	11.3	.140	22.83			819	58.807			H1-1b
155		<u>M73</u>	W24X62	.426	11.305	.140	22.84			819	58.807		1	H1-1b
156		M74	W24X62	.426	11.3	.140	22.83			819	58.807	573.75	1	H1-1b
157	2	<u>M75</u>	W24X62	.426	11.3	.140	22.83		103.845	819	58.807	573.75	1	H1-1b
158	2	M76	W24X62	.396	11.111	.135	0	У	111.828	819	58.807	573.75	1	H1-1b
159	2	<u> M77</u>	W24X62	.328	14.848	.055	15.152	У	60.139	819		123.171		
160	2	M78	W24X62	.218	11.53	.072	22.83			819	58.807			H1-1b
161	2	M79	W24X62	.218	11.305	.072	22.84		103.754	819	58.807	573.75	1	H1-1b
162	2	M80	W24X62	.218	11.53	.072	22.83			819	58.807	573.75		H1-1b
163	2	<u>M81</u>	W24X62	.218	11.53	.072	22.83			819	58.807	573.75	1	H1-1b
164	2	M82	W24X62	.203	10.889	.069	0	У		819	58.807		1	H1-1b
165		M5	W24X62	.007	10.146	.002	20.5	٧		819	58.807		1	H1-1b
166		<u>M6</u>	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
167	3	<u>M7</u>	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
168	3	M8	W24X62	.007	10.354	.002	20.5	У		819	58.807	573.75	1	H1-1b
169	3	<u>M9</u>	W24X62	.007	10.062	.002	20.33			819	58.807		1	H1-1b
170	3	M10	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Eqn
171	3	M11	W24X62	.007	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
172	3	M12	W24X62	.007	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
173	3	M13	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
174	3	M14	W24X62	.007	10.146	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
175	3	M15	W24X62	.007	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
176	3	M16	W24X62	.007	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
177	3	M17	W24X62	.007	10.146	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
178	3	M18	W24X62	.007	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
179	3	M19	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
180	3	M20	W24X62	.007	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
181	3	M21	W24X62	.007	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
182	3	M22	W24X62	.007	10.146	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
183	3	M23	W24X62	.100	10.146	.005	20.5	z	128.792	819	58.807	573.75	1	H1-1b
184	3	M24	W24X62	.098	10.268	.005	20.33	Z	130.955	819	58.807	573.75	1	H1-1b
185	3	M25	W24X62	.100	10.146	.005	20.5	z	128.792	819	58.807	573.75	1	H1-1b
186	3	M26	HSS6X6X4	.047	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
187	3	M27	HSS6X6X4	.437	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
188	3	M28	HSS6X6X4	.438	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
189	3	M29	HSS6X6X4	.223	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1a
190	3	M30	HSS6X6X4	.258	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
191	3	M31	HSS6X6X4	.760	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
192	3	M32	HSS6X6X4	.760	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
193	3	M33	HSS6X6X4	.283	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
194	3	M34	HSS6X6X4	.336	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
195	3	M35	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
196	3	M36	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
197	3	M37	HSS6X6X4	.231	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
198	3	M38	HSS6X6X4	.343	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
199	3	M39	HSS6X6X4	.656	0	.000	0	y	149.039	216.297	38.625	38.625	1	H1-1a
200	3	M40	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
201	3	M41	HSS6X6X4	.336	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
202	3	M42	HSS6X6X4	.336	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
203	3	M43	HSS6X6X4	.656	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1a
204	3	M44	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
205	3	M45	HSS6X6X4	.336	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
206	3	M46	HSS6X6X4	.330	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
207	3	M47	HSS6X6X4	.581	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
208	3	M48	HSS6X6X4	.579	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
209	3	M49	HSS6X6X4	.330	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	
210	3	M50	HSS6X6X4	.083	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
211		M51	HSS6X6X4	.322	0	.000	0	z	149.039	216.297	38.625		1	H1-1a
212		M52	HSS6X6X4	.324	0	.000	0	Z	149.039	216.297	38.625		1	H1-1a
213	3	M53	HSS6X6X4	.083	0	.000	0	Z	149.039	216.297	38.625	38.625		
214		M54	HSS6X6X4	.379	10.115	.003	20.863	У		216.297	38.625	38.625		H1-1a
215	3	M55	HSS6X6X4	.221	10.747	.003	20.863	У		216.297	38.625	38.625		
216	3	M56	HSS6X6X4	.039	12.359	.004	24.971	У		216.297		38.625		
217	3	M57	HSS6X6X4	.268	8.762	.002	0	У	118.296	216.297	38.625			
218		M58	HSS6X6X4	.058	8.946	.002	0	У	118.344	216.297	38.625	38.625		
219		M59	HSS6X6X4	.039	12.682	.004	25.11		71.087	216.297	38.625			
220	3	M60	HSS6X6X4	.316	12.775	.004	0	У	64.559	216.297				
221	3	M61	HSS6X6X4	.307	12.775	.004	0	٧	64.559	216.297		38.625		
222	3	M62	HSS6X6X4	.036	12.428	.004	25.11	У	71.087	216.297		38.625	1.14	
223	3	M59A	W24X62	.421	14.848	.105	0	٧	60.139	819	58.807	573.75	1	H1-1b
224		M60A	W24X62	.162	11.53	.050	11.53		103.845	819		227.267		
225	3	M61A	W24X62	.244	11.305	.080	22.84			819	58.807	573.75	1	H1-1b
226	3	M62A	W24X62	.244	11.3	.080	22.83			819	58.807	573.75	1	H1-1b
227	3	M63	W24X62	.244	11.3	.080	22.83	У	103.845	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
228	3	M64	W24X62	.226	10.889	.077	0	٧	111.828	819	58.807	573.75	1	H1-1b
229	3	M65	W24X84	.566	14.848	.187	0	V	164.553	1111.5	122.25	840	1	H1-1b
230	3	M66	W24X62	.477	11.3	.157	22.83	v	103.845	819	58.807	573.75	1	H1-1b
231	3	M67	W24X62	.477	11.305	.157	22.84	v	103.754	819	58.807	573.75	1	H1-1b
232	3	M68	W24X62	.477	11.3	.157	22.83	V	103.845	819	58.807	573.75	1	H1-1b
233	3	M69	W24X62	.477	11.3	.157	22.83	v	103.845	819	58.807	573.75	1	H1-1b
234	3	M70	W24X62	.443	10.889	.151	0	v	111.828	819	58.807	573.75	1	H1-1b
235	3	M71	W24X84	.566	14.848	.187	0	v	164.553	1111.5	122.25	840	1	H1-1b
236	3	M72	W24X62	.477	11.3	.157	22.83	V	103.845	819	58.807	573.75	1	H1-1b
237	3	M73	W24X62	.477	11.305	.157	22.84	V	103.754	819	58.807	573.75	1	H1-1b
238	3	M74	W24X62	.477	11.3	.157	22.83	V	103.845	819	58.807	573.75	1	H1-1b
239	3	M75	W24X62	.477	11.3	.157	22.83	V	103.845	819	58.807	573.75	1	H1-1b
240	3	M76	W24X62	.443	10.889	.151	0	V	111.828	819	58.807	573.75	1	H1-1b
241	3	M77	W24X62	.366	14.848	.062	15.152	V	60.139	819	58.807	123.15	1.099	H1-1b
242	3	M78	W24X62	.244	11.3	.080	22.83	V	103.845	819	58.807	573.75	1	H1-1b
243	3	M79	W24X62	.244	11.305	.080	22.84	V	103.754	819	58.807	573.75	1	H1-1b
244	3	M80	W24X62	.244	11.3	.080	22.83	V	103.845	819	58.807	573.75	1	H1-1b
245	3	M81	W24X62	.244	11.3	.080	22.83	V	103.845	819	58.807	573.75	1	H1-1b
246	3	M82	W24X62	.226	10.889	.077	0	V	111.828	819	58.807	573.75	1	H1-1b
247	4	M5	W24X62	.007	10.146	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
248	4	M6	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
249	4	M7	W24X62	.007	10.354	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
250	4	M8	W24X62	.007	10.354	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
251	4	M9	W24X62	.007	10.062	.003	20.33	V	130.955	819	58.807	573.75	1	H1-1b
252	4	M10	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
253	4	M11	W24X62	.007	10.146	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
254	4	M12	W24X62	.007	10.062	.003	20.33	У	130.955	819	58.807	573.75	1	H1-1b
255	4	M13	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
256	4	M14	W24X62	.007	10.354	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
257	4	M15	W24X62	.007	10.062	.003	20.33	V	130.955	819	58.807	573.75	1	H1-1b
258	4	M16	W24X62	.007	10.354	.002	20.55	V	128.792	819	58.807	573.75	1	H1-1b
259	4	M17	W24X62	.007	10.146	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
260	4	M18	W24X62	.007	10.062	.003	20.33	V	130.955	819	58.807	573.75	1	H1-1b
261	4	M19	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
262	4	M20	W24X62	.007	10.354	.003	20.5	V	128.792	819	58.807	573.75	1	H1-1b
263	4	M21	W24X62	.007	10.062	.003	20.33	V	130.955	819	58.807	573.75	1	H1-1b
264	4	M22	W24X62	.007	10.146	.002	20.5		128.792	819	58.807	573.75	1	H1-1b
265	4	M23	W24X62	.007	10.354	.003	20.5	y v	128.792	819	58.807	573.75	1	H1-1b
266	4	M24	W24X62	.007	10.062	.003	20.33	V	130.955	819	58.807	573.75	1	H1-1b
267	4	M25	W24X62	.007	10.354	.002	20.5	_	128.792	819	58.807	573.75	1	H1-1b
			HSS6X6X4				_	У -		216.297				
268 269	4	<u>M26</u> M27	HSS6X6X4	.047 .460	0	.000	0	Z	149.039 149.039		38.625	38.625 38.625		
270		M28	HSS6X6X4	.438	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a H1-1a
271	4	M29	HSS6X6X4	.223		.000	_	Z	149.039	216.297 216.297	38.625	38.625	-	H1-1a
272	4	M30	HSS6X6X4	.258	0	.000	0	Z V	149.039	216.297	38.625 38.625	38.625		
273		M31	HSS6X6X4					_		216.297				
	4		HSS6X6X4	.760	0	.000	0	Z	149.039		38.625		1	H1-1a
274		M32 M33	HSS6X6X4	.760	0	.000	0	Z		216.297		38.625	1 678	H1-1a
275			HSS6X6X4	.283	0	.000	0	V	149.039 149.039	216.297	38.625	38.625		H1-1a H1-1a
276 277	4	M34 M35	HSS6X6X4	.336	0	.000	0	У		216.297	38.625	38.625		
		M35 M36	HSS6X6X4	.656	0		0	У	149.039	216.297	38.625	38.625	1	H1-1a
278	4	M36	HSS6X6X4	.656	0	.000	0	У	149.039	216.297		38.625	1 678	H1-1a
279	4	M37	HSS6X6X4	.231	0	.000	0	V	149.039	216.297	38.625			
280		M38 M30	HSS6X6X4	.366	0	.000	0	У	149.039	216.297	38.625	38.625		
281	4	M39	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
282		M40	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625 38.625		H1-1a
283		M41	HSS6X6X4	.336	0	.000	0	У	149.039	216.297				
284	4	M42	173307074	.336	0	.000	0	У	149.039	216.297	30.025	38.625	1.078	ni-la

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Eqn
285 4	M43	HSS6X6X4	.656	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
286 4	M44	HSS6X6X4	.656	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1a
287 4	M45	HSS6X6X4	.336	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
288 4	M46	HSS6X6X4	.330	0	.000	0	٧	149.039	216.297	38.625	38.625	1.678	H1-1a
289 4	M47	HSS6X6X4	.586	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1a
290 4	M48	HSS6X6X4	.584	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
291 4	M49	HSS6X6X4	.330	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
292 4	M50	HSS6X6X4	.083	0	.000	0	z	149.039	216.297	38.625	38.625		H1-1b
293 4	M51	HSS6X6X4	.322	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
294 4	M52	HSS6X6X4	.345	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
295 4	M53	HSS6X6X4	.083	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
296 4	M54	HSS6X6X4	.394	10.115	.003	0	٧	100.047	216.297	38.625	38.625		H1-1a
297 4	M55	HSS6X6X4	.115	10.537	.003	0	V	100.047	216.297	38.625	38.625	1.14	
298 4	M56	HSS6X6X4	.047	12.612	.003	24.971	V	71.878	216.297	38.625	38.625		H1-1b
299 4	M57	HSS6X6X4	.282	8.762	.002	18.457	V	118.296	216.297	38.625	38.625		H1-1a
		HSS6X6X4											
	M58	HSS6X6X4	.050	8.946 12.682	.002	0	У	71.097	216.297	38.625	38.625		H1-1b
301 4	M59	HSS6X6X4	.052	12.775	.004	26.349	V	71.087	216.297	38.625	38.625		H1-1b
302 4	M60	HSS6X6X4	.297	12.775	.004	26.349	У	64.559	216.297	38.625	38.625		H1-1a
303 4	M61	HSS6X6X4	.286	12.775	.004		У	64.559	216.297	38.625	38.625		H1-1a
304 4	M62		.048		.004	25.11	У	71.087	216.297	38.625	38.625		H1-1b
305 4	M59A	W24X62	.604	14.848	.105	0	У	60.139	819	58.807	573.75	1 270	H1-1b
306 4	M60A	W24X62	.188	11.53	.050	11.53	У	103.845	819	58.807	227.267		
307 4	M61A	W24X62	.350	11.305	.080	22.84	V	103.754	819	58.807	573.75	1	H1-1b
308 4	M62A	W24X62	.350	11.3	.080	22.83	У	103.845	819	58.807	573.75	1	H1-1b
309 4	M63	W24X62	.350	11.3	.080	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
310 4	M64	W24X62	.325	10.889	.077	0	У	111.828	819	58.807	573.75	1	H1-1b
311 4	M65	W24X84	.566	14.848	.187	0	У	164.553	<u>1111.5</u>	122.25	840	1	H1-1b
312 4	M66	W24X62	.477	11.3	.157	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
313 4	M67	W24X62	.477	11.305	.157	22.84	У	103.754	819	58.807	573.75	1	H1-1b
314 4	M68	W24X62	.477	11.3	.157	22.83	У	103.845	819	58.807	573.75	1	H1-1b
315 4	M69	W24X62	.477	11.3	.157	22.83	У	103.845	819	58.807	573.75	1	H1-1b
316 4	M70	W24X62	.443	10.889	.151	0	У	111.828	819	58.807	573.75	1	H1-1b
317 4	M71	W24X84	.566	14.848	.187	0	V	164.553	1111.5	122.25	840	1	H1-1b
318 4	M72	W24X62	.477	11.3	.157	22.83	У	103.845	819	58.807	573.75	1	H1-1b
319 4	M73	W24X62	.477	11.305	.157	22.84	У	103.754	<u>819</u>	58.807	573.75	1	H1-1b
320 4	M74	W24X62	.477	11.3	.157	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
321 4	M75	W24X62	.477	11.3	.157	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
322 4	M76	W24X62	.443	10.889	.151	0	У	111.828	819	58.807	573.75	1	H1-1b
323 4	M77	W24X62	.366	14.848	.062	15.152	У	60.139	<u>819</u>	58.807	123.15		
324 4	M78	W24X62	.244	11.3	.080	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
325 4	M79	W24X62	.244	11.305	.080	22.84			<u>819</u>	58.807			H1-1b
326 4	M80	W24X62	.244	11.3	.080	22.83		103.845	<u>819</u>	58.807			H1-1b
327 4	M81	W24X62	.244	11.3	.080	22.83		103.845	<u>819</u>	58.807		1	H1-1b
328 4	M82	W24X62	.226	10.889	.077	0	У	111.828	819	58.807		1	H1-1b
329 5	M5	W24X62	.007	10.146	.002	20.5	У	128.792	<u>819</u>	58.807		1	H1-1b
330 5	M6	W24X62	.007	10.062	.002	20.33	_	130.955	819	58.807			H1-1b
331 5	M7	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807		1	H1-1b
332 5	M8	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807		1	H1-1b
333 5	M9	W24X62	.007	10.062	.002	20.33	У	130.955	<u>819</u>	58.807		1	H1-1b
334 5	M10	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807		1	H1-1b
335 5	M11	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807			H1-1b
336 5	M12	W24X62	.007	10.062	.002	20.33	_	130.955	819	58.807			H1-1b
337 5	M13	W24X62	.007	10.354	.002	20.5	٧	128.792	819	58.807		1	H1-1b
338 5	M14	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807		1	H1-1b
339 5	M15	W24X62	.007	10.062	.002	20.33	1	130.955	<u>819</u>	58.807		1	H1-1b
340 5	M16	W24X62	.007	10.354	.002	20.5	У	128.792	<u>819</u>	58.807			H1-1b
341 5	M17	W24X62	.007	10.354	.002	20.5	у	128.792	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
342	5	M18	W24X62	.007	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
343	5	M19	W24X62	.007	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
344	5	M20	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
345	5	M21	W24X62	.007	10.062	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
346	5	M22	W24X62	.007	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
347	5	M23	W24X62	.193	10.146	.010	20.5	z	128.792	819	58.807	573.75	1	H1-1b
348	5	M24	W24X62	.189	10.268	.009	20.33	z	130.955	819	58.807	573.75	1	H1-1b
349	5	M25	W24X62	.193	10.146	.010	20.5	z	128.792	819	58.807	573.75	1	H1-1b
350	5	M26	HSS6X6X4	.042	0	.000	0	Z	149.039	216.297	38.625	38.625	1.678	
351	5	M27	HSS6X6X4	.392	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
352	5	M28	HSS6X6X4	.393	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
353	5	M29	HSS6X6X4	.201	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	
354	5	M30	HSS6X6X4	.232	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
355	5	M31	HSS6X6X4	.680	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
356	5	M32	HSS6X6X4	.680	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
357	5	M33	HSS6X6X4	.254	0	.000	0	V	149.039	216.297	38.625	38.625		
358	5	M34	HSS6X6X4	.302	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
359	5	M35	HSS6X6X4	.587	0	.000	0	V	149.039	216.297	38.625	38.625	1.070	H1-1a
360	5	M36	HSS6X6X4	.587	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
361	5	M37	HSS6X6X4	.208	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
362	5	M38	HSS6X6X4	.308	0	.000	0	V	149.039	216.297	38.625	38.625		
363	5	M39	HSS6X6X4	.587	0	.000	0	V		216.297	38.625	38.625	1.070	
			HSS6X6X4	.587			0		149.039 149.039	216.297		38.625	1	H1-1a
364 365	5	M40 M41	HSS6X6X4	.302	0	.000		У	149.039	216.297	38.625	38.625	1.678	H1-1a H1-1a
			HSS6X6X4	.302	0		0	У			38.625 38.625	38.625	1.678	
366	5	M42	HSS6X6X4			.000	0	У	149.039	216.297				
367	5	M43	HSS6X6X4	.587	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
368	5	M44	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625	38.625	1 679	H1-1a
369	5	M45	HSS6X6X4	.301	0	.000	0	V	149.039	216.297	38.625	38.625	1.678 1.678	
370	5	M46	HSS6X6X4	.296	0	.000	0	У	149.039	216.297	38.625	38.625		
371	5	M47		.515	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
372	5	M48	HSS6X6X4	.513	0	.000	0	У	149.039	216.297	38.625	38.625	1 670	H1-1a
373	5	M49	HSS6X6X4	.296	0	.000	0	V	149.039	216.297	38.625	38.625		
374	5	<u>M50</u>	HSS6X6X4	.074	0	.000	0	Z	149.039	216.297	38.625	38.625	1.678	
375	5	<u>M51</u>	HSS6X6X4	.289	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
376	5	<u>M52</u>	HSS6X6X4	.291	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
377	5	<u>M53</u>	HSS6X6X4	.074	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
378	5	M54	HSS6X6X4	.324	10.115	.003	20.863	У	100.047	216.297	38.625	38.625		H1-1a
379	5	<u>M55</u>	HSS6X6X4	.209	18.123	.003	0	У	100.047	216.297	38.625	38.625	1.14	
380	5	<u>M56</u>	HSS6X6X4	.040	12.359	.004	24.971	У	71.878	216.297	38.625	38.625		H1-1b
381	5	<u> M57</u>	HSS6X6X4	.226	8.762	.002	18.457	У	118.296	216.297	38.625	38.625		H1-1a
382		<u>M58</u>	HSS6X6X4	.061	8.946	.002	0	У	118.344	216.297		38.625		
383	5	<u>M59</u>	HSS6X6X4	.038	12.682	.004	0	٧	71.087	216.297	38.625			
384		M60	HSS6X6X4	.309	12.775	.004	0	У	64.559	216.297	38.625	38.625		
385		<u>M61</u>	HSS6X6X4	.300	12.775	.004	26.349	У	64.559	216.297	38.625	38.625		
386		M62	HSS6X6X4	.036	12.428	.004	0	У	71.087	216.297		38.625		
387	5	<u>M59A</u>	W24X62	.377	15.152	.094	0	У	60.139	819	58.807	573.75	1	H1-1b
388		M60A	W24X62	.145	11.53	.045	11.53			819		227.391		
389		M61A	W24X62	.218	11.305	.072	22.84		103.754	819	58.807	573.75	1	H1-1b
390		M62A	W24X62	.218	11.53	.072	22.83			819	58.807	573.75	1	H1-1b
391	5	M63	W24X62	.218	11.53	.072	22.83			819	58.807	573.75	1	H1-1b
392		M64	W24X62	.203	10.889	.069	0	У		819	58.807	573.75	1	H1-1b
393		M65	W24X84	.506	14.848	.167	0	У	164.553	1111.5	122.25	840	1	H1-1b
394		M66	W24X62	.426	11.3	.140	22.83	У	103.845	819	58.807	573.75	1	H1-1b
395		M67	W24X62	.426	11.305	.140	22.84		103.754	819	58.807	573.75	1	H1-1b
396		M68	W24X62	.426	11.3	.140	22.83			819	58.807	573.75	1	H1-1b
397	5	M69	W24X62	.426	11.3	.140	22.83		103.845	819	58.807	573.75	1	H1-1b
398	5	M70	W24X62	.396	11.111	.135	0	У	111.828	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Locifti	Shear UC	Locfft	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
399 5	M71	W24X84	.506	14.848	.167	0	V	164.553	1111.5	122.25	840	1	H1-1b
400 5	M72	W24X62	.426	11.3	.140	22.83	٧	103.845	819	58.807	573.75	1	H1-1b
401 5	M73	W24X62	.426	11.305	.140	22.84	V	103.754	819	58.807	573.75	1	H1-1b
402 5	M74	W24X62	.426	11.3	.140	22.83	V	103.845	819	58.807	573.75	1	H1-1b
403 5	M75	W24X62	.426	11.3	.140	22.83		103.845	819	58.807	573.75	1	H1-1b
404 5	M76	W24X62	.396	11.111	.135	0	V	111.828	819	58.807	573.75	1	H1-1b
405 5	M77	W24X62	.328	14.848	.055	15.152	v	60.139	819	58.807	123.17		H1-1b
406 5	M78	W24X62	.218	11.53	.072	22.83	V	103.845	819	58.807	573.75	1	H1-1b
407 5	M79	W24X62	.218	11.305	.072	22.84		103.754	819	58.807	573.75	1	H1-1b
408 5	M80	W24X62	.218	11.53	.072	22.83	V	103.845	819	58.807	573.75	1	H1-1b
409 5	M81	W24X62	.218	11.53	.072	22.83	V	103.845	819	58.807	573.75	1	H1-1b
410 5	M82	W24X62	.203	10.889	.069	0	V	111.828	819	58.807	573.75	1	H1-1b
411 6	M5	W24X62	.007	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
412 6	M6	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
413 6	M7	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
414 6	M8	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
415 6	M9	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
416 6	M10	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
417 6	M11	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
418 6	M12	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
419 6	M13	W24X62	.007	10.354	.002	20.5	_		819	58.807	573.75	1	H1-1b
		W24X62		10.354	.002	20.5	У	128.792				1	H1-1b
420 6	M14		.007	10.334			У	128.792	819	58.807	573.75		H1-1b
421 6	M15	W24X62	.007		.002	20.33	У	130.955	819	58.807	573.75	1	
422 6	M16	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
423 6	M17	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
424 6	M18	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
425 6	M19	W24X62	.007	10.354	.002	20.5	У	128.792	<u>819</u>	58.807	573.75	1	H1-1b
426 6	M20	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
427 6	M21	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
428 6	M22	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
429 6	M23	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
430 6	M24	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
431 6	M25	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
432 6	M26	HSS6X6X4	.042	0	.000	0	Z	149.039	216.297	38.625	38.625	1.678	H1-1b
433 6	M27	HSS6X6X4	.438	0	.000	0	Z	149.039	216.297	38.625	38.625	11	H1-1a
434 6	M28	HSS6X6X4	.393	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
435 6	M29	HSS6X6X4	.201	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1a
436 6	M30	HSS6X6X4	.232	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
437 6	M31	HSS6X6X4	.680	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
438 6	M32	HSS6X6X4	.680	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
439 6	M33	HSS6X6X4	.254	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
440 6	M34	HSS6X6X4	.302	0	.000	0	У	149.039	216.297	38.625			
441 6	M35	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625			H1-1a
442 6	M36	HSS6X6X4	.587	0	.000	0	У	149.039	216.297		38.625		H1-1a
443 6	M37	HSS6X6X4	.208	0	.000	0	v	149.039	216.297	38.625			
444 6	M38	HSS6X6X4	.352	0	.000	0	у	149.039	216.297		38.625		
445 6	M39	HSS6X6X4	.587	0	.000	0	v	149.039	216.297	38.625		1	H1-1a
446 6	M40	HSS6X6X4	.587	0	.000	0	У	149.039	216.297		38.625		H1-1a
447 6	M41	HSS6X6X4	.302	0	.000	0	V	149.039	216.297	38.625			
448 6	M42	HSS6X6X4	.301	0	.000	0	V	149.039	216.297	38.625			
449 6	M43	HSS6X6X4	.587	0	.000	0	У	149.039	216.297		38.625	1	H1-1a
450 6	M44	HSS6X6X4	.587	0	.000	0	У	149.039	216.297	38.625			H1-1a
451 6	M45	HSS6X6X4	.301	0	.000	0	У	149.039	216.297	38.625			
451 6	M46	HSS6X6X4	.296	0	.000	0	V	149.039	216.297		38.625		
453 6	M47	HSS6X6X4	.525	0	.000	0	V	149.039	216.297		38.625	1.070	H1-1a
454 6	M48	HSS6X6X4	.523	0	.000	0		149.039	216.297		38.625		H1-1a
		HSS6X6X4					У						
455 6	M49	110000004	.296	0	.000	0	У	149.039	216.297	_აი.ნ∠ნ	38.625	1.070	<u>ı⊓ı-1a</u>

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

456 6   M50   HSS6KW4   289 0 . 0.00 0   0   2   149.039   216.297   38.625   38.625   1   H1-1a   458 6   M52   HSS6KW4   334   0 . 0.00 0   0   2   149.039   216.297   38.625   38.625   1   H1-1a   458 6   M52   HSS6KW4   334   0 . 0.00   0   2   149.039   216.297   38.625   38.625   1   H1-1a   469 6   M54   HSS6KW4   364   10.115   0.03   20.803   1   00.004   216.297   38.625   38.625   1   H1-1a   461 6   M55   HSS6KW4   364   10.115   0.03   20.803   1   00.004   216.297   38.625   38.625   1.4   H1-1b   462 6   M56   HSS6KW4   0.61   12.612   0.04   24.971   7   71.878   216.297   38.625   38.625   1.4   H1-1b   462 6   M56   HSS6KW4   254   8.762   0.02   18.457   118.296   216.297   38.625   38.625   1.4   H1-1b   463 6   M58   HSS6KW4   4.66   8.762   0.02   0   7   18.574   216.297   38.625   38.625   1.4   H1-1b   466 6   M60   HSS6KW4   254   12.872   0.04   22.914   7   1.087   216.297   38.625   38.625   1.4   H1-1b   466 6   M60   HSS6KW4   2.66   12.775   0.04   22.349   0.64.559   216.297   38.625   38.625   1.4   H1-1b   466 6   M60   HSS6KW4   2.60   12.775   0.04   22.349   0.64.559   216.297   38.625   38.625   1.4   H1-1b   469   6   M52   M52		LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
##   ##   ##   ##   ##   ##   ##   #	456														
469 6   M54	457	6	M51	HSS6X6X4	.289	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
ABO   6   MS4   HSSRKEWL   354   10.115   .003   20.88   y   100.047   216.297   38.625   38.625   1.14   H1-1a   ABO   6   MS5   HSSRKEWL   .061   12.612   .004   24.971   y   .71.878   .216.297   38.625   38.625   1.14   H1-1b   .462   6   MS6   HSSRKEWL   .624   .8762   .002   18.457   y   .71.878   .216.297   38.625   38.625   1.14   H1-1b   .464   6   MS6   HSSRKEWL   .046   8.946   .002   0   y   .118.344   .216.297   38.625   38.625   .114   H1-1b   .466   6   MS9   HSSRKEWL   .056   12.982   .004   .25.11   y   .71.087   .216.297   38.625   38.625   .114   H1-1b   .466   6   M60   HSSRKEWL   .056   .7275   .004   .25.11   y   .71.087   .216.297   .38.625   .38.625   .114   H1-1b   .466   6   M60   HSSRKEWL   .270   12.775   .004   .25.349   y   .64.559   .216.297   .38.625   .38.625   .114   H1-1a   .488   6   M62   HSSRKEWL   .061   12.682   .004   .25.11   y   .71.087   .216.297   .38.625   .38.625   .114   H1-1a   .488   6   M62   HSSRKEWL   .061   12.682   .004   .25.11   y   .71.087   .216.297   .38.625   .38.625   .114   H1-1a   .488   6   M62   HSSRKEWL   .061   12.682   .004   .25.11   y   .71.087   .216.297   .38.625   .38.625   .114   H1-1a   .488   .004   .005   .004	458	6	M52	HSS6X6X4	.334	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
AGE   6   MS5	459	6	M53	HSS6X6X4	.074	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
Heart   Hear	460	6	M54	HSS6X6X4	.354	10.115	.003	20.863	У	100.047	216.297	38.625	38.625	1.14	H1-1a
463   6   M57	461	6	M55	HSS6X6X4	.106	10.537	.003	0	٧	100.047	216.297	38.625	38.625	1.14	H1-1b
463 6   M57	462	6	M56	HSS6X6X4	.061	12.612	.004	24.971	٧	71.878	216.297	38.625	38.625	1.14	H1-1b
465   6   M59	463	6	M57	HSS6X6X4	.254	8.762	.002	18.457	V	118.296		38.625			H1-1a
ABG	464	6	M58		.046	8.946	.002	0	У	118.344	216.297	38.625	38.625	1.14	H1-1b
487 6   M61	465	6	M59	HSS6X6X4	.065	12.682	.004	25.11	У	71.087	216.297	38.625	38.625	1.14	H1-1b
469 6   M69A	466	6	M60	HSS6X6X4	.270	12.775	.004	26.349	У	64.559	216.297	38.625	38.625	1.14	H1-1a
469   6   M59A	467	6		HSS6X6X4	.260	12.775	.004	26.349	У	64.559	216.297	38.625	38.625	1.14	H1-1a
470         6         M60A         W24X62         .196         11.53         .045         11.53         .045         11.53         .045         11.53         .045         11.53         .072         .22.84         y         103.754         .819         .58.807         .527.375         1         .11-1b           472         6         M62A         W24X62         .431         11.53         .072         .22.83         y         103.845         .819         .58.807         .573.75         1         .11-1b           473         6         M63         W24X62         .430         11.18.3         .072         .22.83         y         103.845         .819         .58.807         .573.75         1         .11-1b         .475         6         M66         M24X62         .426         .11.3         .140         .22.83         y         103.845         .819         .58.807         .573.75         1         .11-1b         .475         6         M66         M24X62         .426         .11.3         .140         .22.83         y         103.845         .819         .58.807         .573.75         1         .11-1b         .479         .6         M68         W24X62         .426         .11.3	468	6	M62	HSS6X6X4	.061	12.682	.004	25.11	У	71.087	216.297	38.625	38.625	1.14	H1-1b
471         6         M61A         W24K62         431         11.305         072         22.84         V 103.754         819         58.807         573.75         1         H1-1b           472         6         M63         W24K62         431         11.53         .072         22.83         V 103.845         819         58.807         573.75         1         H1-1b           475         6         M64         W24K62         400         10.889         .069         0         V 114.828         819         58.807         573.75         1         H1-1b           475         6         M66         W24K62         400         10.888         .069         0         V 144.553         111.51         112.225         840         1.11           477         6         M66         W24K62         426         11.33         140         22.83         V 103.845         819         58.807         573.75         1         H1-1b           477         6         M69         W24K62         426         11.3         140         22.83         V 103.845         819         58.807         573.75         1         H1-1b           479         6         M69         W24	469	6	M59A	W24X62	.744	14.848	.094	0	У		819	58.807	573.75	<u> </u>	H1-1b
472 6         M62A         W24K62         431         11.53         072         22.83         V 103.845         819         58.807         573.75         1         H1-1b           473 6         M63         W24K62         430         10.889         .069         0         V 111.828         819         58.807         573.75         1         H1-1b           475 6         M65         W24K84         .506         14.848         .167         0         V 164.553         1111.5         122.25         840         1         H1-1b           476 6         M66         M66         W24K62         426         11.3         .140         22.83         V 103.845         819         58.807         573.75         1         H1-1b           477 6         M67         W24K62         .426         11.3         .140         22.84         V 103.754         819         58.807         573.75         1         H1-1b           479 6         M69         W24K62         .426         11.3         .140         22.83         V 103.845         819         58.807         573.75         1         H1-1b           479 6         M69         W24K62         .426         11.3         .140	470	6	M60A		.196	11.53	.045	11.53	У	103.845	819	58.807	227.392	1.38	H1-1b
473         6         M63         W/24X62         431         11.53         0.72         22.83         v         103.845         819         58.807         573.75         1         H1-1b           476         6         M65         W24X62         426         11.3         14.0         22.83         v         103.845         819         58.807         573.75         1         H1-1b           477         6         M66         W24X62         426         11.30         140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           478         6         M66         W24X62         426         11.30         140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           479         6         M69         W24X62         426         11.3         140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           481         6         M70         W24X62         426         11.3         140         22.83         v         103.845         819         58.807         573.75         1<		6	M61A			11.305	.072		У	103.754	819	58.807	573.75	1	
474         6         M64         W/24X62         400         10.889         .069         0         V         11.1828         819         58.807         573.75         1         H1-1b           476         6         M65         W24X62         .426         11.3         .140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           477         6         M67         W24X62         .426         11.30         .140         22.84         v         103.754         819         58.807         573.75         1         H1-1b           478         6         M68         W24X62         .426         11.3         .140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           478         6         M69         W24X62         .426         11.33         .140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           480         6         M70         W24X62         .426         11.3         .140         22.83         v         103.845         819         58.807         573.75	472	6		W24X62		11.53			У	103.845	819	58.807	573.75	1	H1-1b
475         6         M65         W24X84         .506         14.848         .167         0         v         164.553         1111.5         122.25         840         1         H1-1b           476         6         M66         W24X62         .426         11.3         1.40         22.83         v         103.845         819         58.807         573.75         1         H1-1b           478         6         M68         W24X62         .426         11.3         140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           479         6         M69         W24X62         .426         11.3         .140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           480         6         M70         W24X62         .236         11.31         .140         22.83         v         111.828         819         58.807         573.75         1         H1-1b           481         6         M70         W24X62         .246         11.3         .140         22.83         v         103.845         819         58.807         573.75 <t< td=""><td>473</td><td></td><td>M63</td><td>W24X62</td><td></td><td></td><td></td><td>22.83</td><td>٧</td><td>103.845</td><td></td><td></td><td></td><td>1</td><td></td></t<>	473		M63	W24X62				22.83	٧	103.845				1	
476         6         M66         W24X62         .426         11.3         140         22.84         y         103.754         819         58.807         573.75         1         H1-1b           478         6         M68         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           479         6         M69         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           480         6         M70         W24X62         .396         11111         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           481         6         M71         W24X62         .366         11.31         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           482         6         M72         W24X62         .426         11.33         .140         22.83         y         103.845         819         58.807         573.75 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td><td>У</td><td></td><td></td><td></td><td></td><td></td><td></td></t<>								0	У						
477         6         M67         W24X62         .426         11.30         .140         22.83         y         103.845         .819         58.807         573.75         1         H1-1b           479         6         M69         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           480         6         M70         W24X62         .396         11.11         135         0         y         111.82         819         58.807         573.75         1         H1-1b           481         6         M70         W24X62         .396         11.111         135         0         y         111.828         819         58.807         573.75         1         H1-1b           482         6         M72         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b         483         6         M73         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1		6	M65	W24X84			.167	_	У		1111.5			1	H1-1b
478         6         M68         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           479         6         M69         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           480         6         M71         W24X62         .366         11.111         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           482         6         M71         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           483         6         M72         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           485         6         M74         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75 <t< td=""><td>476</td><td></td><td></td><td>W24X62</td><td></td><td></td><td></td><td></td><td>У</td><td>103.845</td><td></td><td></td><td></td><td>1</td><td>H1-1b</td></t<>	476			W24X62					У	103.845				1	H1-1b
479         6         M69         W224X62         .426         11.31         .140         22.83         v         103.845         819         58.807         573.75         1         H1-1b           480         6         M70         W24X62         .396         11.111         .135         0         y         118.28         819         58.807         573.75         1         H1-1b           481         6         M72         W24X62         .426         11.305         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           483         6         M73         W24X62         .426         11.30         .140         22.84         y         103.845         819         58.807         573.75         1         H1-1b           484         6         M76         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         6         M76         W24X62         .396         11.11         .135         0         y         111.828         819         58.807         573.75         <									٧					_	
480         6         M70         W24X62         .396         11.11         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           481         6         M71         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           483         6         M73         W24X62         .426         11.30         .140         22.84         y         103.754         819         58.807         573.75         1         H1-1b           484         6         M74         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           485         6         M76         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           487         6         M76         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75									У						
481         6         M71         W24X82         .506         14.848         .167         0         v         164.553         1111.5         122.25         840         1         H1-1b           482         6         M72         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           483         6         M74         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           485         6         M75         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         M76         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75         1         H1-1b           487         6         M77         W24X62         .218         11.53         .072         .22.83         y         103.845         819         58.807         573.75         1															
482         6         M72         W24X62         .426         11.30         .140         22.84         y         103.845         819         58.807         573.75         1         H1-1b           483         6         M73         W24X62         .426         11.305         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           485         6         M75         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         6         M76         W24X62         .328         11.111         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           487         6         M76         W24X62         .238         11.153         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           488         6         M78         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75									У						
483         6         M73         W24X62         .426         11.30         .140         22.84         y         103.754         819         58.807         573.75         1         H1-1b           486         6         M74         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         6         M76         W24X62         .396         11.111         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           487         6         M77         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75         1         H1-1b           488         6         M78         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           489         6         M79         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75								_	_						
484         6         M74         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         6         M76         W24X62         .396         11.111         135         0         y         11.1828         819         58.807         573.75         1         H1-1b           487         6         M77         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75         1         H1-1b           488         6         M78         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           489         6         M79         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           490         6         M80         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75									-						
485         6         M75         W24X62         .426         11.3         .140         22.83         y         103.845         819         58.807         573.75         1         H1-1b           486         6         M76         W24X62         .396         11.111         .135         0         y         11.1828         819         58.807         573.75         1         H1-1b           487         6         M77         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75         1         H1-1b           488         6         M79         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           489         6         M79         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M82         W24X62         .203         10.889         .069         0         y         111.828         819         58.807         573.75															
486         6         M76         W24X62         .396         11.111         .135         0         y         111.828         819         58.807         573.75         1         H1-1b           487         6         M77         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         573.75         1         H1-1b           488         6         M79         W24X62         .218         11.530         .072         22.84         y         103.845         819         58.807         573.75         1         H1-1b           490         6         M80         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M80         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M81         W24X62         .203         10.889         .069         0         y         111.828         819         58.807         573.75															
487         6         M77         W24X62         .328         14.848         .055         15.152         y         60.139         819         58.807         123.171         1.099         H1-1b           488         6         M78         W24X62         .218         11.53         .072         .22.84         y         103.845         819         58.807         573.75         1         H1-1b           489         6         M79         W24X62         .218         11.305         .072         .22.84         y         103.845         819         58.807         573.75         1         H1-1b           490         6         M80         W24X62         .218         11.53         .072         .22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M81         W24X62         .203         10.889         .069         0         y         11.828         819         58.807         573.75         1         H1-1b           492         6         M82         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75 </td <td></td>															
488         6         M78         W24X62         .218         11.53         .072         .22.83         y         103.845         819         58.807         573.75         1         H1-1b           490         6         M79         W24X62         .218         11.305         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           490         6         M80         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M81         W24X62         .203         10.889         .069         0         y         111.828         819         58.807         573.75         1         H1-1b           492         6         M82         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           493         7         M6         W24X62         .007         10.062         .002         20.5         y         128.792         819         58.807         573.75									-					<u> </u>	
489         6         M79         W24X62         .218         11.305         .072         22.84         y         103.754         819         58.807         573.75         1         H1-1b           490         6         M80         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M81         W24X62         .203         10.889         .069         0         y         11.828         819         58.807         573.75         1         H1-1b           492         6         M82         W24X62         .203         10.889         .069         0         y         11.828         819         58.807         573.75         1         H1-1b           493         7         M5         W24X62         .007         10.062         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           495         7         M7         W24X62         .007         10.062         .002         20.5         y         128.792         819         58.807         573.75 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>															
490         6         M80         W24X62         .218         11.53         .072         .22.83         y         103.845         819         58.807         573.75         1         H1-1b           491         6         M81         W24X62         .218         11.53         .072         22.83         y         103.845         819         58.807         573.75         1         H1-1b           492         6         M82         W24X62         .003         10.889         .069         0         y         11.828         819         58.807         573.75         1         H1-1b           493         7         M5         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           494         7         M6         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           495         7         M7         W24X62         .007         10.46         .002         20.5         y         128.792         819         58.807         573.75									,						
491         6         M81         W24X62         .218         11.53         .072         22.83         v         103.845         819         58.807         573.75         1         H1-1b           492         6         M82         W24X62         .003         10.889         .069         0         y         111.828         819         58.807         573.75         1         H1-1b           493         7         M5         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           494         7         M6         W24X62         .007         10.354         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           496         7         M8         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75														_	
492         6         M82         W24X62         .203         10.889         .069         0         y         111.828         819         58.807         573.75         1         H1-1b           493         7         M5         W24X62         .007         10.146         .002         20.5         v         128.792         819         58.807         573.75         1         H1-1b           494         7         M6         W24X62         .007         10.354         .002         20.5         v         128.792         819         58.807         573.75         1         H1-1b           496         7         M8         W24X62         .007         10.466         .002         20.5         v         128.792         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.062         .002         20.33         v         130.955         819         58.807         573.75         1         H1-1b           498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75									_					-	
493         7         M5         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           494         7         M6         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           495         7         M7         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           496         7         M8         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75			-					_							
494         7         M6         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           495         7         M7         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           496         7         M8         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           499         7         M11         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.364         .002         20.5         y         128.792         819         58.807         573.75								_	-						
495         7         M7         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           496         7         M8         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           499         7         M11         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75		-													
496         7         M8         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           497         7         M9         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           499         7         M11         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           501         7         M13         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75		-							_						
497         7         M9         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           499         7         M11         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           501         7         M13         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           502         7         M14         W24X62         .007         10.062         .002         20.5         y         128.792         819         58.807         573.75		-												1	
498         7         M10         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           499         7         M11         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           501         7         M13         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           502         7         M14         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           503         7         M15         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75									_					1	
499         7         M11         W24X62         .007         10.354         .002         20.5         ŷ         128.792         819         58.807         573.75         1         H1-1b           500         7         M12         W24X62         .007         10.062         .002         20.33         ŷ         130.955         819         58.807         573.75         1         H1-1b           501         7         M13         W24X62         .007         10.354         .002         20.5         ŷ         128.792         819         58.807         573.75         1         H1-1b           502         7         M14         W24X62         .007         10.354         .002         20.5         ŷ         128.792         819         58.807         573.75         1         H1-1b           503         7         M15         W24X62         .007         10.354         .002         20.5         ŷ         128.792         819         58.807         573.75         1         H1-1b           504         7         M16         W24X62         .007         10.354         .002         20.5         ŷ         128.792         819         58.807         573.75															
500         7         M12         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           501         7         M13         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           502         7         M14         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           503         7         M15         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           504         7         M16         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75									-						
501         7         M13         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           502         7         M14         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           503         7         M15         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           504         7         M16         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           506         7         M18         W24X62         .007         10.062         .002         20.5         y         128.792         819         58.807         573.75															
502         7         M14         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           503         7         M15         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           504         7         M16         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           506         7         M18         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75									_						
503         7         M15         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           504         7         M16         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           506         7         M18         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75									_						
504         7         M16         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           506         7         M18         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           509         7         M21         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75									-						
505         7         M17         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           506         7         M18         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           509         7         M21         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           510         7         M22         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75															
506         7         M18         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           509         7         M21         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           510         7         M22         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           511         7         M23         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75															
507         7         M19         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           509         7         M21         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           510         7         M22         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           511         7         M23         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b															
508         7         M20         W24X62         .007         10.146         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           509         7         M21         W24X62         .007         10.062         .002         20.33         y         130.955         819         58.807         573.75         1         H1-1b           510         7         M22         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b           511         7         M23         W24X62         .007         10.354         .002         20.5         y         128.792         819         58.807         573.75         1         H1-1b									_						
509     7     M21     W24X62     .007     10.062     .002     20.33     y     130.955     819     58.807     573.75     1     H1-1b       510     7     M22     W24X62     .007     10.354     .002     20.5     y     128.792     819     58.807     573.75     1     H1-1b       511     7     M23     W24X62     .007     10.354     .002     20.5     y     128.792     819     58.807     573.75     1     H1-1b															
510     7     M22     W24X62     .007     10.354     .002     20.5     y     128.792     819     58.807     573.75     1     H1-1b       511     7     M23     W24X62     .007     10.354     .002     20.5     y     128.792     819     58.807     573.75     1     H1-1b									-					_1	
511 7 M23 W24X62 .007 10.354 .002 20.5 v 128.792 819 58.807 573.75 1 H1-1b															
									_						
			M24	W24X62		10.062					819		573.75		H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	.phi*Mnz	Cb	Eqn
513 7	M25	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
514 7	M26	HSS6X6X4	.040	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
515 7	M27	HSS6X6X4	.371	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
516 7	M28	HSS6X6X4	.372	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
517 7	M29	HSS6X6X4	.095	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
518 7	M30	HSS6X6X4	.220	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
519 7	M31	HSS6X6X4	.644	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
520 7	M32	HSS6X6X4	.644	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
521 7	M33	HSS6X6X4	.241	0	.000	0	v	149.039	216.297	38.625	38.625		H1-1a
522 7	M34	HSS6X6X4	.286	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
523 7	M35	HSS6X6X4	.556	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
524 7	M36	HSS6X6X4	.556	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
525 7	M37	HSS6X6X4	.098	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
526 7	M38	HSS6X6X4	.292	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
527 7	M39	HSS6X6X4	.556	0	.000	0	V	149.039	216.297	38.625	38.625	1.070	H1-1a
		HSS6X6X4		0								1	H1-1a
	M40	HSS6X6X4	.556	0	.000	0	У	149.039	216.297	38.625 38.625	38.625		H1-1a
	M41	HSS6X6X4	.286	0	.000	0	V	149.039	216.297		38.625 38.625		H1-1a
530 7	M42	HSS6X6X4	.286		.000	0	У	149.039	216.297	38.625			
531 7	M43	HSS6X6X4	.556	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
532 7	M44		.556	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
533 7	M45	HSS6X6X4	.286	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
534 7	M46	HSS6X6X4	.281	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
535 7	M47	HSS6X6X4	.383	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1a
536 7	M48	HSS6X6X4	.382	0	.000	0	У	149.039	216.297	38.625	38.625	1 070	H1-1a
537 7	M49	HSS6X6X4	.281	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
538 7	M50	HSS6X6X4	.071	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
539 7	M51	HSS6X6X4	.274	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
540 7	M52	HSS6X6X4	.276	0	.000	0	Z	149.039	216.297	38.625	38.625	1 070	H1-1a
541 7	M53	HSS6X6X4	.071	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
542 7	M54	HSS6X6X4	.038	10.537	.003	0	У	100.047	216.297	38.625	38.625		H1-1b
543 7	M55	HSS6X6X4	.566	10.747	.003	0	V	100.047	216.297	38.625			H1-1a
544 7	M56	HSS6X6X4	.041	12.359	.004	0	У	71.878	216.297	38.625	38.625		H1-1b
545 7	M57	HSS6X6X4	.040	9.322	.002	18.457	V	118.296	216.297	38.625	38.625	1.14	
546 7	M58	HSS6X6X4	.397	8.76	.002	0	У	118.344	216.297	38.625	38.625		H1-1a
547 7	M59	HSS6X6X4	.038	12.682	.004	25.11	У	71.087	216.297	38.625	38.625		H1-1b
548 7	M60	HSS6X6X4	.733	12.775	.004	0	У	64.559	216.297	38.625	38.625		H1-1a
549 7	M61	HSS6X6X4	.726	12.775	.004	0	У	64.559	216.297	38.625	38.625		H1-1a
550 7	M62	HSS6X6X4	.036	12.682	.004	25.11	У	71.087	216.297	38.625	38.625	1.14	1 1 1 1 1 1
551 7	M59A	W24X62	.357	14.848	.089	0	У	60.139	819	58.807	573.75	1	H1-1b
552 7	M60A	W24X62	.138	11.53	.043	11.53	У	103.845	819	58.807	227.493		H1-1b
553 7	M61A	W24X62	.207	11.535	.068	22.84			819	58.807		1	H1-1b
554 7	M62A	W24X62	.206	11.53	.068	22.83		103.845	819	58.807		1	H1-1b
555 7	M63	W24X62	.206	11.53	.068	22.83		103.845	819	58.807		1	H1-1b
556 7	M64	W24X62	.192	10.889	.065	0	У	111.828	819	58.807		1	H1-1b
557 7	M65	W24X84	.479	14.848	.158	0	У	164.553	1111.5	122.25		1	H1-1b
558 7	M66	W24X62	.403	11.3	.132	22.83		103.845	819	58.807		1	H1-1b
559 7	M67	W24X62	.403	11.305	.132	22.84		103.754	819	58.807		1	H1-1b
560 7	M68	W24X62	.403	11.3	.132	22.83		103.845	819	58.807		1	H1-1b
561 7	M69	W24X62	.403	11.3	.132	22.83		103.845	819	58.807		1	H1-1b
562 7	M70	W24X62	.374	11.111	.127	0	У	111.828	819	58.807		1	H1-1b
563 7	M71	W24X84	.479	14.848	.158	0	V	164.553	1111.5	122.25		1	H1-1b
564 7	M72	W24X62	.403	11.3	.132	22.83		103.845	819	58.807		1	H1-1b
565 7	M73	W24X62	.403	11.305	.132	22.84		103.754	819	58.807		1	H1-1b
566 7	M74	W24X62	.403	11.3	.132	22.83		103.845	819	58.807		1	H1-1b
567 7	M75	W24X62	.403	11.3	.132	22.83	1	103.845	819	58.807		1	H1-1b
568 7	M76	W24X62	.374	11.111	.127	0	У	111.828	819	58.807			H1-1b
569 7	M77	W24X62	.310	15.152	.052	15.152	у	60.139	819	58.807	123.193	1.1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

ı	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Egn
570	7	M78	W24X62	.206	11.53	.068	22.83	У	103.845	819	58.807	573.75	1	H1-1b
571	7	M79	W24X62	.207	11.535	.068	22.84	У	103.754	819	58.807	573.75	1	H1-1b
572	7	M80	W24X62	.206	11.53	.068	22.83	V	103.845	819	58.807	573.75	1	H1-1b
	7	M81	W24X62	.206	11.53	.068	22.83	v	103.845	819	58.807	573.75	1	H1-1b
	7	M82	W24X62	.192	10.889	.065	0	V	111.828	819	58.807	573.75	1	H1-1b
	8	M5	W24X62	.007	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
	8	M6	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	8	M7	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	8	M8	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	8	M9	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	8	M10	W24X62	.007	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	8	M11	W24X62	.007	10.354	.002	20.5	_	128.792	819	58.807	573.75	1	H1-1b
	8	M12	W24X62	.007	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	8		W24X62	.007	10.354	.002	20.5	У	128.792		58.807	573.75	1	H1-1b
	8	M13			10.146	.002	20.5	У	128.792	819		573.75	1	
		M14	W24X62	.007				У		819	58.807			H1-1b
	8	M15	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
	8	M16	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	M17	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	M18	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
	8	M19	W24X62	.007	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	<u>M20</u>	W24X62	.007	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	<u>M21</u>	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
	8	M22	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	M23	W24X62	.007	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
	8	M24	W24X62	.007	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
595	8	M25	W24X62	.007	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
596	8	M26	HSS6X6X4	.040	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
	8	M27	HSS6X6X4	.612	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
598	8	M28	HSS6X6X4	.372	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
599	8	M29	HSS6X6X4	.095	0	.000	0	У	149.039	216.297	38.625	38.625	11	H1-1b
600	8	M30	HSS6X6X4	.220	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
601	8	M31	HSS6X6X4	.644	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
	8	M32	HSS6X6X4	.644	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
603	8	M33	HSS6X6X4	.241	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
604	8	M34	HSS6X6X4	.286	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
605	8	M35	HSS6X6X4	.556	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
606	8	M36	HSS6X6X4	.556	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1a
	8	M37	HSS6X6X4	.098	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
	8	M38	HSS6X6X4	.539	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
	8	M39	HSS6X6X4	.556	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1a
	8	M40	HSS6X6X4	.556	0	.000	0	V	149.039	216.297		38.625	1	H1-1a
	8	M41	HSS6X6X4	.286	0	.000	0	ý	149.039	216.297	38.625		1	H1-1a
	8	M42	HSS6X6X4	.286	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
	8	M43	HSS6X6X4	.556	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
	8	M44	HSS6X6X4	.556	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
	8	M45	HSS6X6X4	.286	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
	8	M46	HSS6X6X4	.281	0	.000	0	У	149.039	216.297		38.625	1	H1-1a
	8	M47	HSS6X6X4	.496	0	.000	0	V	149.039	216.297	38.625		1	H1-1a
	8	M48	HSS6X6X4	.496	0	.000	0	У	149.039	216.297	38.625		1	H1-1a
	8	M49	HSS6X6X4	.281	0	.000	0	y	149.039	216.297	38.625		1	H1-1a
	8	M50	HSS6X6X4	.071	0	.000	0	V	149.039	216.297	38.625			H1-1b
	8	M51	HSS6X6X4	.274	0	.000	0	У	149.039	216.297	38.625		1	H1-1a
	8	M52	HSS6X6X4	.529	0	.000	0		149.039	216.297	38.625		1	H1-1a
	8	M53	HSS6X6X4	.071	0	.000	0	У	149.039	216.297	38.625		1	H1-1b
	8	M54	HSS6X6X4	.348	10.115	.003	20.863	У	100.047	216.297	38.625			
	8	M55	HSS6X6X4	.096	10.537	.003	0	V	100.047	216.297		38.625		
	8	M56	HSS6X6X4	.314	12.612	.003	24.971	V	71.878	216.297		38.625		
020	U	IVIOU	110000000	.014	12.012	.004	27.071	У	11.010	210.291	100.020	100.020	1.14	IIII-Id

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
627	8	M57	HSS6X6X4	.231	8.762	.002	18.457	У	118.296	216.297	38.625	38.625		H1-1a
628	8	M58	HSS6X6X4	.050	8.946	.002	0	V	118.344	216.297	38.625	38.625	1.14	H1-1b
629	8	M59	HSS6X6X4	.331	12.682	.004	25.11	v	71.087	216.297	38.625	38.625		H1-1a
630	8	M60	HSS6X6X4	.253	12.775	.004	26.349	٧	64.559	216.297	38.625	38.625		H1-1a
631	8	M61	HSS6X6X4	.254	12.775	.004	26.349	V	64.559	216.297	38.625	38.625		H1-1a
632	8	M62	HSS6X6X4	.334	12.682	.004	25.11	v	71.087	216.297	38.625	38.625		H1-1a
633	8	M59A	W24X62	.357	14.848	.089	0	v	60.139	819	58.807	573.75	1	H1-1b
634	8	M60A	W24X62	.139	11.53	.043	11.53	v	103.845	819	58.807	227.459	1.38	H1-1b
635	8	M61A	W24X62	.207	11.535	.068	22.84	v	103.754	819	58.807	573.75	1	H1-1b
636	8	M62A	W24X62	.206	11.53	.068	22.83	v	103.845	819	58.807	573.75	1	H1-1b
637	8	M63	W24X62	.206	11.53	.068	22.83	v	103.845	819	58.807	573.75	1	H1-1b
638	8	M64	W24X62	.192	10.889	.065	0	V	111.828	819	58.807	573.75	1	H1-1b
639	8	M65	W24X84	.479	14.848	.158	0	v	164.553	1111.5	122.25	840	1	H1-1b
640	8	M66	W24X62	.403	11.3	.132	22.83	v	103.845	819	58.807	573.75	1	H1-1b
641	8	M67	W24X62	.403	11.305	.132	22.84	v	103.754	819	58.807	573.75	1	H1-1b
642	8	M68	W24X62	.403	11.3	.132	22.83	V	103.845	819	58.807	573.75	1	H1-1b
643	8	M69	W24X62	.403	11.3	.132	22.83	V	103.845	819	58.807	573.75	1	H1-1b
644	8	M70	W24X62	.374	11.111	.127	0	٧	111.828	819	58.807	573.75	1	H1-1b
645	8	M71	W24X84	.479	14.848	.158	0	v	164.553	1111.5	122.25	840	1	H1-1b
646	8	M72	W24X62	.403	11.3	.132	22.83	v	103.845	819	58.807	573.75	1	H1-1b
647	8	M73	W24X62	.403	11.305	.132	22.84	V	103.754	819	58.807	573.75	1	H1-1b
648	8	M74	W24X62	.403	11.3	.132	22.83	V	103.845	819	58.807	573.75	1	H1-1b
649	8	M75	W24X62	.403	11.3	.132	22.83	V	103.845	819	58.807	573.75	1	H1-1b
650	8	M76	W24X62	.374	11.111	.127	0	٧	111.828	819	58.807	573.75	1	H1-1b
651	8	M77	W24X62	.310	15.152	.052	15.152	v	60.139	819	58.807	123.182	1.1	H1-1b
652	8	M78	W24X62	.206	11.53	.068	22.83	V	103.845	819	58.807	573.75	1	H1-1b
653	8	M79	W24X62	.207	11.535	.068	22.84	v	103.754	819	58.807	573.75	1	H1-1b
654	8	M80	W24X62	.206	11.53	.068	22.83	V	103.845	819	58.807	573.75	1	H1-1b
655	8	M81	W24X62	.206	11.53	.068	22.83	ý	103.845	819	58.807	573.75	1	H1-1b
656	8	M82	W24X62	.192	10.889	.065	0	٧	111.828	819	58.807	573.75	1	H1-1b
657	9	M5	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
658	9	M6	W24X62	.005	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
659	9	M7	W24X62	.005	10.354	.002	20.5	y	128.792	819	58.807	573.75	1	H1-1b
660	9	M8	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
661	9	M9	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
662	9	M10	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
663	9	M11	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
664	9	M12	W24X62	.005	10.062	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
665	9	M13	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
666	9	M14	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
667	9	M15	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
668		M16	W24X62	.005	10.146	.002	20.5	у		819	58.807	573.75	1	H1-1b
669	9	M17	W24X62	.005	10.354	.002	20.5	y	128.792	819	58.807	573.75	1	H1-1b
670		M18	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
671	9	M19	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
672	9	M20	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
673	9	M21	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
674		M22	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
675		M23	W24X62	.191	10.146	.010	20.5	z	128.792	819	58.807	573.75	1	H1-1b
676	9	M24	W24X62	.188	10.268	.009	20.33	z		819	58.807	573.75	1	H1-1b
677	9	M25	W24X62	.191	10.146	.010	20.5	z		819	58.807	573.75	1	H1-1b
678	9	M26	HSS6X6X4	.030	0	.000	0	z	149.039	216.297		38.625	1.678	
679	9	M27	HSS6X6X4	.278	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
680		M28	HSS6X6X4	.279	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
681	9	M29	HSS6X6X4	.071	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
682		M30	HSS6X6X4	.082	0	.000	0	У		216.297		38.625	1.678	H1-1b
683	9	M31	HSS6X6X4	.483	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny		Cb	Egn
684	9	<u>M32</u>	HSS6X6X4	.483	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
685	9	M33	HSS6X6X4	.090	0	.000	0	У	149.039	216.297	38.625	38.625		
686	9	M34	HSS6X6X4	.214	0	.000	0	у	149.039	216.297	38.625		1.678	
687	9	M35	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
688	9	M36	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
689	9	M37	HSS6X6X4	.074	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1b
690	9	M38	HSS6X6X4	.219	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
691	9	M39	HSS6X6X4	.417	0	.000	0	v	149.039	216.297	38.625		1	H1-1a
692	9	M40	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
693	9	M41	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625			H1-1a
694	9	M42	HSS6X6X4	.214	0	.000	0		149.039	216.297	38.625	38.625		H1-1a
	9	M43	HSS6X6X4		_			У					1.070	H1-1a
695			HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	
696	9	M44		.417	0	.000	0	У	149.039	216.297	38.625			H1-1a
697	9	<u>M45</u>	HSS6X6X4	.214	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
698	9	M46	HSS6X6X4	.211	0	.000	0	У	149.039	216.297	38.625			H1-1a
699	9	<u>M47</u>	HSS6X6X4	.363	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
700	9	M48	HSS6X6X4	.362	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
701	9	M49	HSS6X6X4	.211	0	.000	0	У	149.039	216.297	38.625			
702	9	M50	HSS6X6X4	.053	0	.000	0	Z	149.039	216.297	38.625	38.625	1.678	H1-1b
703	9	M51	HSS6X6X4	.206	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
704	9	M52	HSS6X6X4	.207	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
705	9	M53	HSS6X6X4	.053	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	
706	9	M54	HSS6X6X4	.221	10.115	.002	20.863	V	100.047	216.297	38.625			
707	9	M55	HSS6X6X4	.091	10.537	.002	0	V	100.047	216.297	38.625	38.625		H1-1b
708	9	M56	HSS6X6X4	.030	12.359	.003	24.971	V	71.878	216.297	38.625			H1-1b
709	9	M57	HSS6X6X4	.083	8.949	.003	18.457	V	118.296	216.297	38.625	38.625		H1-1b
710	9	M58	HSS6X6X4	.048	8.946	.001	0		118.344	216.297	38.625	38.625		H1-1b
			HSS6X6X4		12.682			У						
711	9	M59		.029		.003	25.11	V	71.087	216.297	38.625			H1-1b
712	9	M60	HSS6X6X4	.232	12.775	.003	0	У	64.559	216.297	38.625	38.625		H1-1a
713	9	<u>M61</u>	HSS6X6X4	.226	11.178	.003	26.349	У	64.559	216.297	38.625			H1-1a
714	9	M62	HSS6X6X4	.027	12.428	.003	25.11	У	71.087	216.297	38.625			H1-1b
715	9	M59A	W24X62	.267	14.848	.067	0	У	60.139	819	58.807	573.75	1	H1-1b
716	9	M60A	W24X62	.103	11.53	.032	11.53	у	103.845	819	58.807	227.46	1.38	H1-1b
717	9	M61A	W24X62	.155	11.535	.051	22.84	У	103.754	819	58.807	573.75	1	H1-1b
718	9	M62A	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
719	9	M63	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
720	9	M64	W24X62	.144	10.889	.049	0	V	111.828	819	58.807	573.75	1	H1-1b
721	9	M65	W24X84	.359	15.152	.118	0	V	164.553	1111.5	122.25	840	1	H1-1b
722	9	M66	W24X62	.302	11.53	.099	22.83	v	103.845	819	58.807	573.75	1	H1-1b
723	9	M67	W24X62	.302	11.305	.099	22.84	v	103.754	819	58.807	573.75	1	H1-1b
724		M68	W24X62	.302	11.53		22.83			819		573.75		H1-1b
725	9	M69	W24X62	.302	11.53	.099	22.83		103.845	819	58.807			H1-1b
726		M70	W24X62	.281	10.889	.099	0		111.828	819	58.807			H1-1b
					15.152		0	У						
727	9	M71	W24X84	.359		.118		У	164.553	1111.5	122.25		1	H1-1b
728	9	M72	W24X62	.302	11.53	.099	22.83		103.845	819	58.807		1	H1-1b
729	9	<u>M73</u>	W24X62	.302	11.305	.099	22.84		103.754	819	58.807			H1-1b
730	9	M74	W24X62	.302	11.53	.099	22.83		103.845	819	58.807		1	H1-1b
731	9	M75	W24X62	.302	11.53	.099	22.83		103.845	819	58.807			H1-1b
732	9	M76	W24X62	.281	10.889	.096	0	У	111.828	819	58.807		1	H1-1b
733	9	M77	W24X62	.233	14.848	.039	15.152	У	60.139	819		123.183		H1-1b
734	9	M78	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
735	9	M79	W24X62	.155	11.535	.051	22.84		103.754	819	58.807		1	H1-1b
736		M80	W24X62	.155	11.3	.051	22.83		103.845	819	58.807			H1-1b
737	9	M81	W24X62	.155	11.3	.051	22.83		103.845	819	58.807			H1-1b
738	9	M82	W24X62	.144	10.889	.049	0	У	111.828	819	58.807			H1-1b
739		M5	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807			H1-1b
740		M6	W24X62	.005	10.268	.002	20.33		130.955	819		573.75	1	H1-1b
740	10	IVIO	VVZ4A0Z	.005	10.200	.002	20.33	У	130.900	019	100.007	010.10		1111-10

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	nhi*Mnv	.phi*Mnz	Cb	Eqn
741	10	M7	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
742	10	M8	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
743	10	M9	W24X62	.005	10.268	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
744	10	M10	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
745	10	M11	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
746	10	M12	W24X62	.005	10.268	.002	20.33	y	130.955	819	58.807	573.75	1	H1-1b
747	10	M13	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
748	10	M14	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
749	10	M15	W24X62	.005	10.268	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
750	10	M16	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
751	10	M17	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
752	10	M18	W24X62	.005	10.268	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
753	10	M19	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
754	10	M20	W24X62	.005	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
755	10	M21	W24X62	.005	10.268	.002	20.33	ý	130.955	819	58.807	573.75	1	H1-1b
756	10	M22	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
757	10	M23	W24X62	.005	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
758	10	M24	W24X62	.005	10.268	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
759	10	M25	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
760	10	M26	HSS6X6X4	.030	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	-
761	10	M27	HSS6X6X4	.324	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
762	10	M28	HSS6X6X4	.279	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
763	10	M29	HSS6X6X4	.071	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
764	10	M30	HSS6X6X4	.082	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
765	10	M31	HSS6X6X4	.483	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
766	10	M32	HSS6X6X4	.483	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
767	10	M33	HSS6X6X4	.090	0	.000	0	٧	149.039	216.297	38.625	38.625	1.678	
768	10	M34	HSS6X6X4	.214	0	.000	0	٧	149.039	216.297	38.625	38.625		H1-1a
769	10	M35	HSS6X6X4	.417	0	.000	0	ý	149.039	216.297	38.625	38.625	1	H1-1a
770	10	M36	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
771	10	M37	HSS6X6X4	.074	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1b
772	10	M38	HSS6X6X4	.263	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
773	10	M39	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
774	10	M40	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
775	10	M41	HSS6X6X4	.214	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
776	10	M42	HSS6X6X4	.214	0	.000	0	У	149.039	216.297	38.625	38.625	1.678	H1-1a
777	10	M43	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
778	10	M44	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
779	10	M45	HSS6X6X4	.214	0	.000	0	У	149.039	216.297	38.625	38.625		
780	10	M46	HSS6X6X4	.211	0	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
781		M47	HSS6X6X4	.373	0	.000	0	У	149.039	216.297		38.625	1	H1-1a
782		M48	HSS6X6X4	.371	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
783		M49	HSS6X6X4	.211	0	.000	0	У	149.039	216.297		38.625		
784		M50	HSS6X6X4	.053	0	.000	0	Z	149.039	216.297			1.678	
785		M51	HSS6X6X4	.206	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
786		M52	HSS6X6X4	.249	0	.000	0	Z	149.039	216.297		38.625	1	H1-1a
787		M53	HSS6X6X4	.053	0	.000	0	Z	149.039	216.297	38.625	38.625	1.678	H1-1b
788		M54	HSS6X6X4	.252	10.115	.002	0	У	100.047	216.297		38.625		
789		M55	HSS6X6X4	.076	10.537	.002	0	У	100.047	216.297		38.625		
790		M56	HSS6X6X4	.052	12.612	.003	24.971	У	71.878	216.297		38.625		
791		M57	HSS6X6X4	.097	8.949	.001	18.457	У	118.296	216.297		38.625		
792		M58	HSS6X6X4	.034	8.946	.001	18.451	У	118.344	216.297	38.625	38.625		
793		M59	HSS6X6X4	.055	12.682	.003	25.11	У	71.087	216.297	38.625			
794		M60	HSS6X6X4	.113	13.041	.003	0	У	64.559	216.297	38.625			
795		<u>M61</u>	HSS6X6X4	.110	13.041	.003	0	У	64.559	216.297		38.625		
796		M62	HSS6X6X4	.052	12.682	.003	25.11	У	71.087	216.297		38.625		
797	10	M59A	W24X62	.635	14.848	.067	0	у	60.139	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

L	C	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	.phi*Mnz	Cb	Egn
798 1	10	M60A	W24X62	.154	11.53	.032	11.53	У	103.845	819	58.807	227.46	1.38	H1-1b
799 1	10	M61A	W24X62	.368	11.535	.051	22.84	У	103.754	819	58.807	573.75	1	H1-1b
800 1	10	M62A	W24X62	.368	11.3	.051	22.83	V	103.845	819	58.807	573.75	1	H1-1b
801 1	10	M63	W24X62	.368	11.3	.051	22.83	V	103.845	819	58.807	573.75	1	H1-1b
	10	M64	W24X62	.341	10.889	.049	0	V	111.828	819	58.807	573.75	1	H1-1b
	10	M65	W24X84	.359	15.152	.118	0	v	164.553	1111.5	122.25	840	1	H1-1b
	10	M66	W24X62	.302	11.53	.099	22.83	V	103.845	819	58.807	573.75	1	H1-1b
	10	M67	W24X62	.302	11.305	.099	22.84	V	103.754	819	58.807	573.75	1	H1-1b
	10	M68	W24X62	.302	11.53	.099	22.83	V	103.845	819	58.807	573.75	1	H1-1b
	10	M69	W24X62	.302	11.53	.099	22.83	V	103.845	819	58.807	573.75	1	H1-1b
	10	M70	W24X62	.281	10.889	.096	0	V	111.828	819	58.807	573.75	1	H1-1b
	10	M71		.359	15.152	.118	0	_		1111.5	122.25	840	1	H1-1b
			W24X84					V	164.553				1	
	10	M72	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	-	H1-1b
	10	M73	W24X62	.302	11.305	.099	22.84	У	103.754	819	58.807	573.75	1	H1-1b
	10	M74	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
	10	<u>M75</u>	W24X62	.302	11.53	.099	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
	10	M76	W24X62	.281	10.889	.096	0	У	111.828	819	58.807	573.75	1	H1-1b
	10	<u>M77</u>	W24X62	.233	14.848	.039	15.152	У	60.139	819	58.807	123.183		H1-1b
	10	M78	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
	10	M79	W24X62	.155	11.535	.051	22.84	У	103.754	819	58.807	573.75	1	H1-1b
	10	M80	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
	10	M81	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
	10	M82	W24X62	.144	10.889	.049	0	У	111.828	819	58.807	573.75	1	H1-1b
821 1	11	M5	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
822 1	11	M6	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
823 1	11	M7	W24X62	.005	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
824 1	11	M8	W24X62	.005	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
	11	M9	W24X62	.005	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	11	M10	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M11	W24X62	.005	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
	11	M12	W24X62	.005	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	11	M13	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
	11	M14	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M15	W24X62	.005	10.062	.002	20.33	ý	130.955	819	58.807	573.75	1	H1-1b
	11	M16	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M17	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M18	W24X62	.005	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
	11	M19	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M20	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
	11	M21	W24X62	.005	10.062	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
838 1		M22	W24X62	.005	10.146	.002	20.5			819	58.807			H1-1b
839 1		M23	W24X62	.005	10.140	.002	20.5	У	128.792	819	58.807		1	H1-1b
840 1		M24	W24X62	.005	10.062	.002	20.33	У	130.955	819	58.807			H1-1b
841 1			W24X62 W24X62		10.002			У					1	
		M25	HSS6X6X4	.005		.002	20.5	У	128.792	819	58.807			H1-1b
842 1		M26		.030	0	.000	0	Z	149.039	216.297	38.625			H1-1b
843 1		M27	HSS6X6X4 HSS6X6X4	.278	0	.000	0	Z	149.039	216.297	38.625			H1-1a
844 1		M28		.279	0	.000	0	Z	149.039	216.297		38.625		H1-1a
845 1		M29	HSS6X6X4	.071	0	.000	0	Z	149.039	216.297	38.625			
846 1		M30	HSS6X6X4	.082	0	.000	0	У	149.039	216.297	38.625			
847 1		<u>M31</u>	HSS6X6X4	.483	0	.000	0	Z	149.039	216.297	38.625			H1-1a
848 1		<u>M32</u>	HSS6X6X4	.483	0	.000	0	Z	149.039	216.297	38.625			H1-1a
849 1		M33	HSS6X6X4	.090	0	.000	0	У	149.039	216.297	38.625			
850 1		M34	HSS6X6X4	.214	0	.000	0	У	149.039	216.297	38.625			
	11	M35	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625		1	H1-1a
	11	M36	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625			H1-1a
853 1		M37	HSS6X6X4	.074	0	.000	0	У	149.039	216.297		38.625		
854 1	11	M38	HSS6X6X4	.219	0	.000	0	у	149.039	216.297	38.625	38.625	1.678	H1-1a

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	C N	/lember	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Eqn
855 1°	1	M39	HSS6X6X4	.417	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
856 1°	1	M40	HSS6X6X4	.417	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1a
857 1°		M41	HSS6X6X4	.214	0	.000	0	v	149.039	216.297	38.625	38.625	1.678	
858 1		M42	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
859 1°		M43	HSS6X6X4	.417	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1a
860 1		M44	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
861 1		M45	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
862 1		M46	HSS6X6X4	.211	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
863 1		M47	HSS6X6X4	.259	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
864 1		M48	HSS6X6X4	.258	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
865 1		M49	HSS6X6X4	.211	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
866 1		M50	HSS6X6X4	.053	0	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
867 1		M51	HSS6X6X4	.206	0	.000	0		149.039	216.297	38.625	38.625	1	H1-1a
868 1		M52	HSS6X6X4	.208	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
869 1		M53	HSS6X6X4	.053	0	.000		Z		216.297	38.625	38.625		H1-1b
							0	Z	149.039					
870 1		M54	HSS6X6X4 HSS6X6X4	.051	10.537	.002	0	У	100.047	216.297	38.625	38.625		H1-1b
871 1		M55		.521		.002	24.071	У	100.047	216.297	38.625	38.625		H1-1a
872 1		M56	HSS6X6X4	.031	12.359	.003	24.971	У	71.878	216.297	38.625	38.625		H1-1b
873 1		M57	HSS6X6X4	.052	9.322	.001	18.457	У	118.296	216.297	38.625	38.625		H1-1b
874 11		M58	HSS6X6X4	.377	8.76	.001	0	У	118.344	216.297	38.625	38.625		H1-1a
875 1		M59	HSS6X6X4	.029	12.682	.003	25.11	У	71.087	216.297	38.625	38.625		H1-1b
876 1		M60	HSS6X6X4	.668	12.775	.003	26.349	У	64.559	216.297	38.625	38.625		H1-1a
877 1		M61	HSS6X6X4	.663	12.775	.003	26.349	У	64.559	216.297	38.625	38.625	1.14	
878 1		M62	HSS6X6X4	.027	12.682	.003	25.11	У	71.087	216.297	38.625	38.625		H1-1b
879 1		M59A	W24X62	.267	14.848	.067	0	У	60.139	819	58.807	573.75	1	H1-1b
880 1		M60A	W24X62	.103	11.3	.032	11.53	У	103.845	819	58.807	227.512		
881 1		M61A	W24X62	.155	11.535	.051	22.84	У	103.754	819	58.807	573.75	1	H1-1b
882 1		M62A	W24X62	.155	11.3	.051	22.83	У	103.845	819	58.807	573.75	1	H1-1b
883 11		M63	W24X62	.155	11.3	.051	22.83	У	103.845	<u>819</u>	58.807	573.75	1	H1-1b
884 1		M64	W24X62	.144	10.889	.049	0	У	111.828	819	58.807	573.75	1	H1-1b
885 1		M65	W24X84	.359	15.152	.118	0	У	164.553	1111.5	122.25	840	1	H1-1b
886 1		M66	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
887 1		M67	W24X62	.302	11.305	.099	22.84	У	103.754	819	58.807	573.75	1	H1-1b
888 1		M68	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
889 1		M69	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
890 1		M70	W24X62	.281	10.889	.096	0	У	111.828	819	58.807	573.75	1	H1-1b
891 1		M71	W24X84	.359	15.152	.118	0	У	164.553	1111.5	122.25	840	1	H1-1b
892 1		M72	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
893 1		M73	W24X62	.302	11.305	.099	22.84	У	103.754	819	58.807	573.75	1	H1-1b
894 1	_	M74	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b
895 1		M75	W24X62	.302	11.53	.099	22.83			819	58.807			H1-1b
896 1		M76	W24X62	.281	10.889	.096	0	У	111.828	819	58.807			H1-1b
897 1		M77	W24X62	.233	15.152	.039	15.152	У	60.139	819		123.202		H1-1b
898 11		M78	W24X62	.155	11.3	.051	22.83		103.845	819	58.807	573.75	1	H1-1b
899 1		M79	W24X62	.155	11.535	.051	22.84		103.754	819	58.807		1	H1-1b
900 1		M80	W24X62	.155	11.3	.051	22.83		103.845	819	58.807			H1-1b
901 1		M81	W24X62	.155	11.3	.051	22.83		103.845	819	58.807		11	H1-1b
902 1		M82	W24X62	.144	10.889	.049	0	У	111.828	819	58.807		1	H1-1b
903 12		<u>M5</u>	W24X62	.005	10.354	.002	20.5	ý	128.792	819	58.807		1	H1-1b
904 12		M6	W24X62	.005	10.268	.002	20.33	_	130.955	819	58.807		1	H1-1b
905 12		M7	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807		1	H1-1b
906 12		M8	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807			H1-1b
907 12		M9	W24X62	.005	10.268	.002	20.33	У	130.955	819	58.807	573.75	1	H1-1b
908 12		M10	W24X62	.005	10.146	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
909 12		M11	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807		1	H1-1b
910 12		M12	W24X62	.005	10.268	.002	20.33	_	130.955	819	58.807			H1-1b
911 12	2	M13	W24X62	.005	10.146	.002	20.5	у	128.792	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
912 12	M14	W24X62	.005	10.354	.002	20.5	У	128.792	819	58.807	573.75	1	H1-1b
913 12	M15	W24X62	.005	10.268	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
914 12	M16	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
915 12	M17	W24X62	.005	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
916 12	M18	W24X62	.005	10.268	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
917 12	M19	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
918 12	M20	W24X62	.005	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
919 12	M21	W24X62	.005	10.268	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
920 12	M22	W24X62	.005	10.146	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
921 12	M23	W24X62	.005	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
922 12	M24	W24X62	.005	10.268	.002	20.33	v	130.955	819	58.807	573.75	1	H1-1b
923 12	M25	W24X62	.005	10.146	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
924 12	M26	HSS6X6X4	.030	0	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
925 12	M27	HSS6X6X4	.518	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
926 12	M28	HSS6X6X4	.279	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
927 12	M29	HSS6X6X4	.071	0	.000	0	z	149.039	216.297	38.625	38.625		H1-1b
928 12	M30	HSS6X6X4	.082	0	.000	0	V	149.039	216.297	38.625	38.625		
929 12	M31	HSS6X6X4	.483	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
930 12	M32	HSS6X6X4	.483	0	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
931 12	M33	HSS6X6X4	.090	0	.000	0	v	149.039	216.297	38.625	38.625	1.678	H1-1b
932 12	M34	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
933 12	M35	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
934 12	M36	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
935 12	M37	HSS6X6X4	.074	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1b
936 12	M38	HSS6X6X4	.465	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
937 12	M39	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1.070	H1-1a
938 12	M40	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
939 12	M41	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
940 12	M42	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1a
941 12	M43	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1.070	H1-1a
942 12	M44	HSS6X6X4	.417	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
943 12	M45	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
943 12	M46	HSS6X6X4	.214	0	.000	0	V	149.039	216.297	38.625	38.625	1.678	
944 12	M47	HSS6X6X4	.372	0	.000	0	V	149.039	216.297	38.625	38.625	1.070	H1-1a
946 12	M48	HSS6X6X4	.372	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
947 12	M49	HSS6X6X4	.211	0	.000	0	V	149.039	216.297	38.625	38.625		H1-1a
947 12	M50	HSS6X6X4	.053	0	.000	0		149.039	216.297	38.625	38.625		
949 12	M51	HSS6X6X4	.206	0	.000	0	Z Z	149.039	216.297	38.625	38.625	1.070	H1-1a
		HSS6X6X4	.459	0		0			216.297		38.625	1	H1-1a
950 12 951 12	M52 M53	HSS6X6X4	.053	0	.000	0	Z Z	149.039 149.039	216.297	38.625 38.625	38.625	1.678	
		HSS6X6X4		10.115		20.863							
952 12 953 12		HSS6X6X4	.263 .071	10.113	.002			100.047	216.297		38.625		
953 12 954 12	M55 M56	HSS6X6X4	.305	12.612	.002	0 24.971	V	100.047 71.878	216.297 216.297	38.625 38.625	38.625 38.625		
		HSS6X6X4				18.457							
955 12	M57	HSS6X6X4	.091	8.949	.001	18.451	У	118.296 118.344	216.297	38.625	38.625 38.625		
956 12	M58		.039	8.946 12.682	.001		У		216.297	38.625			
957 12		HSS6X6X4	.321		.003	25.11	_	71.087	216.297		38.625		
958 12	M60	HSS6X6X4	.111	13.041	.003	0	У	64.559	216.297		38.625		
959 12	M61	HSS6X6X4	.112	13.041	.003	26.349	У	64.559	216.297	38.625	38.625		
960 12	M62	HSS6X6X4	.325	12.682	.003	25.11	•	71.087	216.297	38.625	38.625		
961 12	M59A	W24X62	.267	14.848	.067	0	У	60.139	819	58.807	573.75	1	H1-1b
962 12		W24X62	.105	11.53	.032	11.53			819		227.46		H1-1b
963 12	M61A	W24X62	.155	11.535	.051	22.84		103.754	819	58.807	573.75	1	H1-1b
964 12	M62A	W24X62	.155	11.3	.051	22.83		103.845	819	58.807	573.75	1	H1-1b
965 12	M63	W24X62	.155	11.3	.051	22.83		103.845	819	58.807	573.75	1	H1-1b
966 12	M64	W24X62	.144	10.889	.049	0	У	111.828	819	58.807	573.75	1	H1-1b
967 12		W24X84	.359	15.152	.118	0	У	164.553	<u>1111.5</u>	122.25	840	1	H1-1b
968   12	M66	W24X62	.302	11.53	.099	22.83	У	103.845	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	nhi*Mnv	nhi*Mnz	Cb	Eqn
	12	M67	W24X62	.302	11.305	.099	22.84		103.754	819	58.807	573.75	1	H1-1b
970		M68	W24X62	.302	11.53	.099	22.83			819	58.807	573.75	1	H1-1b
	12	M69	W24X62	.302	11.53	.099	22.83		103.845	819	58.807	573.75	1	H1-1b
	12	M70	W24X62	.281	10.889	.096	0	y	111.828	819	58.807	573.75	1	H1-1b
	12	M71	W24X84	.359	15.152	.118	0	v	164.553	1111.5	122.25	840	1	H1-1b
	12	M72	W24X62	.302	11.53	.099	22.83			819	58.807	573.75	1	H1-1b
	12	M73	W24X62	.302	11.305	.099	22.84	-		819	58.807	573.75	1	H1-1b
	12	M74	W24X62	.302	11.53	.099	22.83		103.845	819	58.807	573.75	1	H1-1b
	12	M75	W24X62	.302	11.53	.099	22.83		103.845	819	58.807	573.75	1	H1-1b
	12	M76	W24X62	.281	10.889	.096	0	V	111.828	819	58.807	573.75	1	H1-1b
	12	M77	W24X62	.233	15.152	.039	15.152		60.139	819		123.184		H1-1b
	12	M78	W24X62	.155	11.3	.051	22.83	_		819	58.807	573.75	1	H1-1b
	12	M79	W24X62	.155	11.535	.051	22.84		103.754	819	58.807	573.75	1	H1-1b
	12	M80	W24X62	.155	11.3	.051	22.83			819	58.807	573.75	1	H1-1b
	12	M81	W24X62	.155	11.3	.051	22.83			819	58.807	573.75	1	H1-1b
	12	M82	W24X62	.144	10.889	.049	0	V		819	58.807	573.75	1	H1-1b
	13	M5	W24X62	- P-Delta		.0-10		У	111.020	010	00.007	010.10		1111 10
	13	M6		- P-Delta										
	13	M7		- P-Delta										
	13	M8		- P-Delta										
	13	M9		- P-Delta										
	13	M10	W24X62	- P-Delta										
	13	M11	W24X62	- P-Delta										
	13	M12	W24X62	- P-Delta	<u>.                                    </u>									
	13	M13	W24X62	- P-Delta										
	13	M14	W24X62	- P-Delta										
	13	M15	W24X62	- P-Delta	•									
	13	M16		- P-Delta										
997		M17		- P-Delta										
	13	M18		- P-Delta										
	13	M19		- P-Delta										
1000		M20	W24X62	- P-Delta										
1001		M21	W24X62	- P-Delta										
1001		M22	W24X62	- P-Delta	<u>.                                    </u>									
1003		M23	W24X62	- P-Delta										
1004		M24	W24X62	- P-Delta										
1005		M25	W24X62	- P-Delta	•									
1005		M26		- P-Delta										
1007		M27		- P-Delta										
1007		M28		- P-Delta										
1009		M29	HSS6X6X4	- P-Delta										
1010		M30	HSS6X6X4	- P-Delta										
1011		M31	HSS6X6X4	- P-Delta										
1012		M32		- P-Delta										
1013		M33		- P-Delta										
1014		M34	HSS6X6X4	- P-Delta										
1015		M35	HSS6X6X4	- P-Delta										
1016		M36	HSS6X6X4	- P-Delta										
1017		M37	HSS6X6X4	- P-Delta										
1018		M38	HSS6X6X4	- P-Delta										
1019		M39	HSS6X6X4	- P-Delta										
1020		M40	HSS6X6X4	- P-Delta										
1021		M41	HSS6X6X4	- P-Delta										
1022		M42	HSS6X6X4	- P-Delta										
1023		M43	HSS6X6X4	- P-Delta										
1024		M44	HSS6X6X4	- P-Delta										
1025		M45	HSS6X6X4	- P-Delta										
	. •										-			

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mnv	phi*Mnz	Cb	Egn
1995 25	M31	HSS6X6X4	- P-Delta			200[.1]		p	p[]				4
1996 25	M32	HSS6X6X4	- P-Delta										
1997 25	M33	HSS6X6X4	- P-Delta										
1998 25	M34	HSS6X6X4	- P-Delta										
1999 25	M35	HSS6X6X4	- P-Delta										
2000 25	M36	HSS6X6X4	- P-Delta										
2001 25	M37	HSS6X6X4	- P-Delta										
2002 25	M38	HSS6X6X4	- P-Delta										
2003 25	M39	HSS6X6X4	- P-Delta										
2004 25	M40	HSS6X6X4	- P-Delta										
2005 25	M41	HSS6X6X4	- P-Delta										
2006 25	M42	HSS6X6X4	- P-Delta										
2007 25	M43	HSS6X6X4	- P-Delta										
2008 25	M44	HSS6X6X4	- P-Delta										
2009 25	M45	HSS6X6X4	- P-Delta										
2010 25	M46	HSS6X6X4	- P-Delta										
2010 25	M47	HSS6X6X4	- P-Delta										
2012 25	M48	HSS6X6X4	- P-Delta										
2012 25	M49	HSS6X6X4	- P-Delta										
2014 25	M50	HSS6X6X4	- P-Delta										
2015 25	M51	HSS6X6X4	- P-Delta										
2016 25	M52	HSS6X6X4	- P-Delta										
2017 25	M53	HSS6X6X4	- P-Delta										
2018 25	M54	HSS6X6X4	- P-Delta	•									
2019 25	M55	HSS6X6X4	- P-Delta	•									
2020 25	M56	HSS6X6X4	- P-Delta	•									
2020 25	M57	HSS6X6X4	- P-Delta	•									
2021 25	M58	HSS6X6X4	- P-Delta	•									
2023 25	M59	HSS6X6X4	- P-Delta	•									
2023 25	M60	HSS6X6X4	- P-Delta	•									
2025 25	M61	HSS6X6X4	- P-Delta	•									
2026 25	M62	HSS6X6X4	- P-Delta	•									
2027 25	M59A	W24X62	- P-Delta	•									
2028 25	M60A	W24X62	- P-Delta	•									
2029 25	M61A	W24X62	- P-Delta	•									
2030 25	M62A	W24X62	- P-Delta	•									
2030 25	M63	W24X62	- P-Delta	•									
2031 25	M64	W24X62	- P-Delta	•									
2032 25	M65	W24X84	- P-Delta										
2034 25	M66	W24X62	- P-Delta	•									
2035 25	M67	W24X62	- P-Delta	•									
2036 25	M68	W24X62	- P-Delta	•									
2036 25	M69	W24X62	- P-Delta	•									
2037 25	M70	W24X62	- P-Delta	•									
2039 25	M71	W24X84	- P-Delta	•									
2039 25	M72	W24X64 W24X62	- P-Delta	•									
2040 25	M73	W24X62	- P-Delta	•									
2041 25	M74	W24X62	- P-Delta	•									
2042 25	M75	W24X62	- P-Delta	•									
			- P-Delta	•									
2044 25	M76	W24X62	- P-Delta	•									
2045 25	M77	W24X62		•									
2046 25	M78	W24X62	- P-Delta	•									
2047 25	M79	W24X62	- P-Delta										
2048 25	M80	W24X62	- P-Delta	•									
2049 25	M81	W24X62	- P-Delta										
2050 25	M82	W24X62	- P-Delta	40.051	000	00.5		400 700	040	E0.00=	F70		114 41
2051 26	M5	W24X62	.006	10.354	.002	20.5	у	128.792	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Egn
2052 26	M6	W24X62	.006	10.268	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
2053 26	M7	W24X62	.006	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
2054 26	M8	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2055 26	M9	W24X62	.006	10.268	.002	20.33	y	130.955	819	58.807	573.75	1	H1-1b
2056 26	M10	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2057 26	M11	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2058 26	M12	W24X62	.006	10.268	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
2059 26	M13	W24X62	.006	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
2060 26	M14	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2061 26	M15	W24X62	.006	10.268	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
2062 26	M16	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2063 26	M17	W24X62	.006	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
2064 26	M18	W24X62	.006	10.268	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
2065 26	M19	W24X62	.006	10.354	.002	20.5	ý	128.792	819	58.807	573.75	1	H1-1b
2066 26	M20	W24X62	.006	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
2067 26	M21	W24X62	.006	10.268	.002	20.33	V	130.955	819	58.807	573.75	1	H1-1b
2068 26	M22	W24X62	.006	10.354	.002	20.5	٧	128.792	819	58.807	573.75	1	H1-1b
2069 26	M23	W24X62	.006	10.354	.002	20.5	V	128.792	819	58.807	573.75	1	H1-1b
2070 26	M24	W24X62	.006	10.268	.002	20.33	٧	130.955	819	58.807	573.75	1	H1-1b
2071 26	M25	W24X62	.006	10.354	.002	20.5	v	128.792	819	58.807	573.75	1	H1-1b
2072 26	M26	HSS6X6X4	.004	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2073 26	M27	HSS6X6X4	.010	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2074 26	M28	HSS6X6X4	.009	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2075 26	M29	HSS6X6X4	.006	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2076 26	M30	HSS6X6X4	.007	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2077 26	M31	HSS6X6X4	.012	0	.000	0	z	149.039	216.297	38.625		1	H1-1b
2078 26	M32	HSS6X6X4	.012	0	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2079 26	M33	HSS6X6X4	.007	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2080 26	M34	HSS6X6X4	.008	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2081 26	M35	HSS6X6X4	.010	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2082 26	M36	HSS6X6X4	.010	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2083 26	M37	HSS6X6X4	.006	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2084 26	M38	HSS6X6X4	.009	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2085 26	M39	HSS6X6X4	.010	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2086 26	M40	HSS6X6X4	.010	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2087 26	M41	HSS6X6X4	.008	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2088 26	M42	HSS6X6X4	.008	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2089 26	M43	HSS6X6X4	.010	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2090 26	M44	HSS6X6X4	.010	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2091 26	M45	HSS6X6X4	.008	0	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2092 26	M46	HSS6X6X4	.008	0	.000	0	V	149.039	216.297		38.625	1	H1-1b
2093 26	M47	HSS6X6X4	.010	0	.000	0	ý	149.039	216.297	38.625		1	H1-1b
2094 26	M48	HSS6X6X4	.010	0	.000	0	V	149.039	216.297	38.625		1	H1-1b
2095 26	M49	HSS6X6X4	.008	0	.000	0	У	149.039	216.297	38.625		1	H1-1b
2096 26	M50	HSS6X6X4	.005	0	.000	0	z	149.039	216.297	38.625		1	H1-1b
2097 26	M51	HSS6X6X4	.007	0	.000	0	z	149.039	216.297	38.625		1	H1-1b
2098 26	M52	HSS6X6X4	.008	0	.000	0	z	149.039	216.297		38.625	1	H1-1b
2099 26	M53	HSS6X6X4	.005	0	.000	0	z	149.039	216.297	38.625		1	H1-1b
2100 26	M54	HSS6X6X4	.025	10.326	.002	0	У	100.047	216.297	38.625			
2101 26	M55	HSS6X6X4	.022	10.537	.002	0	V	100.047	216.297	38.625			
2102 26	M56	HSS6X6X4	.029	12.359	.003	0	V	71.878	216.297	38.625			
2103 26	M57	HSS6X6X4	.017	8.949	.002	18.457	У	118.296	216.297	38.625			
2104 26	M58	HSS6X6X4	.014	8.946	.002	18.451	V	118.344	216.297	38.625			
2105 26	M59	HSS6X6X4	.030	12.682	.002	25.11	-	71.087	216.297	38.625			
2106 26	M60	HSS6X6X4	.037	13.041	.003	0	V	64.559	216.297		38.625		
2107 26	M61	HSS6X6X4	.037	13.041	.003	0	V	64.559	216.297		38.625		
2108 26	M62	HSS6X6X4	.030	12.428	.003	25.11		71.087	216.297		38.625		
00 20	14102				.500		y	1 1.001	2.0.201	00.020	00.020		

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	.phi*Mnz	Cb	Eqn
2109 26	M59A	W24X62	.012	14.848	.003	0	У	60.139	819	58.807	573.75	1	H1-1b
2110 26	M60A	W24X62	.005	11.53	.002	11.53	٧	103.845	819	58.807	254.699	1.545	H1-1b
2111 26	M61A	W24X62	.007	11.305	.002	22.84	V	103.754	819	58.807	573.75	1	H1-1b
2112 26	M62A	W24X62	.007	11.3	.002	22.83	٧	103.845	819	58.807	573.75	1	H1-1b
2113 26	M63	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2114 26	M64	W24X62	.007	10.889	.002	0	V	111.828	819	58.807	573.75	1	H1-1b
2115 26	M65	W24X84	.011	14.848	.004	0	V	164.553	1111.5	122.25	840	1	H1-1b
2116 26	M66	W24X62	.007	11.3	.002	22.83	v	103.845	819	58.807	573.75	1	H1-1b
2117 26	M67	W24X62	.007	11.305	.002	22.84	v	103.754	819	58.807	573.75	1	H1-1b
2118 26	M68	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2119 26	M69	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2120 26	M70	W24X62	.007	10.889	.002	0	V	111.828	819	58.807	573.75	1	H1-1b
2121 26	M71	W24X84	.011	14.848	.004	0	V	164.553	1111.5	122.25	840	1	H1-1b
2122 26	M72	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2123 26	M73	W24X62	.007	11.305	.002	22.84	V	103.754	819	58.807	573.75	1	H1-1b
2124 26	M74	W24X62	.007	11.3	.002	22.83	V	103.734	819	58.807	573.75	1	H1-1b
2125 26	M75	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2126 26	M76	W24X62	.007	10.889	.002	0	V	111.828	819	58.807	573.75	1	H1-1b
				14.848		15.152	-						H1-1b
	M77	W24X62	.011		.002		У	60.139	819	58.807	127.722		
2128 26	M78	W24X62	.007	11.3 11.305	.002	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2129 26	M79	W24X62	.007		.002	22.84	V	103.754	819	58.807	573.75	1	H1-1b
2130 26	M80	W24X62	.007	11.3	.002	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2131 26	<u>M81</u>	W24X62	.007	11.3	.002	22.83	V	103.845	819	58.807	573.75		H1-1b
2132 26	<u>M82</u>	W24X62	.007	10.889	.002	0	У	111.828	819	58.807	573.75	1	H1-1b
2133 27	<u>M5</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	_1_	H1-1b
2134 27	<u>M6</u>	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2135 27	M7	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	_1_	H1-1b
2136 27	M8	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2137 27	M9	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	_1_	H1-1b
2138 27	<u>M10</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2139 27	<u>M11</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2140 27	M12	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2141 27	M13	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	_1_	H1-1b
2142 27	M14	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2143 27	M15	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	_1_	H1-1b
2144 27	<u>M16</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2145 27	<u>M17</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2146 27	M18	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2147 27	<u>M19</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	_1_	H1-1b
2148 27	M20	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2149 27	M21	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75		H1-1b
2150 27	M22	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2151 27	M23	W24X62	.000	0	.000	0	z	128.792	819	58.807		1	H1-1b
2152 27	M24	W24X62	.000	0	.000	0	Z	130.955	819	58.807			H1-1b
2153 27	M25	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2154 27	M26	HSS6X6X4	.004	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2155 27	M27	HSS6X6X4	.020	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2156 27	M28	HSS6X6X4	.021	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2157 27	M29	HSS6X6X4	.010	14.5	.000	0	z	149.039	216.297	38.625		1	H1-1b
2158 27	M30	HSS6X6X4	.012	14.5	.000	0	У	149.039	216.297	38.625			H1-1b
2159 27	M31	HSS6X6X4	.036	14.5	.000	0	z	149.039	216.297	38.625		1	H1-1b
2160 27	M32	HSS6X6X4	.036	14.5	.000	0	Z	149.039	216.297		38.625		H1-1b
2161 27	M33	HSS6X6X4	.013	14.5	.000	0	V	149.039	216.297	38.625		1	H1-1b
2162 27	M34	HSS6X6X4	.016	14.5	.000	0	V	149.039	216.297	38.625			H1-1b
2163 27	M35	HSS6X6X4	.031	14.5	.000	0	v	149.039	216.297	38.625		1	H1-1b
2164 27	M36	HSS6X6X4	.031	14.5	.000	0	V	149.039	216.297		38.625	1	H1-1b
2165 27	M37	HSS6X6X4	.011	14.5	.000	0	v	149.039	216.297		38.625	1	H1-1b
		*					- ,						

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
2166 27	M38	HSS6X6X4	.016	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2167 27	M39	HSS6X6X4	.031	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2168 27	M40	HSS6X6X4	.031	14.5	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1b
2169 27	M41	HSS6X6X4	.016	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2170 27	M42	HSS6X6X4	.016	14.5	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2171 27	M43	HSS6X6X4	.031	14.5	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2172 27	M44	HSS6X6X4	.031	14.5	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2173 27	M45	HSS6X6X4	.016	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2174 27	M46	HSS6X6X4	.015	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2175 27	M47	HSS6X6X4	.028	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2176 27	M48	HSS6X6X4	.028	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2177 27	M49	HSS6X6X4	.015	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2178 27	M50	HSS6X6X4	.008	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2179 27	M51	HSS6X6X4	.005	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2180 27	M52	HSS6X6X4	.015	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
		HSS6X6X4											
2181 27 2182 27	M53	HSS6X6X4	.008	14.5	.000	<u>       0                             </u>	Z	149.039	216.297 216.297	38.625	38.625	1	H1-1b
	M54	HSS6X6X4	.018	0	.000		У	100.047		38.625	38.625	-	H1-1b
2183 27 2184 27	M55	HSS6X6X4	.009	0	.000	0	V	100.047	216.297	38.625	38.625	1	H1-1b
2184 27	M56	HSS6X6X4	.001	0	.000	0	У	71.878	216.297 216.297	38.625	38.625	1	H1-1b
	M57	HSS6X6X4	.013	0	.000	0	У	118.296		38.625	38.625		H1-1b
2186 27	M58	HSS6X6X4	.003	0	.000	0	У	118.344	216.297	38.625	38.625	1	H1-1b
2187 27	M59		.000	0	.000	0	У	71.087	216.297	38.625	38.625	1	H1-1b
2188 27	M60	HSS6X6X4	.012	0	.000	0	У	64.559	216.297	38.625	38.625	1	H1-1b
2189 27	M61	HSS6X6X4	.012	0	.000	0	У	64.559	216.297	38.625	38.625	1	H1-1b
2190 27	M62	HSS6X6X4	.000	0	.000	0	У	71.087	216.297	38.625	38.625	1	H1-1b
2191 27	M59A	W24X62	.040	14.848	.010	0	У	60.139	819	58.807	573.75	1 272	H1-1b
2192 27	M60A	W24X62	.015	11.53	.005	11.53	У	103.845	819		226.203		H1-1b
2193 27	M61A	W24X62	.023	11.305	.008	22.84	V	103.754	819	58.807	573.75	1	H1-1b
2194 27	M62A	W24X62	.023	11.3	.008	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2195 27	M63	W24X62	.023	11.3	.008	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2196 27	M64	W24X62	.022	10.889	.007	0	У	111.828	819	58.807	573.75	1	H1-1b
2197 27	M65	W24X84	.055	14.848	.018	0	V	164.553	1111.5	122.25	840	1	H1-1b
2198 27	M66	W24X62	.046	11.3	.015	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2199 27	M67	W24X62	.046	11.305	.015	22.84	У	103.754	819	58.807	573.75	1	H1-1b
2200 27	M68	W24X62	.046	11.3	.015	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2201 27	M69	W24X62	.046	11.3	.015	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2202 27	M70	W24X62	.043	11.111	.015	0	У	111.828	819	58.807	573.75	1	H1-1b
2203 27	M71	W24X84	.055	14.848	.018	0	V	164.553	1111.5	122.25	840	1	H1-1b
2204 27	M72	W24X62	.046	11.3	.015	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2205 27	M73	W24X62	.046	11.305	.015	22.84	У	103.754	819	58.807	573.75	1	H1-1b
2206 27	M74	W24X62	.046	11.3	.015	22.83			819		573.75		H1-1b
2207 27	M75	W24X62	.046	11.3	.015	22.83		103.845	819	58.807	573.75	1	H1-1b
2208 27	M76	W24X62	.043	11.111	.015	15 152	У	111.828	819	58.807	573.75	1 008	H1-1b
2209 27	M77	W24X62	.035	14.848	.006	15.152	У	60.139	819		122.991		
2210 27	M78	W24X62	.023	11.3	.008	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2211 27	M79	W24X62	.023	11.305	.008	22.84		103.754	819	58.807		1	H1-1b
2212 27	M80	W24X62	.023	11.3	.008	22.83		103.845	819	58.807	573.75	1	H1-1b
2213 27	M81	W24X62	.023	11.3	.008			103.845	819	58.807	573.75	1	H1-1b
2214 27	M82	W24X62	.022	10.889	.007	0	У	111.828	819	58.807	573.75		H1-1b
2215 28	M5	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2216 28	<u>M6</u>	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2217 28	M7	W24X62	.000	0	.000	00	Z	128.792	819	58.807	573.75	1	H1-1b
2218 28	<u>M8</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2219 28	<u>M9</u>	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2220 28	M10	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2221 28	<u>M11</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2222 28	M12	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Eqn
2223 28	M13	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2224 28	M14	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2225 28	M15	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2226 28	M16	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2227 28	M17	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2228 28	M18	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2229 28	M19	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2230 28	M20	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2231 28	M21	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2232 28	M22	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2233 28	M23	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2234 28	M24	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2235 28	M25	W24X62	.000	0	.000	0		128.792	819	58.807	573.75	1	H1-1b
2236 28		HSS6X6X4	.029	14.5	.000	0	Z		216.297	38.625	38.625		H1-1b
2230 28	M26	HSS6X6X4	.290				Z	149.039		38.625	38.625	1.070	
	M27	HSS6X6X4		14.5	.000	0	Z	149.039	216.297			_	H1-1a
2238 28	M28		.291	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1 670	H1-1a
2239 28	M29	HSS6X6X4	.073	14.5	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
2240 28	M30	HSS6X6X4	.085	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1b
2241 28	<u>M31</u>	HSS6X6X4	.513	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
2242 28	M32	HSS6X6X4	.513	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1 070	H1-1a
2243 28	<u>M33</u>	HSS6X6X4	.093	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1b
2244 28	<u>M34</u>	HSS6X6X4	.223	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
2245 28	<u>M35</u>	HSS6X6X4	.444	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
2246 28	M36	HSS6X6X4	.444	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
2247 28	<u>M37</u>	HSS6X6X4	.076	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1b
2248 28	<u>M38</u>	HSS6X6X4	.226	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
2249 28	<u>M39</u>	HSS6X6X4	.444	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1a
2250 28	M40	HSS6X6X4	.444	14.5	.000	0	У	149.039	216.297	38.625	38.625	1 070	H1-1a
2251 28	<u>M41</u>	HSS6X6X4	.223	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
2252 28	M42	HSS6X6X4	.223	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
2253 28	<u>M43</u>	HSS6X6X4	.443	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
2254 28	M44	HSS6X6X4	.443	14.5	.000	0	У	149.039	216.297	38.625	38.625	1 070	H1-1a
2255 28	M45	HSS6X6X4	.223	14.5	.000	0	V	149.039	216.297	38.625	38.625	1.678	
2256 28	M46	HSS6X6X4	.219	14.5	.000	0	У	149.039	216.297	38.625	38.625		H1-1a
2257 28	M47	HSS6X6X4	.395	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1a
2258 28	M48	HSS6X6X4	.393	14.5	.000	0	У	149.039	216.297	38.625	38.625	1 070	H1-1a
2259 28	M49	HSS6X6X4	.219	14.5	.000	0	٧	149.039	216.297	38.625	38.625		H1-1a
2260 28	M50	HSS6X6X4	.054	14.5	.000	0	Z	149.039	216.297	38.625	38.625		111 10
2261 28	<u>M51</u>	HSS6X6X4	.214	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
2262 28	M52	HSS6X6X4	.213	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1 070	H1-1a
2263 28	<u>M53</u>	HSS6X6X4	.054	14.5	.000	0	Z	149.039	216.297		38.625		
2264 28	<u>M54</u>	HSS6X6X4	.251	0	.000	0	У	100.047	216.297	38.625			H1-1a
2265 28	<u>M55</u>	HSS6X6X4	.062	0	.000	0	٧	100.047	216.297	38.625		1	H1-1b
2266 28	M56	HSS6X6X4	.003	0	.000	0	У	71.878	216.297	38.625		1	H1-1b
2267 28	<u>M57</u>	HSS6X6X4	.090	0	.000	0	У	118.296	216.297	38.625		1	H1-1b
2268 28	<u>M58</u>	HSS6X6X4	.024	0	.000	0	У	118.344	216.297		38.625	1	H1-1b
2269 28	<u>M59</u>	HSS6X6X4	.002	0	.000	0	У	71.087	216.297	38.625		1	H1-1b
2270 28	M60	HSS6X6X4	.088	0	.000	0	У	64.559	216.297	38.625		1	H1-1b
2271 28	<u>M61</u>	HSS6X6X4	.085	0	.000	0	У	64.559	216.297	38.625		1	H1-1b
2272 28	M62	HSS6X6X4	.001	0	.000	0	У	71.087	216.297	38.625			H1-1b
2273 28	M59A	W24X62	.285	15.152	.071	0	V	60.139	819	58.807		1	H1-1b
2274 28	M60A	W24X62	.110	11.53	.034	11.53		103.845	819		226.201		
2275 28	M61A	W24X62	.165	11.305	.054	22.84		103.754	819	58.807		1	H1-1b
2276 28	M62A	W24X62	.165	11.3	.054	22.83		103.845	819	58.807		1	H1-1b
2277 28	M63	W24X62	.165	11.3	.054	22.83		103.845	819	58.807		1	H1-1b
2278 28	<u>M64</u>	W24X62	.153	10.889	.052	0	У	111.828	819	58.807			H1-1b
2279 28	M65	W24X84	.388	15.152	.128	0	у	164.553	1111.5	122.25	840	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Egn
2280 28	M66	W24X62	.329	11.53	.108	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2281 28	M67	W24X62	.329	11.305	.108	22.84	У	103.754	819	58.807	573.75	1	H1-1b
2282 28	M68	W24X62	.329	11.53	.108	22.83	٧	103.845	819	58.807	573.75	1	H1-1b
2283 28	M69	W24X62	.329	11.53	.108	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2284 28	M70	W24X62	.305	11.111	.104	0	У	111.828	819	58.807	573.75	1	H1-1b
2285 28	M71	W24X84	.388	15.152	.128	0	У	164.553	1111.5	122.25	840	1	H1-1b
2286 28	M72	W24X62	.329	11.53	.108	22.83	٧	103.845	819	58.807	573.75	1	H1-1b
2287 28	M73	W24X62	.329	11.305	.108	22.84	٧	103.754	819	58.807	573.75	1	H1-1b
2288 28	M74	W24X62	.329	11.53	.108	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2289 28	M75	W24X62	.329	11.53	.108	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2290 28	M76	W24X62	.305	11.111	.104	0	У	111.828	819	58.807	573.75	1	H1-1b
2291 28	M77	W24X62	.248	14.848	.042	15.152	У	60.139	819	58.807	122.987	1.098	H1-1b
2292 28	M78	W24X62	.165	11.3	.054	22.83	V	103.845	819	58.807	573.75	1	H1-1b
2293 28	M79	W24X62	.165	11.305	.054	22.84	У	103.754	819	58.807	573.75	1	H1-1b
2294 28	M80	W24X62	.165	11.3	.054	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2295 28	M81	W24X62	.165	11.3	.054	22.83	У	103.845	819	58.807	573.75	1	H1-1b
2296 28	M82	W24X62	.153	10.889	.052	0	У	111.828	819	58.807	573.75	1	H1-1b
2297 29	M5	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2298 29	M6	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2299 29	M7	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2300 29	M8	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2301 29	M9	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2302 29	M10	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2303 29	M11	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2304 29	M12	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2305 29	M13	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2306 29	M14	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2307 29	M15	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2308 29	M16	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2309 29	M17	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2310 29	M18	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2311 29	M19	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2312 29	M20	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2313 29	M21	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2314 29	M22	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2315 29	M23	W24X62	.116	10.146	.006	20.5	Z	128.792	819	58.807	573.75	1	H1-1b
2316 29	M24	W24X62	.114	10.062	.006	20.33	Z	130.955	819	58.807	573.75	1	H1-1b
2317 29	M25	W24X62	.116	10.146	.006	20.5	Z	128.792	819	58.807	573.75	1	H1-1b
2318 29	M26	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2319 29	M27	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2320 29	M28	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625		1	H1-1b
2321 29	M29	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2322 29	M30	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2323 29	M31	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2324 29	M32	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2325 29	M33	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625		1	H1-1b
2326 29	M34	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297		38.625	1	H1-1b
2327 29	M35	HSS6X6X4	.000	0	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1b
2328 29	M36	HSS6X6X4	.000	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2329 29	M37	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2330 29	M38	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297		38.625	1	H1-1b
2331 29	M39	HSS6X6X4	.000	0	.000	0	У	149.039	216.297	38.625		1	H1-1b
2332 29	M40	HSS6X6X4	.000	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2333 29	M41	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2334 29	M42	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2335 29	M43	HSS6X6X4	.000	0	.000	0	У	149.039	216.297		38.625	1	H1-1b
2336 29	M44	HSS6X6X4	.000	0	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	.phi*Mnz	Cb	Eqn
2337 29	M45	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2338 29	M46	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2339 29	M47	HSS6X6X4	.002	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2340 29	M48	HSS6X6X4	.002	0	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2341 29	M49	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2342 29	M50	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2343 29	M51	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2344 29	M52	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2345 29	M53	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2346 29	M54	HSS6X6X4	.005	0	.000	0	V	100.047	216.297	38.625	38.625	1	H1-1b
2347 29	M55	HSS6X6X4	.010	0	.000	0	v	100.047	216.297	38.625	38.625	1	H1-1b
2348 29	M56	HSS6X6X4	.001	0	.000	0	V	71.878	216.297	38.625	38.625	1	H1-1b
2349 29	M57	HSS6X6X4	.005	0	.000	0	V	118.296	216.297	38.625	38.625	1	H1-1b
2350 29	M58	HSS6X6X4	.008	0	.000	0	V	118.344	216.297	38.625	38.625	1	H1-1b
2351 29	M59	HSS6X6X4	.000	0	.000	0	V	71.087	216.297	38.625	38.625	1	H1-1b
2352 29	M60	HSS6X6X4	.012	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1b
2353 29	M61	HSS6X6X4	.012	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1b
2354 29	M62	HSS6X6X4	.000	0	.000	0	V	71.087	216.297	38.625	38.625	1	H1-1b
2355 29	M59A	W24X62	.000	0	.000	0	Z	60.139	819	58.807	573.75	1	H1-1b
2356 29	M60A	W24X62	.000	11.3	.000	0	Z	103.845	819	58.807	216.96		
2357 29	M61A	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b
2358 29	M62A	W24X62	.000	0	.000	0	Z	103.734	819	58.807	573.75	1	H1-1b
2359 29	M63	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2360 29	M64	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2361 29	M65	W24X84	.000	0	.000	0	Z	164.553	1111.5	122.25	840	1	H1-1b
2362 29	M66	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
				0			_					1	
2363 29	M67	W24X62	.000	_	.000	00	Z	103.754	819	58.807	573.75		H1-1b
2364 29	M68	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1_1	H1-1b
2365 29	<u>M69</u>	W24X62	.000	0	.000	00	Z	103.845	819	58.807	573.75	<u>1</u> 1	H1-1b
2366 29	M70	W24X62	.000		.000	0	Z	111.828	819	58.807	573.75		H1-1b
2367 29	M71	W24X84	.000	0	.000	00	Z	164.553	1111.5	122.25	840	11_	H1-1b
2368 29	M72	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1_	H1-1b
2369 29	M73	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b
2370 29	M74	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1_	H1-1b
2371 29	M75	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1_	H1-1b
2372 29	<u>M76</u>	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2373 29	<u>M77</u>	W24X62	.000	14.848	.000	0_	Z	60.139	819	58.807	147.413		
2374 29	<u>M78</u>	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1_	H1-1b
2375 29	<u>M79</u>	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	_1_	H1-1b
2376 29	<u>M80</u>	W24X62	.000	0	.000	0	Z	103.845	<u>819</u>	58.807	573.75	1_	H1-1b
2377 29	<u>M81</u>	W24X62	.000	0	.000	0	Z	103.845	819	58.807		_1_	H1-1b
2378 29	<u>M82</u>	W24X62	.000	0	.000	0	Z	111.828	<u>819</u>	58.807		1	H1-1b
2379 30	<u>M5</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	_1_	H1-1b
2380 30	<u>M6</u>	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2381 30	<u>M7</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2382 30	<u>M8</u>	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2383 30	M9	W24X62	.000	0	.000	0	Z	130.955	819	58.807		_1_	H1-1b
2384 30	M10	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2385 30	M11	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2386 30	M12	W24X62	.000	0	.000	0	Z	130.955	819	58.807		1	H1-1b
2387 30	M13	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2388 30	M14	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1_	H1-1b
2389 30	M15	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2390 30	M16	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2391 30	M17	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2392 30	M18	W24X62	.000	0	.000	0	Z	130.955	819	58.807		1	H1-1b
2393 30	M19	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

2394 30 M20 W24X62 000 0 0.000 0 z 128,792 819 58,807 573.75 1 H1-1b 2396 30 M21 W24X62 000 0 .000 0 z 130,955 819 58,807 573.75 1 H1-1b 2396 30 M22 W24X62 000 0 .000 0 z 128,792 819 58,807 573.75 1 H1-1b 2398 30 M22 W24X62 000 0 .000 0 z 128,792 819 58,807 573.75 1 H1-1b 2398 30 M24 W24X62 000 0 .000 0 z 128,792 819 58,807 573.75 1 H1-1b 2398 30 M24 W24X62 000 0 .000 0 z 128,792 819 58,807 573.75 1 H1-1b 2398 30 M25 W24X62 .000 0 .000 0 z 128,792 819 58,807 573.75 1 H1-1b 2400 30 M26 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2402 30 M26 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2402 30 M28 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2404 30 M30 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2404 30 M30 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2404 30 M30 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2404 30 M30 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2406 30 M32 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2406 30 M32 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2406 30 M32 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2408 30 M34 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2408 30 M34 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2408 30 M34 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2401 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.5 .000 0 z 149,039 216,297 38,625 38,625 1 H1-1b 2411 30 M36 H586X6X4 000 14.	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	.phi*Mnz	Cb	Egn
2396 30 M22 W24K62 000 0 0.000 0 z 128.792 819 58.807 573.75 1 H1-1b 2398 30 M24 W24K62 000 0 0.000 0 z 130.955 819 58.807 573.75 1 H1-1b 2398 30 M24 W24K62 000 0 0.000 0 z 130.955 819 58.807 573.75 1 H1-1b 2401 30 M25 W24K62 000 0 0.000 0 z 149.792 819 58.807 573.75 1 H1-1b 2402 30 M25 W24K62 000 0 0.000 0 z 149.932 16.297 38.625 38.625 1 H1-1b 2402 30 M26 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2404 30 M30 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M33 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2409 30 M33 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2409 30 M35 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2409 30 M33 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 0 0 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 0 0 0 z 149.039 216.297 38.62	2394 30	M20		.000	0	.000	0	Z	128.792	819	58.807	573.75	1	
2396 30 M22 W24K62 000 0 0.000 0 z 128.792 819 58.807 573.75 1 H1-1b 2398 30 M24 W24K62 000 0 0.000 0 z 130.955 819 58.807 573.75 1 H1-1b 2398 30 M24 W24K62 000 0 0.000 0 z 130.955 819 58.807 573.75 1 H1-1b 2402 30 M25 W24K62 000 1 0.000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M26 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M26 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2402 30 M28 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2404 30 M30 HSS6K64 001 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2404 30 M30 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M32 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2406 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M33 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M33 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2408 30 M34 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 000 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 0 0 z 149.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 0 0 z 149.039 216.297 38	2395 30	M21	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2398 30 M24 W24K62 000 0 .000 0 z 128.792 819 58.807 573.75 1 H1-1b 2399 30 M25 W24K62 000 0 .000 0 z 128.792 819 58.807 573.75 1 H1-1b 2399 30 M25 W24K62 000 0 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2401 30 M27 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2401 30 M27 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2401 30 M29 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2403 30 M29 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2405 30 M31 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2405 30 M31 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2405 30 M31 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2405 30 M31 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2405 30 M34 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2407 30 M33 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2407 30 M34 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2409 30 M35 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2409 30 M35 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2409 30 M36 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2409 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M37 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M38 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39 HSS6K64 000 0 14.5 .000 0 z 148.039 216.297 38.625 38.625 1 H1-1b 2411 30 M39	2396 30	M22	W24X62	.000	0	.000	0	z		819	58.807	573.75	1	H1-1b
2398   30   M25		M23			0		0	z					1	
2399   30   M26					0		0							
2401 30   M26					_			-						
2401 30 MZP HSSKKKM					_									
2402 30 M28 HSSKKK44 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2404 30 M30 HSSKK644 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2406 30 M31 HSSKK644 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2406 30 M32 HSSKK644 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2406 30 M32 HSSKK644 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2406 30 M33 HSSKK644 000 14.5 000 0 z 149.039 z16.297 38.625 38.625 1 H1-1b 2408 30 M34 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2408 30 M34 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2409 30 M35 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2409 30 M35 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2411 30 M37 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2411 30 M37 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2411 30 M38 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2413 30 M39 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2413 30 M39 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2413 30 M39 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2413 30 M34 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2414 30 M34 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2416 30 M41 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2416 30 M41 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2416 30 M44 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2416 30 M44 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2416 30 M44 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2422 30 M48 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2423 30 M49 HSSKK644 000 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2423 30 M49 HSSKK644 000 0 14.5 000 0 y 149.039 z16.297 38.625 38.625 1 H1-1b 2424 30 M50 HSSKK644 000 0 14.5 000 0 y 149.039 z16.297 38.625 38.6														
2403 30         M29         HSSEKSK4         000         14.5         000         0         14.9 0.039         216.297         38.625         38.625         1         H1-1b           2404 30         M30         HSSEKSK4         000         14.5         000         0         y 149.039         216.297         38.625         38.625         1         H1-1b           2406 30         M32         HSSEKSK4         000         14.5         000         0         7         149.039         216.297         38.625         38.625         1         H1-1b           2407 30         M33         HSSEKSK4         000         14.5         000         0         y 149.039         216.297         38.625         38.625         1         H1-1b           2409 30         M34         HSSEKSK4         000         14.5         000         0         y 149.039         216.297         38.625         38.625         1         H1-1b           2409 30         M36         HSSEKSK4         000         14.5         000         0         y 149.039         216.297         38.625         38.625         1         H1-1b           2411 30         M38         HSSEKSK44         000         14.5							_							
2404 30         M30         HSS6X6X4         000         14,5         000         0         y 149,039         216,297         38,625         38,625         1         H1-1b           2406 30         M32         HSS6X6X4         000         14,5         000         0         z 149,039         216,297         38,625         38,625         1         H1-1b           2407 30         M33         HSS6X6X4         000         14,5         000         0         y 149,039         216,297         38,625         38,625         1         H1-1b           2408 30         M34         HSS6X6X4         000         14,5         000         0         y 149,039         216,297         38,625         38,625         1         H1-1b           2409 30         M35         HSS6X6V4         000         14,5         000         0         y 149,039         216,297         38,625         38,625         11,1b         11-1b           2411 30         M36         HSS6X6V4         000         14,5         000         0         y 149,039         216,297         38,625         38,625         11,1-1b           2412 30         M39         HSS6X6V4         000         14,5         000         0 </td <td></td>														
2405 30         M31         HSS6K6W4         000         14,5         000         0         z         149,039         216,297         38,625         38,625         1         H1-1b           2407 30         M33         HSS6K6W4         000         14,5         000         0         V         149,039         216,297         38,625         38,625         1         H1-1b           2408 30         M34         HSS6K6W4         000         14,5         000         0         V         149,039         216,297         38,625         38,625         1         H1-1b           2409 30         M35         HSS6K6W4         000         14,5         000         0         V         149,039         216,297         38,625         38,625         1         H1-1b           2411 30         M36         HSS6K6W4         000         14,5         000         0         V         149,039         216,297         38,625         38,625         1         H1-1b           2411 30         M38         HSS6K6W4         000         14,5         000         0         V         149,039         216,297         38,625         38,625         1         H1-1b           2413 30 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>														
\$\frac{9406}{400}   \$\frac{30}{30}   \$\frac{M32}{32}   \$\frac{8580844}{300}   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$2408.30   \$13.4   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$2409.30   \$30. \$M35   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1410.30   \$16.297   \$36.825   \$36.825   \$1.11-10   \$1411.30   \$M36   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1411.30   \$M37   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1411.30   \$M37   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1413.30   \$M38   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1413.30   \$M39   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1413.30   \$M40   \$18580844   \$0.00   \$14.5   \$0.00   \$0.7   \$149.039   \$216.297   \$36.825   \$36.825   \$1.11-10   \$1415.30   \$1.11-10								_						
2407 30   M33   HSSSKÖK4   .000   14.5   .000   0   v   149.039   216.297   38.625   38.625   1   H1-1b														
2408 30         M34         HSSSKØAV         .000         14.5         .000         0         v 149 039         216 297         38.625         38.625         1         H1-1b           2410 30         M35         HSSSKØAV         .000         14.5         .000         0         v 149.039         216.297         38.625         38.625         1         H1-1b           2411 30         M36         HSSSKØAV         .000         14.5         .000         0         v 149.039         216.297         38.625         38.625         1         H1-1b           2411 30         M37         HSSSKØAV         .000         14.5         .000         0         v 149.039         216.297         38.625         38.625         1         H1-1b           2413 30         M40         HSSSKØAV         .000         14.5         .000         0         v 149.039         216.297         38.625         38.625         1         H1-1b           2414 30         M41         HSSSKØAV         .000         14.5         .000         0         v 149.039         216.297         38.625         38.625         1         H1-1b           2416 30         M42         HSSSKØAV         .000         14.5 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td>_</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>							_							
2410   30   M35														
2411 30   M36								_						
Authorst														
2412   30   M38   HSS6K6X4   .014   14.5   .000   0   v   149.039   216.297   38.625   38.625   1   H1-1b							-	_						
ABSABANA							_							
Best								_						
Automatic   Auto														
Auto								_						1
August   A								У						
Responsible							_	У						
2419 30         M45         HSSEX6X4         .000         14.5         .000         0         y         149.039         216.297         38.625         38.625         1         H1-1b           2420 30         M46         HSSEX6X4         .000         14.5         .000         0         y         149.039         216.297         38.625         38.625         1         H1-1b           2421 30         M48         HSSEX6X4         .000         14.5         .000         0         y         149.039         216.297         38.625         38.625         1         H1-1b           2423 30         M49         HSSEX6X4         .000         14.5         .000         0         y         149.039         216.297         38.625         38.625         1         H1-1b           2424 30         M50         HSSEX6X4         .000         14.5         .000         0         2         149.039         216.297         38.625         38.625         1         H1-1b           2425 30         M51         HSSEX6X4         .000         14.5         .000         0         2         149.039         216.297         38.625         38.625         1         H1-1b           2427 30								У						
2420   30   M46   HSSEX6X4   .000   14.5   .000   0   y   149.039   216.297   38.625   38.625   1   H1-1b   2421   30   M47   HSS6X6X4   .000   14.5   .000   0   y   149.039   216.297   38.625   38.625   1   H1-1b   2422   30   M48   HSSEX6X4   .000   14.5   .000   0   y   149.039   216.297   38.625   38.625   1   H1-1b   2423   30   M49   HSSEX6X4   .000   14.5   .000   0   v   149.039   216.297   38.625   38.625   1   H1-1b   2424   30   M50   HSSEX6X4   .000   14.5   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2425   30   M51   HSSEX6X4   .000   14.5   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2426   30   M52   HSSEX6X4   .000   14.5   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2427   30   M53   HSSEX6X4   .000   14.5   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2428   30   M54   HSSEX6X4   .000   0   14.5   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2428   30   M54   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2429   30   M55   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2429   30   M55   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2429   30   M55   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2430   30   M56   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2431   30   M57   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2432   30   M58   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2433   30   M58   HSSEX6X4   .000   0   .000   0   z   149.039   216.297   38.625   38.625   1   H1-1b   2433   30   M59   HSSEX6X4   .000   0   .000   0   z   148.29   216.297   38.625   38.625   1   H1-1b   2436   30   M60   HSSEX6X4   .000   0   .000   0   z   148.29   216.297   38.625   38.625   1   H1-1b   2437   30   M59   HS		M44			14.5		0	У					1	
2421 30		M45					0	У					<u>1</u>	
2422   30   M48		M46		.000	14.5	.000	0	У					1	
2423         30         M49         HSS6X6X4         .000         14.5         .000         0         y         149.039         216.297         38.625         38.625         1         H1-1b           2424         30         M50         HSS6X6X4         .000         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2425         30         M51         HSS6X6X4         .001         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2426         30         M52         HSS6X6X4         .001         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2427         30         M53         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2429         30         M56         HSS6X6X4         .000         0         0         y         100.047         216.297         38.625         38.625				.000		.000	0	٧	149.039					
2424 30         M50         HSS6X6X4         .000         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2425 30         M51         HSS6X6X4         .000         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2426 30         M52         HSS6X6X4         .013         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2427 30         M53         HSS6X6X4         .000         0         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2428 30         M54         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2430 30         M55         HSS6X6X4         .000         0         .000         0         y         118.296         216.297         38.625         38.625         1         H1-1b           2431 30         <				.000	14.5		0	У					1	
2425 30         M51         HSS6X6X4         .000         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2426 30         M52         HSS6X6X4         .013         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2427 30         M53         HSS6X6X4         .000         0         .000         0         149.039         216.297         38.625         38.625         1         H1-1b           2428 30         M54         HSS6X6X4         .000         0         .000         0         y 100.047         216.297         38.625         38.625         1         H1-1b           2430 30         M56         HSS6X6X4         .017         0         .000         0         y 71.878         216.297         38.625         38.625         1         H1-1b           2431 30         M57         HSS6X6X4         .000         0         .000         0         y 118.344         216.297         38.625         38.625         1         H1-1b           2433 30         M59         HSS6X6X4         .000         0<							0	У						
2426         30         M52         HSS6X6X4         .013         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2427         30         M53         HSS6X6X4         .000         0         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2428         30         M54         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2430         30         M56         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2431         30         M56         HSS6X6X4         .000         0         .000         0         y         118.296         216.297         38.625         38.625         1         H1-1b           2432         30         M58         HSS6X6X4         .000         0         .000         0         y         118.344         216.297         38.625         38.625								Z						
2427 30         M53         HSS6K6X4         .000         14.5         .000         0         z         149.039         216.297         38.625         38.625         1         H1-1b           2428 30         M54         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2429 30         M55         HSS6X6X4         .000         0         .000         0         y         100.047         216.297         38.625         38.625         1         H1-1b           2430 30         M56         HSS6X6X4         .017         0         .000         0         y         71.878         216.297         38.625         38.625         1         H1-1b           2431 30         M57         HSS6X6X4         .000         0         .000         0         y         118.296         216.297         38.625         38.625         1         H1-1b           2432 30         M58         HSS6X6X4         .000         0         .000         0         71.087         216.297         38.625         38.625         1         H1-1b           2435 30         M60         HSS							0	Z						
2428 30         M54         HSS6X6X4         .000         0         .000         0         y 100.047         216.297         38.625         38.625         1 H1-1b           2429 30         M55         HSS6X6X4         .000         0         .000         0         y 100.047         216.297         38.625         38.625         1 H1-1b           2430 30         M56         HSS6X6X4         .000         0         .000         0         y 71.878         216.297         38.625         38.625         1 H1-1b           2431 30         M57         HSS6X6X4         .000         0         .000         0         y 118.296         216.297         38.625         38.625         1 H1-1b           2432 30         M58         HSS6X6X4         .000         0         .000         0         y 71.087         216.297         38.625         38.625         1 H1-1b           2433 30         M59         HSS6X6X4         .006         .000         0         y 71.087         216.297         38.625         38.625         1 H1-1b           2434 30         M60         HSS6X6X4         .000         0         .000         0         y 64.559         216.297         38.625         38.625         1 H1							_							
2429 30         M55         HSS6X6X4         .000         0         .000         0         V         100.047         216.297         38.625         38.625         1         H1-1b           2430 30         M56         HSS6X6X4         .017         0         .000         0         y         71.878         216.297         38.625         38.625         1         H1-1b           2431 30         M57         HSS6X6X4         .000         0         .000         0         y         71.878         216.297         38.625         38.625         1         H1-1b           2432 30         M58         HSS6X6X4         .000         0         .000         0         y         71.874         216.297         38.625         38.625         1         H1-1b           2433 30         M59         HSS6X6X4         .016         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2435 30         M61         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2435 30         M62														
2430 30         M56         HSS6X6X4         .017         0         .000         0         y         71.878         216.297         38.625         38.625         1         H1-1b           2431 30         M57         HSS6X6X4         .000         0         .000         0         y         118.296         216.297         38.625         38.625         1         H1-1b           2432 30         M58         HSS6X6X4         .000         0         .000         0         y         118.344         216.297         38.625         38.625         1         H1-1b           2433 30         M59         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2435 30         M60         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436 30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437 30         M62A					-			У						
2431 30         M57         HSS6X6X4         .000         0         .000         0         Y         118.296         216.297         38.625         38.625         1         H1-1b           2432 30         M58         HSS6X6X4         .000         0         .000         0         y         118.344         216.297         38.625         38.625         1         H1-1b           2433 30         M59         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2435 30         M60         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436 30         M61         HSS6X6X4         .016         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436 30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437 30         M59A					0		0	У						
2432 30         M58         HSS6X6X4         .000         0         .000         0         y         118.344         216.297         38.625         38.625         1         H1-1b           2433 30         M59         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2434 30         M60         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2435 30         M61         HSS6X6X4         .001         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436 30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437 30         MS9A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2439 30         M61A					0		0	У						
2433         30         M59         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2434         30         M60         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2435         30         M61         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436         30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437         30         M59A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2438         30         M60A         W24X62         .032         11.53         .004         11.53         z         103.845         819         58.807         573.75		M57		.000	0	.000	0	٧						
2434 30         M60         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2435 30         M61         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436 30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437 30         M59A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2438 30         M60A         W24X62         .032         11.53         .004         11.53         z         103.845         819         58.807         573.75         1         H1-1b           2439 30         M61A         W24X62         .133         11.30         .006         22.84         z         103.754         819         58.807         573.75         1         H1-1b           2441 30         M63<								У						
2435         30         M61         HSS6X6X4         .000         0         .000         0         y         64.559         216.297         38.625         38.625         1         H1-1b           2436         30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437         30         M59A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2438         30         M60A         W24X62         .032         11.53         .004         11.53         z         103.845         819         58.807         573.75         1         H1-1b           2449         30         M61A         W24X62         .133         11.3         .006         22.84         z         103.754         819         58.807         573.75         1         H1-1b           2440         30         M62A         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75 <td></td> <td></td> <td></td> <td></td> <td>0</td> <td></td> <td>0</td> <td>У</td> <td></td> <td></td> <td></td> <td></td> <td>_1_</td> <td></td>					0		0	У					_1_	
2436         30         M62         HSS6X6X4         .016         0         .000         0         y         71.087         216.297         38.625         38.625         1         H1-1b           2437         30         M59A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2438         30         M60A         W24X62         .032         11.53         .004         11.53         z         103.845         819         58.807         573.75         1         H1-1b           2439         30         M61A         W24X62         .133         11.305         .006         22.84         z         103.754         819         58.807         573.75         1         H1-1b           2440         30         M62A         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2441         30         M63         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75					0			У					1	
2437 30         M59A         W24X62         .230         14.848         .008         0         z         60.139         819         58.807         573.75         1         H1-1b           2438 30         M60A         W24X62         .032         11.53         .004         11.53         z         103.845         819         58.807         573.75         1         H1-1b           2439 30         M61A         W24X62         .133         11.305         .006         22.84         z         103.754         819         58.807         573.75         1         H1-1b           2440 30         M62A         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2441 30         M63         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2442 30         M64         W24X62         .123         10.889         .006         0         z         111.828         819         58.807         573.75         1         H1-1b           2443 30 <t< td=""><td></td><td></td><td></td><td>.000</td><td>0</td><td></td><td>0</td><td>У</td><td></td><td></td><td></td><td></td><td>1</td><td></td></t<>				.000	0		0	У					1	
2438 30         M60A         W24X62         .032         11.53         .004         11.53         z 103.845         819         58.807         573.75         1         H1-1b           2439 30         M61A         W24X62         .133         11.305         .006         22.84         z 103.754         819         58.807         573.75         1         H1-1b           2440 30         M62A         W24X62         .133         11.3         .006         22.83         z 103.845         819         58.807         573.75         1         H1-1b           2441 30         M63         W24X62         .133         11.3         .006         22.83         z 103.845         819         58.807         573.75         1         H1-1b           2442 30         M64         W24X62         .123         10.889         .006         0         z 111.828         819         58.807         573.75         1         H1-1b           2443 30         M65         W24X84         .000         0         .000         0         z 164.553         1111.5         122.25         840         1         H1-1b           2445 30         M66         W24X62         .000         0         .000         <	2436 30	M62		.016		.000			71.087	216.297	38.625		1	
2439         30         M61A         W24X62         .133         11.305         .006         22.84         z         103.754         819         58.807         573.75         1         H1-1b           2440         30         M62A         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2441         30         M63         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2442         30         M64         W24X62         .123         10.889         .006         0         z         111.828         819         58.807         573.75         1         H1-1b           2443         30         M65         W24X84         .000         0         .000         0         z         164.553         1111.5         122.25         840         1         H1-1b           2444         30         M66         W24X62         .000         0         .000         0         z         103.845         819         58.807         573.75	2437 30	M59A	W24X62	.230	14.848	.008	0	Z		819	58.807	573.75	1	
2440 30         M62A         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2441 30         M63         W24X62         .133         11.3         .006         22.83         z         103.845         819         58.807         573.75         1         H1-1b           2442 30         M64         W24X62         .123         10.889         .006         0         z         111.828         819         58.807         573.75         1         H1-1b           2443 30         M65         W24X84         .000         0         .000         0         z         164.553         1111.5         122.25         840         1         H1-1b           2444 30         M66         W24X62         .000         0         .000         0         z         103.845         819         58.807         573.75         1         H1-1b           2445 30         M67         W24X62         .000         0         .000         0         z         103.845         819         58.807         573.75         1         H1-1b           2446 30         M68         W	2438 30	M60A	W24X62	.032	11.53	.004	11.53	Z	103.845	819	58.807	573.75	1	H1-1b
2441 30       M63       W24X62       .133       11.3       .006       22.83       z       103.845       819       58.807       573.75       1       H1-1b         2442 30       M64       W24X62       .123       10.889       .006       0       z       111.828       819       58.807       573.75       1       H1-1b         2443 30       M65       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b         2444 30       M66       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2445 30       M67       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2446 30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807	2439 30	M61A	W24X62	.133	11.305	.006	22.84	Z	103.754	819	58.807	573.75	1	H1-1b
2442 30       M64       W24X62       .123       10.889       .006       0       z       111.828       819       58.807       573.75       1       H1-1b         2443 30       M65       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b         2444 30       M66       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2445 30       M67       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2446 30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448 30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573	2440 30	M62A	W24X62	.133	11.3	.006	22.83	Z	103.845	819	58.807	573.75	1	H1-1b
2442 30       M64       W24X62       .123       10.889       .006       0       z       111.828       819       58.807       573.75       1       H1-1b         2443 30       M65       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b         2444 30       M66       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2445 30       M67       W24X62       .000       0       .000       0       z       103.754       819       58.807       573.75       1       H1-1b         2446 30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448 30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573	2441 30	M63	W24X62	.133	11.3	.006	22.83	Z	103.845	819	58.807	573.75	1	H1-1b
2443       30       M65       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b         2444       30       M66       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2445       30       M67       W24X62       .000       0       .000       0       z       103.754       819       58.807       573.75       1       H1-1b         2446       30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447       30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448       30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573.75       1       H1-1b         2449       30       M71       W24X84       .000       0       .000       0		M64			10.889									
2444 30       M66       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2445 30       M67       W24X62       .000       0       .000       0       z       103.754       819       58.807       573.75       1       H1-1b         2446 30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448 30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573.75       1       H1-1b         2449 30       M71       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b					0									
2445 30       M67       W24X62       .000       0       .000       0       z       103.754       819       58.807       573.75       1       H1-1b         2446 30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448 30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573.75       1       H1-1b         2449 30       M71       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b								_						
2446       30       M68       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2447       30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448       30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573.75       1       H1-1b         2449       30       M71       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b														
2447 30       M69       W24X62       .000       0       .000       0       z       103.845       819       58.807       573.75       1       H1-1b         2448 30       M70       W24X62       .000       0       .000       0       z       111.828       819       58.807       573.75       1       H1-1b         2449 30       M71       W24X84       .000       0       .000       0       z       164.553       1111.5       122.25       840       1       H1-1b														
2448 30     M70     W24X62     .000     0     .000     0     z     111.828     819     58.807     573.75     1     H1-1b       2449 30     M71     W24X84     .000     0     .000     0     z     164.553     1111.5     122.25     840     1     H1-1b														
2449 30 M71 W24X84 .000 0 .000 0 z 164.553 1111.5 122.25 840 1 H1-1b														
								-						

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
2451 30	M73	W24X62	.000	0	.000	0	z	103.754	819	58.807	573.75	1	H1-1b
2452 30	M74	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2453 30	M75	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2454 30	M76	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2455 30	M77	W24X62	.000	14.848	.000	0	z	60.139	819	58.807	573.75	1	H1-1b
2456 30	M78	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2457 30	M79	W24X62	.000	0	.000	0	z	103.754	819	58.807	573.75	1	H1-1b
2458 30	M80	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2459 30	M81	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2460 30	M82	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2461 31	M5	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2462 31	M6	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2463 31	M7	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2464 31	M8	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2465 31	M9	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2466 31	M10	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2467 31	M11	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2468 31	M12	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2469 31	M13	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2470 31	M14	W24X62	.000	0	.000	0	Z	128,792	819	58.807	573.75	1	H1-1b
2471 31	M15	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2472 31	M16	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2473 31	M17	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2474 31	M18	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2475 31	M19	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2476 31	M20	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2477 31	M21	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2478 31	M22	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2479 31	M23	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2480 31	M24	W24X62	.000	0	.000	0	z	130.955	819	58.807	573.75	1	H1-1b
2481 31	M25	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2482 31	M26	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2483 31	M27	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2484 31	M28	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2485 31	M29	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2486 31	M30	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2487 31	M31	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2488 31	M32	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2489 31	M33	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2490 31	M34	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2491 31	M35	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2492 31	M36	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625		1	H1-1b
2493 31	M37	HSS6X6X4	.000	14.5	.000	0	٧	149.039	216.297	38.625	38.625	1	H1-1b
2494 31	M38	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2495 31	M39	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2496 31	M40	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2497 31	M41	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2498 31	M42	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2499 31	M43	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2500 31	M44	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2501 31	M45	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297		38.625	1	H1-1b
2502 31	M46	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297		38.625	1	H1-1b
2503 31	M47	HSS6X6X4	.039	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2504 31	M48	HSS6X6X4	.039	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2505 31	M49	HSS6X6X4	.000	14.5	.000	0	У	149.039	216.297	38.625	38.625	1	H1-1b
2506 31	M50	HSS6X6X4	.000	14.5	.000	0	z		216.297		38.625	1	H1-1b
2507 31	M51	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
2508 31	M52	HSS6X6X4	.001	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2509 31	M53	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2510 31	M54	HSS6X6X4	.089	0	.000	0	٧	100.047	216.297	38.625	38.625	1	H1-1b
2511 31	M55	HSS6X6X4	.386	0	.000	0	У	100.047	216.297	38.625	38.625	1	H1-1a
2512 31	M56	HSS6X6X4	.002	0	.000	0	У	71.878	216.297	38.625	38.625	1	H1-1b
2513 31	M57	HSS6X6X4	.088	0	.000	0	У	118.296	216.297	38.625	38.625	1	H1-1b
2514 31	M58	HSS6X6X4	.320	0	.000	0	٧	118.344	216.297	38.625	38.625	1	H1-1a
2515 31	M59	HSS6X6X4	.000	0	.000	0	v	71.087	216.297	38.625	38.625	1	H1-1b
2516 31	M60	HSS6X6X4	.473	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1a
2517 31	M61	HSS6X6X4	.474	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1a
2518 31	M62	HSS6X6X4	.001	0	.000	0	V	71.087	216.297	38.625	38.625	1	H1-1b
2519 31	M59A	W24X62	.000	0	.000	0	z	60.139	819	58.807	573.75	1	H1-1b
2520 31	M60A	W24X62	.001	11.3	.000	11.53	V	103.845	819	58.807	216.96	1.316	H1-1b
2521 31	M61A	W24X62	.000	0	.000	0	z	103.754	819	58.807	573.75	1	H1-1b
2522 31	M62A	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2523 31	M63	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2524 31	M64	W24X62	.000	0	.000	0	z	111.828	819	58.807	573.75	1	H1-1b
2525 31	M65	W24X84	.000	0	.000	0	z	164.553	1111.5	122.25	840	1	H1-1b
2526 31	M66	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2527 31	M67	W24X62	.000	0	.000	0	z	103.754	819	58.807	573.75	1	H1-1b
2528 31	M68	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2529 31	M69	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2530 31	M70	W24X62	.000	0	.000	0	z	111.828	819	58.807	573.75	1	H1-1b
2531 31	M71	W24X84	.000	0	.000	0	Z	164.553	1111.5	122.25	840	1	H1-1b
2532 31	M72	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2533 31	M73	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b
2534 31	M74	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2535 31	M75	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2536 31	M76	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2537 31	M77	W24X62	.000	14.848	.000	0	V	60.139	819	58.807	147.413		
2538 31	M78	W24X62	.000	0	.000	0	z	103.845	819	58.807	573.75	1	H1-1b
2539 31	M79	W24X62	.000	0	.000	0	z	103.754	819	58.807	573.75	1	H1-1b
2540 31	M80	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2541 31	M81	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2542 31	M82	W24X62	.000	0	.000	0	z	111.828	819	58.807	573.75	1	H1-1b
2543 32	M5	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2544 32	M6	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2545 32	M7	W24X62	.000	0	.000	0	z	128.792	819	58.807	573.75	1	H1-1b
2546 32	M8	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2547 32	M9	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2548 32	M10	W24X62	.000	0	.000	0	Z	128.792	819	58.807			H1-1b
2549 32	M11	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2550 32	M12	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2551 32	M13	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2552 32	M14	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75		H1-1b
2553 32	M15	W24X62	.000	0	.000	0	Z	130.955	819	58.807		1	H1-1b
2554 32	M16	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2555 32	M17												
2556 32	M18	W24X62 W24X62	.000	0	.000	0	Z	128.792 130.955	819 819	58.807 58.807	573.75 573.75	1	H1-1b
2557 32	M19 M20	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	H1-1b
2558 32		W24X62	.000	0	.000	0	Z	128.792	819	58.807		1	
2559 32	M21	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75	1	H1-1b
2560 32	M22	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2561 32	M23	W24X62	.000	0	.000	0	Z	128.792	819	58.807	573.75	1	H1-1b
2562 32	M24	W24X62	.000	0	.000	0	Z	130.955	819	58.807	573.75		H1-1b
2563 32	M25	W24X62	.000	0	.000	0	Z	128.792	819	58.807		1 670	H1-1b
2564 32	M26	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1.078	H1-10

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	. phi*Mnz	Cb	Eqn
2565 32	M27	HSS6X6X4	.236	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1a
2566 32	M28	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2567 32	M29	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1.678	H1-1b
2568 32	M30	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625	1.678	H1-1b
2569 32	M31	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2570 32	M32	HSS6X6X4	.000	14.5	.000	0	z	149.039	216.297	38.625	38.625	1	H1-1b
2571 32	M33	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625	1.678	H1-1b
2572 32	M34	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625	_	H1-1b
2573 32	M35	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2574 32	M36	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625	1	H1-1b
2575 32	M37	HSS6X6X4	.000	14.5	.000	0	v	149.039	216.297	38.625	38.625		H1-1b
2576 32	M38	HSS6X6X4	.243	14.5	.000	0	V	149.039	216.297	38.625	38.625		
2577 32	M39	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2578 32	M40	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2579 32	M41	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625		H1-1b
2580 32	M42	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1b
2581 32	M43	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2582 32	M44	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2583 32	M45	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	_	H1-1b
2584 32	M46	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1b
2585 32	M47	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2586 32	M48	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1	H1-1b
2587 32	M49	HSS6X6X4	.000	14.5	.000	0	V	149.039	216.297	38.625	38.625	1.678	H1-1b
2588 32	M50	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625		H1-1b
2589 32	M51	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1b
2590 32	M52	HSS6X6X4	.250	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1	H1-1a
2591 32	M53	HSS6X6X4	.000	14.5	.000	0	Z	149.039	216.297	38.625	38.625	1.678	H1-1b
2592 32	M54	HSS6X6X4	.005	0	.000	0	V	100.047	216.297	38.625	38.625	1.070	H1-1b
2593 32	M55	HSS6X6X4	.003	0	.000	0	V	100.047	216.297	38.625	38.625	1	H1-1b
2594 32	M56	HSS6X6X4	.281	0	.000	0	V	71.878	216.297	38.625	38.625	1	H1-1a
2595 32	M57	HSS6X6X4	.003	0	.000	0	V	118.296	216.297	38.625	38.625	1	H1-1b
2596 32	M58	HSS6X6X4	.005	0	.000	0	V	118.344	216.297	38.625	38.625	1	H1-1b
2597 32	M59	HSS6X6X4	.290	0	.000	0	V	71.087	216.297	38.625	38.625	1	H1-1a
2598 32	M60	HSS6X6X4	.001	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1b
2599 32	M61	HSS6X6X4	.002	0	.000	0	V	64.559	216.297	38.625	38.625	1	H1-1b
2600 32	M62	HSS6X6X4	.299	0	.000	0	V	71.087	216.297	38.625	38.625	1	H1-1a
2601 32	M59A	W24X62	.000	0	.000	0	_	60.139	819	58.807	573.75	1	H1-1b
2602 32	M60A	W24X62	.002	11.53	.000	11.53	Z	103.845	819	58.807	216.96		H1-1b
2603 32	M61A	W24X62	.002	0	.000	0	Z	103.754	819	58.807	573.75	1.010	H1-1b
2604 32	M62A	W24X62	.000	0	.000	0	Z	103.734	819	58.807	573.75	1	H1-1b
2605 32	M63	W24X62	.000		.000			103.845	819	58.807		1	H1-1b
2606 32	M64	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b
2607 32	M65	W24X84	.000	0	.000	0	Z	164.553	1111.5	122.25	840	1	H1-1b
2608 32	M66	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2609 32	M67	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b
2610 32	M68	W24X62	.000	0	.000	0	Z	103.734	819	58.807	573.75	1	H1-1b
					.000						573.75		
2611 32 2612 32	M69 M70	W24X62 W24X62	.000	0	.000	0	Z	103.845 111.828	819 819	58.807 58.807	573.75	1	H1-1b
	M71				.000	-	Z			122.25		1	H1-1b
2613 32 2614 32		W24X84 W24X62	.000	0		0	Z	164.553 103.845	1111.5		840 573.75		
	M72		.000	0	.000	0	Z		819	58.807	573.75	1	H1-1b
2615 32	M73	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b
2616 32	M74	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2617 32	M75	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2618 32	M76	W24X62	.000	15 152	.000	15 152	Z	111.828	819	58.807	573.75	1	H1-1b
2619 32	M77	W24X62	.000	15.152	.000	15.152		60.139	819		112.034		H1-1b
2620 32	<u>M78</u>	W24X62	.000	0	.000	0	Z		819	58.807	573.75	1	H1-1b
2621 32	M79	W24X62	.000	0	.000	0	Z	103.754	819	58.807	573.75	1	H1-1b

Company Designer Job Number : Parsons Brinckerhoff: Paul Oh May 23, 2012 2:21 PM

: 173133C CIC Det 5-9 Checked By:

	LC	Member	Shape	UC Max	Loc[ft]	Shear UC	Loc[ft]	Dir	phi*Pnc[k]	phi*Pnt[k]	phi*Mny	phi*Mnz	Cb	Egn
2622	32	M80	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2623	32	M81	W24X62	.000	0	.000	0	Z	103.845	819	58.807	573.75	1	H1-1b
2624	32	M82	W24X62	.000	0	.000	0	Z	111.828	819	58.807	573.75	1	H1-1b

# Base Load Reactions

CIC – RA 5-9; Ft. Stewart, Georgia

: Parsons Brinckerhoff: Paul Oh

May 23, 2012 2:24 PM Checked By:\_ Company Designer Job Number : 173133C CIC Det 5-9

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
399	13	N15	777	0	78.036	Ó	O T	NC
400	13	N16	0	0	40.951	0	0	NC
401	13	N17	0	0	40.17	0	0	NC
402	13	N18	0	0	78.346	0	0	NC
403	13	N19	0	0	78.346	0	0	NC
404	13	N20	0	0	40.17	0	0	NC
405	13	N24	0	0	39.456	0	0	NC
406	13	N23	0	0	69.721	0	0	NC
407	13	N22	0	0	70.004	0	0	NC
408	13	N21	0	0	39.456	0	0	NC
409	13	N25	.251	0	20.218	0	0	NC
410	13	N26	0	-10.893	45.997	0	0	NC
411	13	N27	0	-11.322	46.234	0	0	NC
412	13	N28	0	0	19.817	0	0	NC
413	13	N1000	NC	NC	LOCKED	NC NC	NC NC	NC
414	13	N1001	NC 0	NC 0	LOCKED	NC	NC	NC
415	13	Totals: COG (ft):	0	0 V: 71 677	1496.602			
416	13 14	N2	X: 30.667 .538	Y: 71.677	Z: 14.447 46.81	0	0	NC
417	14	N2 N1	.538	0	23.624	0	0	NC NC
419	14 14	N3	0	0	46.043	0	0	NC NC
420	14	N4	0	17.632	27.229	0	0	NC NC
421	14	N5	0	12.604	46.057	0	0	NC NC
422	14	N6	0	0	79.956	0	0	NC
423	14	N7	0	0	79.956	0	0	NC
424	14	N8	0	-10.941	38.06	0	0	NC
425	14	N12	0	0	35.497	0	0	NC
426	14	N11	0	0	69.039	0	0	NC
427	14	N10	0	0	69.039	0	0	NC
428	14	N9	0	-5.036	31.019	0	0	NC
429	14	N13	0	0	35.497	0	0	NC
430	14	N14	0	0	69.039	0	0	NC
431	14	N15	687	0	68.776	0	0	NC
432	14	N16	0	0	36.207	0	0	NC
433	14	N17	0	0	35.49	0	0	NC
434	14	N18	0	0	69.024	0	0	NC
435	14	N19	0	0	69.024	0	0	NC
436	14	N20	0	0	35.49	0	0	NC
437	14	N24	0	0	34.861	0	0	NC
438	14	N23	0	0	60.587	0	0	NC
439	14	N22	0	0	60.823	0	0	NC
440	14	N21	0	0	34.861	0	0	NC
441	14	N25	.149	0	17.891	0	0	NC NC
442	14	N26	0	-10.937	41.606	0	0	NC NC
443	14	N27	0	-11.295	41.725	0	0	NC NC
444	14	N28	0	0	17.562	0	0	NC NC
445	14 14	N1000	NC NC	NC NC	LOCKED	NC NC	NC NC	NC NC
446	<u>14</u> 14	N1001	0	-7.973	1320.794	NC	NC	NC
447	14	Totals: COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			
448	14 15	N2	-5.382	0	42.588	0	0	NC
450	15	N1	-5.36 <u>2</u> 0	0	23.624	0	0	NC NC
451	15 15	N3	0	0	50.265	0	0	NC NC
452	15	N4	0	18.994	28.545	0	0	NC NC
453	15	N5	0	13.898	47.701	0	0	NC NC
454	15	N6	0	0	79.956	0	0	NC
455	15	N7	0	0	79.956	0	0	NC
	- 10	147			, , , , , , ,			.,,,

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
456	15	N8	0	-9.579	36.743	0	0	NC
457	15	N12	0	0	35.497	0	0	NC
458	15	N11	0	0	69.039	0	0	NC
459	15	N10	0	0	69.039	0	0	NC
460	15	N9	0	-3.743	29.376	0	0	NC
461	15	N13	0	0	35.497	0	0	NC
462	15	N14	0	0	69.039	0	0	NC
463	15	N15	-6.419	0	64.722	0	0	NC
464	15	N16	0	0	40.261	0	0	NC
465	15	N17	0	0	35.49	0	0	NC
466	15	N18	0	0	69.024	0	0	NC
467	15	N19	0	0	69.024	0	0	NC
468	15	N20	0	0	35.49	0	0	NC
469	15	N24	0	0	34.861	0	0	NC
470	15	N23	0	0	61.446	0	0	NC
471	15	N22	0	0	61.718	0	0	NC
472	15	N21	0	0	34.861	0	0	NC
473	15	N25	-5.399	0	13.967	0	0	NC
474	15	N26	0	-9.578	44.635	0	0	NC
475	15	N27	0	-9.992	40.866	0	0	NC
476	15	N28	0	0	17.562	0	0	NC
477	15	N1000	NC	NC	LOCKED	NC	NC	NC
478	15	N1001	NC	NC	LOCKED	NC	NC	NC
479	15	Totals:	-17.199	0	1320.794			
480	15	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			
481	16	N2	.637	0	46.881	0	0	NC
482	16	N1	0	0	23.624	0	0	NC
483	16	N3	0	0	45.972	0	0	NC
484	16	N4	0	39	9.808	0	0	NC
485	16	N5	0	-2.555	26.81	0	0	NC
486	16	N6	0	0	79.956	0	0	NC
487	16	N7	0	0	79.956	0	0	NC
488	16	N8	0	-28.962	55.48	0	0	NC
489	16	N12	0	0	35.497	0	0	NC
490	16	N11	0	0	69.039	0	0	NC
491	16	N10	0	0	69.039	0	0	NC
492	16	N9	0	-20.182	50.266	0	0	NC
493	16	N13	0	0	35.497	0	0	NC
494	16	N14	0	0	69.039	0	0	NC
495	16	N15	691	0	68.774	0	0	NC
496	16	N16	0	0	36.209	0	0	NC
497	16	N17	0	0	35.49	0	0	NC
498	16	N18	0	0	69.024	0	0	NC
499	16	N19	0	0	69.024	0	0	NC
500	16	N20	0	0	35.49	0	0	NC
501	16	N24	0	0	34.861	0	0	NC
502	16	N23	0	0	49.697	0	0	NC
503	16	N22	0	0	49.914	0	0	NC
504	16	N21	0	0	34.861	0	0	NC
505	16	N25	.053	0	17.823	0	0	NC
506	16	N26	0	-27.489	52.583	0	0	NC
507	16	N27	0	-27.818	52.615	0	0	NC
508	16	N28	0	0	17.562	0	0	NC
509	16	N1000	NC	NC	LOCKED	NC	NC	NC
510	16	N1001	NC	NC	LOCKED	NC	NC	NC
511	16	Totals:	0	-107.394	1320.794			
512	16	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
513	17	N2	-34.123	0	22.09	Ó	Ö	NC
514	17	N1	0	0	23.624	0	0	NC
515	17	N3	0	0	70.764	0	0	NC
516	17	N4	0	19.557	29.09	0	0	NC
517	17	N5	0	13.362	47.02	0	0	NC
518	17	N6	0	0	79.956	0	0	NC
519	17	N7	0	0	79.956	0	0	NC
520	17	N8	0	-9.015	36.198	0	0	NC
521	17	N12	0	0	35.497	0	0	NC
522	17	N11	0	0	69.039	0	0	NC
523	17	N10	0	0	69.039	0	0	NC
524	17	N9	0	-4.279	30.056	0	0	NC
525	17	N13	0	0	35.497	0	0	NC
526	17	N14	0	0	69.039	0	0	NC
527	17	N15	-36.556	0	43.405	0	0	NC
528	17	N16	0	0	61.577	0	0	NC
529	17	N17	0	0	35.49	0	0	NC
530	17	N18	0	0	69.024	0	0	NC
531	17	N19	0	0	69.024	0	0	NC
532	17	N20	0	0	35.49	0	0	NC
533	17	N24	0	0	34.861	0	0	NC
534	<u> 17</u>	N23	0	0	61.546	0	0	NC
535	17	N22	0	0	61.581	0	0	NC
536	17	N21	0	0	34.861	0	0	NC
537	17	N25	-36.715	0	-8.184	0	0	NC
538	17	N26	0	-9.787	66.923	0	0	NC
539	17	N27	0	-9.839	40.765	0	0	NC
540	17	N28	0	0	17.562	0	0	NC NC
541	17	N1000	NC NC	NC NC	LOCKED	NC	NC NC	NC NC
542	17	N1001	NC 407.204	NC 0	LOCKED	NC	NC	NC
543	17	Totals:	-107.394	0	1320.794			
544 545	<u>17</u> 18	COG (ft): N2	X: 30.667 .641	Y: 71.679	Z: 14.44 51.477	0	0	NC
546	18	N1	.041	0	25.93	0	0	NC NC
547	18	N3	0	0	50.563	0	0	NC NC
548	18	N4	0	6.381	17.277	0	0	NC
549	18	N5	0	2.934	36.723	0	0	NC NC
550	18	N6	0	0	88.045	0	0	NC
551	18	N7	0	0	88.045	0	0	NC NC
552	18	N8	0	-25.051	54.379	0	0	NC
553	18	N12	0	0	39.008	0	0	NC
554	18	N11	0	0	76.032	0	0	NC
555	18	N10	0	0	76.032	0	0	NC
556	18	N9	0	-16.457	47.925	0	0	NC
557	18	N13	0	0	39.008	0	0	NC
558	18	N14	0	0	76.032	0	Ö	NC
559	18	N15	759	0	75.718	0	0	NC
560	18	N16	0	0	39.768	0	0	NC
561	18	N17	0	0	39	0	0	NC
562	18	N18	0	0	76.015	0	0	NC
563	18	N19	0	0	76.015	0	0	NC
564	18	N20	0	0	39	0	0	NC
565	18	N24	0	0	38.307	0	0	NC
566	18	N23	0	0	58.836	0	0	NC
567	18	N22	0	0	59.086	0	0	NC
568	18	N21	0	0	38.307	0	0	NC
569	18	N25	.118	0	19.56	0	0	NC

: Parsons Brinckerhoff: Paul Oh

May 23, 2012 2:24 PM Checked By:\_ Company Designer Job Number : 173133C CIC Det 5-9

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
570	18	N26	0	-23.986	53.598	0	0	NC
571	18	N27	0	-24.366	53.708	0	0	NC
572	18	N28	0	0	19.254	0	0	NC
573	18	N1000	NC	NC	LOCKED	NC	NC	NC
574	18	N1001	NC	NC	LOCKED	NC	NC	NC
575	18	Totals:	0	-80.546	1452.65			
576	18	COG (ft):	X: 30.667	Y: 71.678	Z: 14.446			
577	19	N2	-25.429	0	32.883	0	0	NC
578	19	N1	0	0	25.93	0	0	NC
579	19	N3	0	0	69.157	0	0	NC
580	19	N4	0	21.341	31.739	0	0	NC
581	19	N5	0	14.871	51.88	0	0	NC
582	19	N6	0	0	88.045	0	0	NC
583	19	N7	0	0	88.045	0	0	NC
584	19	N8	0	-10.09	39.917	0	0	NC
585	19	N12	0	0	39.008	0	0	NC
586	19	N11	0	0	76.032	0	0	NC
587	19	N10	0	0	76.032	0	0	NC
588	19	N9	0	-4.53	32.768	0	0	NC
589	19	N13	0	0	39.008	0	0	NC
590	19	N14	0	0	76.032	0	0	NC
591	19	N15	-27.658	0	56.692	0	0	NC
592	19	N16	0	0	58.794	0	0	NC
593	19	N17	0	0	39	0	0	NC
594	19	N18	0	0	76.015	0	0	NC
595	19	N19	0	0	76.015	0	0	NC
596	19	N20	0	0	39	0	0	NC
597	19	N24	0	0	38.307	0	0	NC
598	19	N23	0	0	67.723	0	0	NC
599	19	N22	0	0	67.837	0	0	NC
600	19	N21	0	0	38.307	0	0	NC
601	19	N25	-27.458	0	.055	0	0	NC
602	19	N26	0	-10.71	64.353	0	0	NC
603	<u>19</u>	N27	0	-10.882	44.821	0	0	NC
604	<u> 19</u>	N28	0	0	19.254	0	0	NC
605	<u>19</u>	N1000	NC	NC	LOCKED	NC	NC	NC
606	19	N1001	NC	NC	LOCKED	NC	NC	NC
607	19	Totals:	-80.545	0	1452.65			
608	19	COG (ft):	X: 30.667	Y: 71.678	Z: 14.446	0	0	NC
609	20	N2	.566	0	51.424 25.93	0	0	NC NC
610	20 20	N1 N3	0	0		0	0	NC NC
612	20	N4	0	19.897	50.616 30.343	0	0	NC NC
613	20	N5	0	14.303	51.158	0	0	NC NC
614	20	N6	0	0	88.045	0	0	NC NC
615	20	N7	0	0	88.045	0	0	NC NC
616	20	N8	0	-11.535	41.313	0	0	NC NC
617	20	N12	0	0	39.008	0	0	NC NC
618	20	N11	0	0	76.032	0	0	NC NC
619	20	N10	0	0	76.032	0	0	NC NC
620	20	N9	0	-5.098	33.49	0	0	NC NC
621	20	N13	0	0	39.008	0	0	NC NC
622	20	N14	0	0	76.032	0	0	NC NC
623	20	N15	756	0	75.72	0	0	NC NC
624	20	N16	0	0	39.766	0	0	NC NC
625	20	N17	0	0	39	0	0	NC
626	20	N18	0	0	76.015	0	0	NC NC
020	20	1110	U		10.010		U	110

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
627	20	N19	0	0	76.015	0	0	NC
628	20	N20	0	0	39	0	0	NC
629	20	N24	0	0	38.307	0	0	NC
630	20	N23	0	0	67.004	0	0	NC
631	20	N22	0	0	67.268	0	0	NC
632	20	N21	0	0	38.307	0	0	NC
633	20	N25	.19	0	19.611	0	0	NC
634	20	N26	0	-11.573	45.365	0	0	NC
635	20	N27	0	-11.974	45.541	0	0	NC
636	20	N28	0	0	19.254	0	0	NC
637	20	N1000	NC	NC	LOCKED	NC	NC	NC
638	20	N1001	NC	NC	LOCKED	NC	NC	NC
639	20	Totals:	0	-5.98	1452.65			
640	20	COG (ft):	X: 30.667	Y: 71.678	Z: 14.446		_	
641	21	N2	-3.874	0	48.257	0	0	NC
642	21	N1	0	0	25.93	0	0	NC
643	21	N3	0	0	53.783	0	0	NC
644	21	N4	0	20.918	31.33	0	0	NC
645	21	N5	0	15.274	52.391	0	0	NC
646	21	N6	0	0	88.045	0	0	NC
647	21	N7	0	0	88.045	0	0	NC NC
648	21	N8	0	-10.513	40.326	0	0	NC NC
649	21	N12	0	0	39.008	0	0	NC NC
650 651	21	N11	0	0	76.032	0	0	NC NC
651	21	N10	0	0	76.032	0	0	NC NC
652	21	N9		-4.128	32.258	0	0	NC NC
653 654	21 21	N13 N14	0	0	39.008 76.032	0	0	NC NC
655	<u>21</u> 21	N15	-5.054	0	76.032	0	0	NC NC
656	21	N16	-5.054	0	42.807	0	0	NC NC
657	21	N17	0	0	39	0	0	NC NC
658	21	N18	0	0	76.015	0	0	NC NC
659	21	N19	0	0	76.015	0	0	NC NC
660	21	N20	0	0	39	0	0	NC NC
661	21	N24	0	0	38.307	0	0	NC NC
662	21	N23	0	0	67.648	0	0	NC
663	21	N22	0	0	67.94	0	0	NC
664	21	N21	0	0	38.307	0	0	NC
665	21	N25	-3.972	0	16.668	0	0	NC
666	21	N26	0	-10.554	47.637	0	0	NC
667	21	N27	0	-10.997	44.897	0	0	NC
668	21	N28	0	0	19.254	0	0	NC
669	21	N1000	NC	NC	LOCKED	NC	NC	NC
670	21	N1001	NC	NC	LOCKED	NC	NC	NC
671	21	Totals:	-12.9	0	1452.65			
672	21	COG (ft):	X: 30.667	Y: 71.678	Z: 14.446			
673	22	N2	.352	0	28.107	0	0	NC
674	22	N1	0	0	14.174	0	0	NC
675	22	N3	0	0	27.605	0	0	NC
676	22	N4	0	10.013	15.79	0	0	NC
677	22	N5	0	7.065	27.003	0	0	NC
678	22	N6	0	0	47.974	0	0	NC
679	22	N7	0	0	47.974	0	0	NC
680	22	N8	0	-7.131	23.383	0	0	NC
681	22	N12	0	0	21.298	00	0	NC
682	22	N11	0	0	41.423	0	0	NC
683	22	N10	0	0	41.423	0	0	NC

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
684	22	N9	0	-3.518	19.243	0	0	NC
685	22	N13	0	0	21.298	0	0	NC
686	22	N14	0	0	41.423	0	0	NC
687	22	N15	413	0	41.265	0	0	NC
688	22	N16	0	0	21.725	0	0	NC
689	22	N17	0	0	21.294	0	0	NC
690	22	N18	0	0	41.415	0	0	NC
691	22	N19	0	0	41.415	0	0	NC
692	22	N20	0	0	21.294	0	0	NC
693	22	N24	0	0	20.917	0	0	NC
694	22	N23	0	0	36.005	0	0	NC
695	22	N22	0	0	36.141	0	0	NC
696	22	N21	0	0	20.917	0	0	NC
697	22	N25	.061	0	10.715	0	0	NC
698	22	N26	0	-7.098	25.337	0	0	NC
699	22	N27	0	-7.304	25.382	0	0	NC
700	22	N28	0	0	10.537	0	0	NC
701	22	N1000	NC	NC	LOCKED	NC NC	NC	NC
702	22	N1001	NC	NC	LOCKED	NC	NC	NC
703	22	Totals:	0	-7.973	792.476			
704	22	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			110
705	23	N2	-5.567	0	23.885	0	0	NC
706	23	N1	0	0	14.174	0	0	NC
707	23	N3	0	0	31.827	0	0	NC
708	23	N4	0	11.375	17.106	0	0	NC
709	23	N5	0	8.359	28.646	0	0	NC
710	23	N6	0	0	47.974	0	0	NC
711	23	N7	0	0	47.974	0	0	NC NC
712	23	N8	0	-5.769	22.067	0	0	NC
713	23	N12	0	0	21.298	0	0	NC NC
714	23	N11	0	0	41.423	0	0	NC NC
715 716	23 23	N10 N9	0	-2.225	41.423	0	0	NC NC
717	<u>23</u> 23	N13	0	0	17.599 21.298	0	0	NC NC
718	23	N14	0	0	41.423	0	0	NC NC
719	23	N15	-6.145	0	37.211	0	0	NC NC
720	23	N16	0	0	25.779	0	0	NC NC
721	23	N17	0	0	21.294	0	0	NC
722	23	N18	0	0	41.415	0	0	NC
723	23	N19	0	0	41.415	0	0	NC
724	23	N20	0	0	21.294	0	0	NC
725	23	N24	0	0	20.917	0	0	NC
726	23	N23	0	0	36.864	0	0	NC
727	23	N22	0	0	37.037	0	0	NC
728	23	N21	0	0	20.917	0	0	NC
729	23	N25	-5.488	0	6.79	0	0	NC
730	23	N26	0	-5.739	28.366	0	0	NC
731	23	N27	0	-6.001	24.523	0	0	NC
732	23	N28	0	0	10.537	0	0	NC
733	23	N1000	NC	NC	LOCKED	NC	NC	NC
734	23	N1001	NC	NC	LOCKED	NC	NC	NC
735	23	Totals:	-17.199	0	792.476			
736	23	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			
737	24	N2	.452	0	28.178	0	0	NC
738	24	N1	0	0	14.174	0	0	NC
739	24	N3	0	0	27.534	0	0	NC
740	24	N4	0	-8.009	-1.631	0	0	NC

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
741	24	N5	0	-8.093	7.756	0	0	NC .
742	24	N6	0	0	47.974	0	0	NC
743	24	N7	0	0	47.974	0	0	NC
744	24	N8	0	-25.152	40.804	0	0	NC
745	24	N12	0	0	21.298	0	0	NC
746	24	N11	0	0	41.423	0	0	NC
747	24	N10	0	0	41.423	0	0	NC
748	24	N9	0	-18.664	38.49	0	0	NC
749	24	N13	0	0	21.298	0	0	NC
750	24	N14	0	0	41.423	0	0	NC
751	24	N15	417	0	41.262	0	0	NC
752	24	N16	0	0	21.727	0	0	NC
753	24	N17	0	0	21.294	0	0	NC
754	24	N18	0	0	41.415	0	0	NC
755	24	N19	0	0	41.415	0	0	NC
756	24	N20	0	0	21.294	0	0	NC
757	24	N24	0	0	20.917	0	0	NC
758	24	N23	0	0	25.115	0	0	NC
759	24	N22	0	0	25.232	0	0	NC
760	24	N21	0	0	20.917	0	0	NC
761	24	N25	035	0	10.647	0	0	NC
762	24	N26	0	-23.649	36.314	0	0	NC
763	24	N27	0	-23.827	36.272	0	0	NC
764	24	N28	0	0	10.537	0	0	NC
765	24	N1000	NC	NC	LOCKED	NC	NC	NC
766	24	N1001	NC	NC	LOCKED	NC	NC	NC
767	24	Totals:	0	-107.394	792.476			
768	24	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44			
769	25	N2	-34.308	0	3.387	0	0	NC
770	25	N1	0	0	14.174	0	0	NC
771	25	N3	0	0	52.326	0	0	NC
772	25	N4	0	11.938	17.651	0	0	NC
773	25	N5	0	7.823	27.965	0	0	NC
774	25	N6	0	0	47.974	0	0	NC
775	25	N7	0	0	47.974	0	0	NC
776	25	N8	0	-5.205	21.522	0	0	NC
777	25	N12	0	0	21.298	0	0	NC
778	25	N11	0	0	41.423	0	0	NC
779	<u>25</u>	N10	0	0	41.423	0	0	NC
780	25	N9	0	-2.761	18.28	0	0	NC
781	25	N13	0	0	21.298	0	0	NC NC
782	25	N14	0	0	41.423	0	0	NC NC
783	25	N15	-36.282	0	15.894	0	0	NC NC
784	25	N16	0	0	47.095	0	0	NC NC
785	25	N17	0	0	21.294	0	0	NC NC
786	25	N18	0	0	41.415	0	0	NC NC
787	25	N19	0	0	41.415	0	0	NC NC
788	25	N20	0	0	21.294	0	0	NC NC
789	25 25	N24 N23	0	0	20.917	0	0	NC NC
790					36.964		0	
791	25	N22	0	0	36.899	0	0	NC NC
792	25	N21	•	0	20.917	0	0	NC NC
793	25 25	N25	-36.803	5.047	-15.36 50.653	0	0	NC NC
794	<u>25</u> 25	N26 N27	0	-5.947	50.653	0	0	NC NC
795				-5.848	24.423			
796	25	N28	0	0	10.537	0	0	NC NC
797	25	N1000	NC	NC	LOCKED	NC	NC	NC

Company Designer Job Number : Parsons Brinckerhoff: Paul Oh

May 23, 2012 2:24 PM Checked By:\_ : 173133C CIC Det 5-9

700	LC_	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
798	25	N1001	NC	NC	LOCKED	NC	NC	NC
799	25	Totals:	-107.394	0	792.476			
800	25	COG (ft):	X: 30.667	Y: 71.679	Z: 14.44	•		110
801	26	N2	.02	0	3.019	0	0	NC
802	26	N1	0	0	1.822	0	0	NC
803	26	N3	0	0	2.99	0	0	NC
804	26	N4	0	.983	2.395	0	0	NC
805	26	N5	0	.725	3.142	0	0	NC
806	26	N6	0	0	3.49	0	0	NC
807	<u> 26</u>	N7	0	0	3.49	0	0	NC
808	26	N8	0	563	2.696	0	0	NC
809	26	N12	0	0	2.307	0	0	NC
810	26	N11	0	0	2.936	0	0	NC
811	<u>26</u>	N10	0	0	2.936	0	0	NC
812	26	N9	0	275	2.349	0	0	NC
813	26	N13	0	0	2.307	0	0	NC
814	26	N14	0	0	2.936	0	0	NC
815	26	N15	028	0	3.14	0	0	NC
816	26	N16	0	0	2.55	0	0	NC
817	<u> 26</u>	N17	0	0	2.306	0	0	NC
818	26	N18	0	0	2.936	0	0	NC
819	26	N19	0	0	2.936	0	0	NC
820	26	N20	0	0	2.306	0	0	NC
821	26	N24	0	0	2.281	0	0	NC
822	26	N23	0	0	2.852	0	0	NC
823	26	N22	0	0	2.864	0	0	NC
824	26	N21	0	0	2.281	0	0	NC
825	26	N25	.007	0	1.802	0	0	NC
826	26	N26	0	426	2.937	0	0	NC
827	26	N27	0	443	2.73	0	0	NC
828	26	N28	0	0	1.574	0	0	NC
829	26	N1000	NC	NC	LOCKED	NC	NC	NC
830	26	N1001	NC	NC	LOCKED	NC	NC	NC
831	<u>26</u>	Totals:	0	0	74.31			
832	26	COG (ft):	X: 30.7	Y: 71.912	Z: 13.438	•		110
833	27	N2	.061	0	6.168	0	0	NC
834	27	N1	0	0	3.075	0	0	NC
835	27	N3	0	0	6.081	0	0	NC
836	27	N4	0	2.548	3.696	0	0	NC
837	27	N5	0	1.851	6.276	0	0	NC
838	27	N6	0	0	10.785	0	0	NC NC
839	27	N7	0	0	10.785	0	0	NC NC
840	27	N8	0	-1.264	4.794	0	0	NC NC
841	27	N12	0	0	4.681	0	0	NC NC
842	27	N11	0	0	9.324	0	0	NC NC
843	27	N10	0	0	9.324	0	0	NC NC
844	27	N9	0	496	3.82	0	0	NC NC
845	27	N13	0	0	4.681	0	0	NC NC
846	27	N14	0	0	9.324	0	0	NC NC
847	27	N15	094	0	9.257	0	0	NC
848	27	N16	0	0	4.748	0	0	NC
849	27	N17	0	0	4.68	0	0	NC
850	27	N18	0	0	9.321	0	0	NC
851	27	N19	0	0	9.321	0	0	NC
852	27	N20	0	0	4.68	0	0	NC
853	27	N24	0	0	4.595	0	0	NC
854	27	N23	0	0	8.266	0	0	NC

: Parsons Brinckerhoff : Paul Oh

May 23, 2012 2:24 PM Checked By:\_ Company Designer Job Number : 173133C CIC Det 5-9

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
855	27	N22	0	0	8.3	Ó	Ó	NC
856	27	N21	0	0	4.595	0	0	NC
857	27	N25	.029	0	2.275	0	0	NC
858	27	N26	0	-1.293	5.323	0	0	NC
859	27	N27	0	-1.344	5.377	0	0	NC
860	27	N28	0	0	2.255	0	0	NC
861	27	N1000	NC	NC	LOCKED	NC	NC	NC
862	27	N1001	NC	NC	LOCKED	NC	NC	NC
863	27	Totals:	0	0	175.809			
864	27	COG (ft):	X: 30.665	Y: 71.665	Z: 14.5			NO
865	28	N2	.355	005	43.668	0	0	NC NC
866 867	28 28	N1 N3	.005 .011	003 005	21.802 43.176	0	0	NC NC
868	28	N4	.006	18.09	26.224	0	0	NC NC
869	28	N5	.01	13.145	44.527	0	0	NC NC
870	28	N6	.018	009	76.466	0	0	NC NC
871	28	N7	.018	009	76.466	0	0	NC NC
872	28	N8	.008	-8.946	33.973	0	0	NC
873	28	N12	.007	003	33.191	0	0	NC
874	28	N11	.015	008	66.103	0	0	NC
875	28	N10	.015	008	66.103	0	0	NC
876	28	N9	.006	-3.497	27.058	0	0	NC
877	28	N13	.007	004	33.191	0	0	NC
878	28	N14	.014	008	66.103	0	0	NC
879	28	N15	732	007	65.576	0	0	NC
880	28	N16	.007	004	33.718	0	0	NC
881	28	N17	.007	004	33.183	0	0	NC
882	28	N18	.013	008	66.088	0	0	NC
883	28	N19	.013	008	66.088	0	0	NC
884	28	N20	.007	003	33.183	0	0	NC NC
885	28	N24	.006	003	32.58	0	0	NC NC
886 887	28 28	N23 N22	.011 .011	007 007	58.621 58.86	0	0	NC NC
888	28	N21	.006	007	32.58	0	0	NC NC
889	28	N25	.137	002	16.083	0	0	NC NC
890	28	N26	.007	-9.153	37.775	0	0	NC
891	28	N27	.007	-9.516	38.109	0	0	NC
892	28	N28	.003	002	15.989	0	0	NC
893	28	N1000	NC	NC	LOCKED	NC	NC	NC
894	28	N1001	NC	NC	LOCKED	NC	NC	NC
895	28	Totals:	0	0	1246.484			
896	28	COG (ft):	X: 30.665	Y: 71.665	Z: 14.5			
897	29	N2	.074	0	.053	0	0	NC
898	29	N1	0	0	0	0	0	NC
899	29	N3	0	0	053	0	0	NC
900	29	N4	0	-1.416	-1.369	0	0	NC
901	29	N5	0	-1.243	-1.578	0	0	NC
902	29	N6	0	0	0	0	0	NC NC
903	29	N7	0	0	0	0	0	NC NC
904	29	N8	0	-1.416	1.369	0	0	NC NC
905	29 29	N12 N11	0	0	0	0	0	NC NC
906	<u>29</u> 29	N10	0	0	0	0	0	NC NC
907	<u>29</u> 29	N10 N9	0	-1.242	1.578	0	0	NC NC
909	<u>29</u> 29	N13	0	0	0	0	0	NC NC
910	29	N14	0	0	0	0	0	NC NC
911	29	N15	003	0	002	0	0	NC NC

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
912	29	N16	0	0	.002	0	0	NC
913	29	N17	0	0	0	0	0	NC
914	29	N18	0	0	0	0	0	NC
915	29	N19	0	0	0	0	0	NC
916	29	N20	0	0	0	0	0	NC
917	29	N24	0	0	0	0	0	NC
918	29	N23	0	0	868	0	0	NC
919	29	N22	0	0	882	0	0	NC
920	29	N21	0	0	0	0	0	NC
921	29	N25	071	0	05	0	0	NC
922	29	N26	0	-1.338	.933	0	0	NC
923	29	N27	0	-1.317	.868	0	0	NC
924	29	N28	0	0	0	0	0	NC
925	29	N1000	NC	NC	LOCKED	NC	NC	NC
926	29	N1001	NC	NC	LOCKED	NC	NC	NC
927	29	Totals:	0	-7.973	0			
928	29	COG (ft):	NC	NC	NC			
929	30	N2	-5.846	0	-4.169	0	0	NC
930	30	N1	0	0	0	0	0	NC
931	30	N3	0	0	4.169	0	0	NC
932	30	N4	0	054	052	0	0	NC
933	30	N5	0	.051	.065	0	0	NC
934	30	N6	0	0	0	0	0	NC
935	30	N7	0	0	0	0	0	NC
936	30	N8	0	054	.052	0	0	NC
937	30	N12	0	0	0	0	0	NC
938	30	N11	0	0	0	0	0	NC
939	30	N10	0	0	0	0	0	NC
940	30	N9	0	.051	065	0	0	NC
941	30	N13	0	0	0	0	0	NC
942	30	N14	0	0	0	0	0	NC
943	30	N15	-5.735	0	-4.056	0	0	NC
944	30	N16	0	0	4.056	0	0	NC
945	30	N17	0	0	0	0	0	NC
946	30	N18	0	0	0	0	0	NC
947	30	N19	0	0	0	0	0	NC
948	30	N20	0	0	0	0	0	NC
949	30	N24	0	0	0	0	0	NC NC
950	30	N23	0	0	009	0	0	NC NC
951	30	N22	0	0	.014	0	0	NC NC
952	30	N21	0	0	0	0	0	NC NC
953	30	N25	-5.621	0	-3.975	0	0	NC NC
954	30	N26	0	.021	3.961	0	0	NC NC
955	30 30	N27	0	014 0	.009	0	0	NC NC
956		N28	NC	•		NC	-	
957 958	30 30	N1000	NC NC	NC NC	LOCKED		NC NC	NC NC
		N1001			LOCKED	NC	INC	NC
959 960	30 30	Totals: COG (ft):	-17.2 NC	0 NC	NC			
961	30 31	N2		0	.177	0	0	NC
961	31	N2 N1	.248	0	0	0	0	NC NC
962	31		0	0	177	0		
963	31	N3	0	-27.782		0	0	NC NC
965	31 31	N4 N5	0	-27.782 -23.448	-26.84 -29.749	0	0	NC NC
966	31 31	N6	0	-23.446	-29.749	0	0	NC NC
967	31 31	N7	0	0	0			NC NC
						0	0	
968	31	N8	0	-27.749	26.84	0	0	NC

Company Designer Job Number : 173133C CIC Det 5-9 Checked By:

0 0		ions (by combinat	ion, toomin	10.00,				
	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
969	31	N12	0	0	0	0	0	NC
970	31	N11	0	0	0	0	0	NC
971	31	N10	0	0	0	0	0	NC
972	31	N9	0	-23.391	29.749	0	0	NC
973	31	N13	0	0	0	0	0	NC
974	31	N14	0	0	0	0	0	NC
975	31	N15	009	0	006	0	0	NC
976	31	N16	0	0	.006	0	0	NC
977	31	N17	0	0	0	0	0	NC
978	31	N18	0	0	0	0	0	NC
979	31	N19	0	0	0	0	0	NC
980	31	N20	0	0	0	0	0	NC
981	31	N24	0	0	0	0	0	NC
982	31	N23	0	011	-16.802	0	0	NC
983	31	N22	0	011	-16.849	0	0	NC
984	31	N21	0	0	0	0	0	NC
985	31	N25	239	0	169	0	0	NC
986	31	N26	0	-25.549	17.018	0	0	NC
987	31	N27	0	-25.479	16.802	0	0	NC
988	31	N28	0	0	0	0	0	NC
989	31	N1000	NC	NC	LOCKED	NC	NC	NC
990	31	N1001	NC	NC	LOCKED	NC	NC	NC
991	31	Totals:	0	-153.42	0			
992	31	COG (ft):	NC	NC	NC			
993	32	N2	-49.454	0	-35.23	0	0	NC
994	32	N1	0	0	0	0	0	NC
995	32	N3	.045	0	35.23	0	0	NC
996	32	N4	0	.729	.704	0	0	NC
997	32	N5	001	693	88	0	0	NC
998	32	N6	0	0	0	0	0	NC
999	32	N7	0	0	0	0	0	NC
1000	32	N8	0	.729	704	0	0	NC
1001	32	N12	0	0	0	0	0	NC
1002	32	N11	0	0	0	0	0	NC
1003	32	N10	0	0	0	0	0	NC
1004	32	N9	.001	693	.88	0	0	NC
1005	32	N13	0	0	0	0	0	NC
1006	32	N14	0	0	0	0	0	NC
1007	32	N15	-51.293	0	-36.236	0	0	NC
1008	32	N16	.047	0	36.236	0	0	NC
1009	32	N17	0	0	0	0	0	NC
1010	32	N18	0	0	0	0	0	NC
1011	32	N19	0	0	0	0	0	NC
1012	32	N20	0	0	0	0	0	NC
1013	32	N24	0	0	0	0	0	NC
1014	32	N23	0	0	.13	0	0	NC
1015	32	N22	0	0	177	0	0	NC
1016	32	N21	0	0	0	0	0	NC
1017	32	N25	-52.815	0	-37.31	0	0	NC
1018	32	N26	.051	268	37.487	0	0	NC
1019	32	N27	0	.197	13	0	0	NC
1020	32	N28	0	0	0	0	0	NC
1021	32	N1000	NC	NC	LOCKED	NC	NC	NC
1022	32	N1001	NC	NC	LOCKED	NC	NC	NC
1023	32	Totals:	-153.419	0	0			
1024	32	COG (ft):	NC	NC	NC			
					•			

## Foundation Design

CIC – RA 5-9; Ft. Stewart, Georgia




SubjectCIC Defachment 5-9	
Footing Design - Interior Column (BRACE	)

Page	of [A3/33 C]
	by Paul Oh
Date	5/17/12
Checi	ked by
Date	

Footing Node: NG

Load Case 13: ASD 16-10 = D + RLL

Fz = 0 Fy = 0 Fz = 90.41 K



CONC WT = 145 pcf 801 WT = 120 pcf

### Footing Compression Check

Allowable Soil Bearing Capacity = 2 ksf

FZ= 90,41 K

Footing Wt : (145 pcf)(2'x8'x2') = 18.56 k

$$\frac{90.41k+ 18.56k+11.52k}{(8'\times8')} = 1.88 \text{ Ksf} < 2.0 \text{ ksf} / \text{ok}$$

Conclusion: use 8'x 8' x 2' Footings For Interior Non-braced Columns.



# **COMPUTATION SHEET**

Subject		CIC	De-	tachment	5-9	~~~
<u> </u>	otivi	Design		Interior	Braced	Columb


Page	of	173133C
Made	by Paul Oh	
Date	5/21/12	ner with one limit has limit has one one one has one one limit has we still be one Wh
Chec	ked by	
Date		

Footing Node: NIS

LOAD CASE 17: ASD 16-126.1 = D + O.7E

 $F_X = -36.532 k$ Fy = 0

FZ = 43.428 /c



CONC WEIGHT = 145 pcf Soil Weight = 120 pef

### FOOTING SUDNER CHECK

Try 8' × 8' × 2' Footing

Downward Force: 43.423k + (145 pcf)(8'x8'x2') + (120 pcf)(8'x8'x15')

= 73.503 k

U = 0.5

u (ne+ downward force) = 0,5(73,503 €)= 36,752 €

36.752 K > Fx = 36.532 Ł OŁV



Subject	CIC	Deta	hment	5-9		
Footh	G Desi	en -	INTERLOR	Column	Braceo	

Page	of 173  33 C
Made	by Paul Oh
Date	5/21/12
Checi	ked by
Date	

\* Footing Uplit Check not needed ble it is negligible compared to superimposed dead land.

### FOOTING COMPRESSION CHECK

Allowable Soil Bearing: 2 Ksf

LOAD CASE 20: D+ 0.75W+ 0.75 Lr = 75,737 k

Soil weight = (120 pcf)(8' x 8' x 1.5') = 11.52 k

CONCLUSION: USC 8' x 8' x 2' FOOTINGS FOR INTERIOR BRACED COLUMNS.

USE 8' x 8' x 2' FOR ALL COLUMNS, 8' x 8' x 2' adequate by inspection.

U.S. Army Criminal Investigation Command RA 5-9 Adapt-Build Fort Stewart, Georgia

# APPENDIX D ELECTRICAL CALCULATIONS

#### Criminal Investigation Command Field Operations Building RA 5-9 Adapt-Build Fort Stewart, GA

465 Spring Park Place Herndon, VA 20170


Parsons Brinckerhoff

Date:6/21/2012

Page 1 of 2

Calculation Summary						
Label	Units	Avq	Max	Min	Avg/Min	Max/Mir
002 Vestibule Floor	Fc	17.14	21.2	11.9	1.44	1.78
003 - Vestibule North Floor			19.9	12.6	1.32	1.58
102 Corridor Floor	Fc	25.50	30.9	16.3	1.56	1.90
103 Men Floor	Fc	18.30	26.0	8.2	2.23	3.17
104 Women Floor	Fc	16.88	23.8	8.8	1.92	2.70
105 - Corridor Floor	Fc	23.68	31.7	9.8	2.42	3.23
106 - Multi Purpose Workpla		41.19	62.7	14.2	2.90	4.42
107 SAC Workplane	Fc	32.79	52.5	16.8	1.95	3.13
108 Large Interview Workpla		54.65	67.5	34.5	1.58	1.96
109 Small Interview Workpla		40.17	55.0	25.1	1.60	2.19
110 Small Interview Workpla		40.63	55.7	26.3	1.54	2.12
111 Photo ID Workplane	Fc	41.72	56.1	25.0	1.67	2.24
112 - Polygraph Office Work		31.74	46.1	18.3	1.73	2.52
113 - Polygraph Exam Workpl		30.25	39.8	20.2	1.50	1.97
114 - Observation Room Work		41.89	55.7	26.2	1.60	2.13
115 - Suspect Waiting Workp		29.20	45.4	10.2	2.86	4.45
116 - Supsect Toilet Floor	Fc	5.17	5.9	3.6	1.44	1.64
117 - Corridor Floor	Fc	26.11	40.6	6.4	4.08	6.34
118 Evidence Custodian Work		34.73	48.3	20.9	1.66	2.31
119 Evidence Depository Wor		62.78	78.7	33.4	1.88	2.36
120 Evidence Processing Wor		37.16	54.4	20.6	1.80	2.64
121 Duty Agent Workplane	Fc	34.15	48.8	17.1	2.00	2.85
122 Storage Floor	Fc	25.70	33.7	14.7	1.75	2.29
123 Arms Vault Floor	Fc	20.68	25.5	16.0	1.29	1.59
124 Telecom Rm Floor	Fc	10.41	13.0	6.8	1.53	1.91
125 Electrical Floor	Fc	20.68	26.2	14.6	1.42	1.79
126 Mechanical Floor	Fc	15.71	22.7	6.9	2.28	3.29
127 - Corridor Floor	Fc	26.18	32.4	11.0	2.38	2.95
128 - RA CIC Workplane	Fc	40.54	55.6	26.0	1.56	2.14
129 - Team Chief Workplane	Fc	39.75	54.8	25.8	1.54	2.12
130 - Investigative OPS Tec	hFWor	36.84	52.6	21.7	1.70	2.42
131 - Drug Supression Workp		39.76	54.8	25.8	1.54	2.12
132 - Special Agents Workpl		36.83	52.6	21.6	1.71	2.44
133 - Special Agents Workpl		43.42	59.8	18.9	2.30	3.16
	1Fc	19.08	24.7	13.7	1.39	1.80
135 Admin OPS Workplane	Fc	44.63	62.7	16.2	2.75	3.87
136 Shower Floor	Fc	14.42	18.1	8.3	1.74	2.18
137 - Janitor Floor	Fc	9.35	10.1	8.4	1.11	1.20
157 Danitoi_F1001	1 - 0	7.55	10.1	0.7	± • ± ±	1.20

**Parsons Brinckerhoff Criminal Investigation Command** 465 Spring Park Place **Field Operations Building** RA 5-9 Herndon, VA 20170 Adapt-Build Fort Stewart, GA Date:6/21/2012 Page 2 of 2



Calculation Summary						
Label	Units	Avg	Max	Min	Avg/Min	Max/Min
North Road_Planar	Fc	2.02	5.2	0.4	5.05	13.00
North Sidewalk_Planar	Fc	1.87	4.4	0.5	3.74	8.80
South Sidewalk_Planar_1	Fc	2.82	4.6	0.8	3.53	5.75
West Road_Planar	Fc	1.52	2.8	0.0	N.A.	N.A.

U.S. Army Criminal Investigation Command RA 5-9 Adapt-Build Fort Stewart, Georgia

# APPENDIX E ENERGY MODELING

### CIC Adapt-Build BIM

#### **Energy Modeling Approach and Simulation Parameters**

(This process is specifically written to address the Detachment 24 Building, however the process for modeling the other three buildings is essentially the same.)

#### Comparison

The "Alternative 1" is set up as the Baseline Alternative, which complies with ASHRAE 90.1-2007. "Alternative 2" and "Alternative 3" are set up as Design Alternatives. The form, fabric, and system information between "Alternative 2" and "Alternative 3" is the same. The two Design Alternatives differ in the primary cooling plant – "Alternative 2" uses a cooling tower and "Alternative 3" uses an air-cooled chiller.

Per ASHRAE 90.1-2007 requirements, the following are included in the model:

- Energy parameters are set to calculate 8760 simulation hours.
- Alternative 1 is set as the "Base Alternative" for "Economic comparison."
- Alternative 1 is set as the "Base Alternative" for "Performance rating method" and Alternative 1
  is set to "Rotate and average PRM results."

#### Weather Data

The weather data is taken from the Department of Energy website as a \*.bin file, changed to a \*.tmy file, and imported into the Trane TRACE 700 weather library.

Weather overrides have been set for the 1% ASHRAE Summer Design Cooling and 99.6% for the Winter Design Heating, per ASHRAE 90.1-2007 energy simulation requirements.

#### **Energy Cost Rates**

Annual energy costs are determined using state average unit prices from EIA, which is updated annually on EIA's website (www.eia.doe.gov).

#### Schedules and Internal Loads

Schedules are set to model hourly variations in occupancy, lighting power, miscellaneous equipment power, and HVAC system operations, and are defined separately for each day of the week and holidays per ASHRAE 90.1-2007 requirement. Modeling the thermostat set points is explained below.

#### Occupancy

The expected occupancy for the CIDC building is from 0630 to 2000. Due to TRACE's limitations dealing with fractional hours, the hours from 0600 to 0700 are staffed at 50 percent, and the hours from 0700

to 2000 are staffed at 100 percent for Monday to Sunday and 0 percent from midnight to midnight for holidays. Occupancy is defined room-by-room according to the Standard Design Criteria.

#### Lights

The lighting schedule is set to match the occupancy schedule with the exception that during unoccupied hours, the lighting power is set to 5 percent to account for emergency lighting. In the Baseline Building, the lighting power density is defined at the template level. In the Design Alternatives, the lighting power density is defined at the room level as the lighting power density requirements are satisfied via Space-by-Space Method.

In the design alternatives, the lighting power densities are reduced by 10% for any space that has occupancy sensors, per ASHRAE 189.1 requirements for energy modeling.

#### Miscellaneous Equipment

This loading is defined with the Occupancy Schedule. Miscellaneous equipment defines receptacle loads, exclusively. Area-based loading is derived from ASHRAE 90.1-1989 and is assumed to be 0.75 W/sf.

#### Ventilation

Vent schedules match the occupancy schedule as the intent is to close outdoor air dampers during unoccupied mode, and the system shall re-circulate air to maintain temperature drift points.

The Design Alternatives apply ASHRAE 62.1 ventilation requirements on a template and room level. The template defines the typical space-type as "Office space" and any rooms that deviate from this space-type are defined at the room level. The option to "Apply ASHRAE Std 62.1-2004/2007" is selected and the "System Ventilation Flag" is set to "ASHRAE Standard 62.1-2004/2007." This sets the program to use equations from ASHRAE 62.1 to calculate the system-level ventilation requirement, based on the room ventilation requirements. Per ASHRAE 90.1, demand control ventilation (DCV) is required for the Command Conference Room, Multi-purpose Lounge, Large Interview Room (Room 281), and Suspect Waiting Room. These rooms are served by the Primary and Secondary VAV Systems, therefore, these two systems have their "System Ventilation Flags" set to "ASHRAE 62.1-2004/2007 w/ Vent Reset." Proportional control is selected allowing the outdoor air controller to adjust the outdoor air intake flow proportionally between the minimum ventilation flow and the design ventilation flow.

Zone distribution effectiveness for cooling is defined as 100 percent based on a ceiling supply and ceiling return and 100 percent for heating assuming the "worst case scenario" for a ceiling supply and ceiling return.

ASHRAE 90.1, G3.1.2.5 requires that ventilation rates for the Baseline and Design Alternatives be the same. In order to ensure this requirement, the Baseline Building ventilation rates are determined by taking the total ventilation requirement for all systems in the design case, totaled, and divided by the building area. This provides for a ventilation rate per area for the Baseline Building. The application of ASHRAE 62.1 Standard is disabled, and the ventilation rates previously calculated are applied for cooling

and heating modes. At the system level, the "System ventilation flag" is defined as "Sum Room OA Reqs." This sets the program to sum the (user-defined) individual room ventilation requirements to calculate the system-level ventilation requirement.

In both Baseline and Design Alternatives, "people-averaging" is not used – the ventilation rates are based on highest, user-defined occupancy.

Room exhaust rates are calculated based on ASHRAE 62.1 requirements and are the same in the Baseline and Design Alternatives.

#### Thermostat Set Points

Schedules are not defined for thermostat set points. Cooling and heating dry bulb temperatures, relative humidity, and cooling and heating drift points are defined. TRACE allows the room temperature to drift to the user-defined temperature drift point during the hours in which the Occupancy Schedule reads 5 percent or less; if the Occupancy Schedule reads greater than 5 percent, the thermostat will try to control the room to the design room dry bulb temperature.

Thermostat sensors are located at the zone level per ASHRAE 90.1, Section 6.4.3.1.1.

#### **Building Form**

The "Spaces" in Autodesk Revit bring door, window, wall, partition, roof, and floor information into Trane TRACE via gbXML.

The National Renewable Energy Laboratory (NREL) published a report on the typical infiltration rates for large office buildings based on ASHRAE 90.1-1989, the latest version which includes infiltration requirements. Since air barrier requirements are introduced in ASHRAE 90.1-2010 and 189.1-2009, tests were performed on large office buildings to compare results. The infiltration rates are labeled in terms of air changes per hour. The 1989 values are used as the baseline infiltration and the 2010 values are used as the design. The maximum infiltration rates (which occur during non-operating hours), for the baseline and design, are modeled for perimeter zones and for the core zones. A "Utilization Schedule" is created to step down the infiltration rates by a specified percentage during occupancy. The schedule is applied to all spaces, and each space is distinguished by perimeter zone or core zone. This set-up simulates a lower infiltration rate during occupancy, and the design case models a lower all-around infiltration rate based on the envelope requirements from ASHRAE 90.1-2010 and 189.1-2009.*Roofs* 

Roof area and orientation is determined by projecting the roof line over a floor plan layout and determining the projected area of the roof over each space and is divided according to orientation. The actual area is determined by developing a multiplication factor from the cosine-based relationship between the projected area and the actual roof area. The angle for this calculation is determined by converting the slope, 4:12, to degrees. The pitch angle is taken from the vertical plane and rotates toward the sky; therefore the 4:12 slope from the 90° vertical plane gives TRACE's roof pitch.

The TRACE program is limited in accurately modeling a building with an attic space, so a substitute is provided. The heat transfer from the roof to the plenum is modeled as a single construction element – the roof is modeled with roof components and the gypsum board and insulation layers separating the attic and the plenum.

#### **Shading Devices**

The shading devices modeled are unique to each building. This device is applied over window opening in the exterior wall. The Battalion HQ shading device is modeled as equivalent to the design intent by considering the Projection Factor for the designed shading device and applying a shading device that provides the same Projection Factor. Per ASHRAE 90.1 requirements, the shading device is applied only to the Design Alternative; manual internal shading devices are not modeled in either the Baseline Building or the Design Alternatives.

#### Walls

Walls are derived from the "Spaces" created in the Revit model. Adjacencies (or absence of) define interior and exterior walls. Partitions are defined at the template level to have a miniscule U-factor (U=10^-7) to negate the estimation of heat transfer across partitions – this prevents the system coils sizing from being affected by a non-existent load.

#### Floors

ASHRAE 90.1 provides a minimum F-value (the perimeter heat loss factor for slab-on-grade, expressed in Btu/h·ft·F°) whereas the TRACE input is in the form of a U-value. The conversion is determined by calculating heat loss with the F-value and dividing by area of slab to acquire loss per square foot.

#### **Building Fabric**

Per ASHRAE 90.1 requirement, the model is set to calculate heat loss/gain for heat transfer via conduction, internal loads, or solar through the time delay based on actual mass – the program calculates the room specific mass (in lb/sf of floor area).

Custom library construction types are built specifically for this project... The Baseline Building is modeled with envelope values defined by ASHRAE 90.1 for the appropriate Climate Zone. Per ASHRAE 90.1 requirements, the construction types mandated for the Baseline model are as follows: Roofs – Insulation entirely above deck, Above-grade walls – Steel-framed. Slab-on-grade floors shall match the F-factor for unheated slabs from the same tables.

Per ASHRAE 90.1 requirements, all roof surfaces in the Baseline Building are modeled with a reflectivity of 0.30. This translates to TRACE by defining the "Outside shortwave (solar) absorptivity" as 0.7.

#### **Systems**

**Baseline Building** 

According to ASHRAE 90.1, the Baseline Building system is a constant volume Packaged Single Zone Air Conditioner with a Fossil fuel furnace. ASHRAE 90.1 requires that for this system, each thermal block is modeled with its own HVAC system. The Baseline Building system in TRACE is the "Single Zone" under the "Constant Volume – Non-mixing" system category. This system has supply fans ("cooling fan") and heating and cooling coils at the zone level and a return fan at the system level.

ASHRAE 90.1 Table G.3.1.2.6A indicates that air-side economizers are required to be modeled in the Baseline Building for the project's climate zone, 3B. Table G.3.1.2.6B states that the high-limit shutoff temperature for the climate zone is 75°F DB. This is addressed in ...

On the Energy Parameters dialog box, the "Apply ECB/PRM rules to fan sizing" option is checked and ASHRAE 90.1-2007 is selected from the drop-down menu. This tells TRACE uses the rules stipulated in Section G3.1.2.9 to calculate fan energy rate for energy analysis. This supersedes the fan full load energy rates input on the "Fans" tab under "Create Systems." The fan cycling schedule is set to cycle with all loads, as defined on the "Fans" tab.

Section G3.1.2.8 states that system design supply airflow rates for the Baseline Building shall be based on a supply air/room air temperature difference of 20°F. The thermostat settings for cooling dry bulb and heating dry bulb are 75°F and 70°F, respectively, so in the "Temp/Humidity" tab under "Create Systems," the cooling supply air max and min are set to 55°F and the heating supply air max and min are set to 90°F.

The Baseline Building coil capacities are set to 115% and 125% of the design capacity for the cooling and heating coils, respectively. Should the number of unmet load hours for Design Alternative exceed the Baseline Building by more than 50, simulated capacities in the Baseline Building shall be decreased incrementally and the building re-simulated until the unmet load hours are within 50 of the unmet load hours of the proposed design. If unmet load hours for the Design Alternative or Baseline Building exceed 300, simulated capacities shall be increased incrementally, and the building with unmet loads resimulated until unmet load hours are reduced to 300 or less.

#### Design Alternative1

Central systems include the two VAV systems – one which serves the "Administrative Areas" of the building and the other serving the "Special Uses Area" of the building. The system type is variable air volume with baseboard heating about the exterior zones. The Administrative Area system is labeled "Primary – VAV w/ BB" and the Special Uses system is labeled "Secondary – VAV w/ BB." A central fan, optional exhaust/return fan, preheat coil, and cooling coil is defined at the system level. Baseboard heaters and VAV terminals (auxiliary fans) are defined at the zone level. The TRACE program begins the simulation by calculating what effect the operation of the OA-controlled baseboard units will have on the room's drift temperature. This heat output is determined by the outdoor air reset schedule. For these systems, the "Reset per worst case room" is set to "Off" and "Use system default outside air reset" is checked – the system default to a reset schedule defined for the system type. In this system, the default reset schedule assumes that the output of the baseboard units is proportional to the room heating-thermostat-to-outside-air temperature difference. During setback periods, the baseboard

heating output is modulated downward proportionally to the amount of degrees setback from the daytime heating setpoint. The heat output of the OA-controlled baseboard unit adds additional heat gain to the space to offset the conduction heat loss. When the drift temperature rises above the hour's cooling thermostat set point, the VAV box opens and delivers a proportionate quantity of supply air to the space – enough cool supply air to bring down and maintain the space temperature according to the thermostat setpoint. So long as the room drift temperature is below the cooling thermostat setpoint this hour, the VAV box is fully closed. While the drift temperature is within the dead band region, there is no air movement and absolutely no cooling can be provided by the main system VAV box. Should the skin heating system not supply enough heat to satisfy the space heating load, the drift temperature will fall below this hour's heating thermostat setpoint.

These systems have air-side economizers set to monitor outdoor dry-bulb temperature.

Spaces that require heating only, i.e. vestibules, are handled by the "Unit Heaters" system type under the "Heating Only" system category. The system is labeled as "CUHs – Vestibules." The system schematic defines a fan and heating coil at the zone level. Each of the individual vestibules and the mechanical rooms are assigned to their own individual zones, therefore TRACE assigns a fan and heating coil to each room. The vestibules have no ventilation requirements set at the rooms, so the coil does not factor in condition ventilation air.

In order to satisfy the ventilation requirements for the Electrical Room, the "Ventilation and Heating" system type is applied (under the "Heating Only" system category). The system is labeled as "FCU – Elec," and the fan and heating coil are set to the system level, therefore only the Electrical Room is applied to this system. The system supplies a constant volume of heated supply air and the heating coil is cycled to meet varying loads. When heating is not needed, the system attempts to bring the space temperatures down using unconditioned ventilation air. The "Return Air Path" is defined as being a "Plenum" return. This allows TRACE to account for loads from the roof, lights, etc in the return air going to the system. The requirement for satisfying cooling is ventilation air, so the room is set to 10 air changes per hour. TRACE does not recognize this air flow rate as ventilation air.

This same system is set up for the Mechanical Room, since the Mechanical Room will have its own dedicated fans and coils. The requirement for satisfying cooling is ventilation air, so the room is set to 6 air changes per hour. TRACE does not recognize this air flow rate as ventilation air.

The Evidence Depository Room requires separate heating, cooling, and ventilation. This is satisfied with the "Fan Coil" system type under the "Constant Volume – Non-mixing" system category. The system is labeled "FCU – Evid Dep" and consists of a zone level fan and heating/cooling coil. TRACE treats this system as a separate fan coil unit, including a fan, cooling coil, and heating coil, located in each room. The program assumes that the fan coil unit is a four-pipe arrangement with heating and cooling coil available year-round. The unit supplies a constant volume of conditioned air to the room, and the coils are cycled to meet the varying load. When the room drift-temperature rises above the room heating thermostat, the heating coil is de-activated, allowing the space temperature to drift upward. Since the supply air will be at the return/outside air dry bulb temperature, scheduling outside air into the space

will temper this effect to some degree. When the room drift-temperature drops below the room heating thermostat, the heating coil is modulated to produce a supply air dry bulb temperature that will bring the room temperature up to the heating thermostat.

Telecommunications Rooms 1 and 2 have similar system setups. These rooms are modeled with separate systems because Telecomm Room 1 does not utilize a cooling coil, and so the cooling coil is placed on a "DUMMY" plant, and the plants will be sized separately according to the load it needs to handle.

The TRACE program requires all spaces to be assigned to systems and all system components to be assigned to a plant regardless of whether the space is being conditioned. This includes interstitial spaces. To circumvent adding additional energy consumption by the system that will not "see" the space, a "DUMMY" system is set in place in which these spaces will be assigned. The particulars on how energy circumvention takes place at the plants set for this system.

#### Design Alternative 2

The second design alternative differs in the Primary and Secondary System selection—rather than VAV with Skin Baseboard Heating, the systems are set as Fan-Powered Terminal Units with Reheat on the plenum inlet. The other system settings remain unchanged from the first design alternative.

#### **Daylighting Controls**

Daylighting controls are utilized throughout all perimeter spaces with windows. To model this, a "Daylighting Controls Definition" is created. Geometry, daylighting control type, room parameters, glass, construction, and internal shade parameters are set here for all Alternatives. The Baseline Building is modeled with no daylighting controls and the Design Alternatives have daylighting controls available, 100%. Daylighting that is added to a space that has no fenestration is ignored by the program. The daylighting controller is the "Std Stepped Controller" template. This controller is added to the "Daylighting Reference Pt 1" under the "Room Parameters" tab.

#### **Plants**

Plant capacities are not user-defined. When the value is left blank, TRACE automatically determines plant capacity by summing the coil capacities attached to the plant. The "Equipment type" and "Heat rejection type" determines the equipments' unloading curves and fundamental energy rates. These pieces of equipment use "Standard" curve types – this selection indicates that a combination of ARI unloading curves and an ambient modification curve will be used to determine the power consumed at each of the hourly load conditions.

#### Baseline Building

According to ASHRAE 90.1 requirements, the cooling and heating plants for this project size is direct expansion cooling and fossil fuel furnace heating. The plants are labeled as "Cooling plant – 001" and

"Heating plant – 002." The cooling plant has an "air-cooled unitary" piece of equipment attached with an air-cooled condenser. The heating plant has a "gas-fired heat exchanger" attached.

The cooling equipment type is defined as the "90.1-07 Min PTAC New Cons > 15 MBh Cap." The sequencing type is defined as "Single" as there is only one piece of equipment that handles the entire cooling load. The equipment is set to reject condenser heat to the "heat rejection equipment," i.e. the air-cooled condenser. The heat rejection equipment is defined as a "90.1 Min Air Cooled Condenser." The energy rate is defined by TRACE's library of minimum efficiency values from ASHRAE 90.1. The heating equipment is defined as the "90.1-07 Min Gas Furnace < 225 MBh." The energy rate is defined according to the ASHRAE 90.1 requirements.

#### Design Alternatives 1

The Design Alternatives are set up with a main cooling plant and a main heating plant. These are labeled as "Cooling plant – 001" and "Heating plant – 002," respectively. Addition cooling plants are in place to handle cooling equipment not addressed by the main cooling plant, e.g. direct expansion for a standalone system. "DUMMY" plants are in place to host the "DUMMY" systems required to satisfy TRACE's requirement for every coil to be hosted by a plant without affection equipment and plant capacity calculations. The "DUMMY" plants are scheduled to "Off" – the equipment is arbitrarily defined as the equipment will not be functioning and therefore do not affect the load or energy consumption.

In the first Design Alternative (TRACE Alternative 2: Design w/ CT), the equipment type is a "water-cooled unitary" unit with a "cooling tower" and "condenser water pump." The equipment type is defined as "90.1-07 Min Other Heat SS/SP 135-240 MBh." Sequencing type is "Single" since there is one water-cooled unit. The equipment is set to reject condenser heat to the "Heat rejection equipment," the "90.1 Min Cooling Tower."

To ensure maximum effectiveness of the fan coil unit systems, a "Micro-Chiller" plant is modeled to satisfy the cooling load for those spaces. The Micro-Chiller rejects its heat to the Cooling Tower. TRACE is currently incapable of applying systems to specific plant components, so modeling the Micro-Chiller under the same plant as the water-cooled unitary equipment is not feasible. To get the performance benefit of running rejecting heat to an otherwise running cooling tower, the Micro-Chiller plant load is specified to exceed 50% of the total system load. This way, the cooling tower is modeled separately from the cooling tower assigned to the water-cooled unitary equipment, but mimics the heat rejection equipment performance as if the water-cooled unitary equipment and the Micro-Chiller were utilizing the same cooling tower.

The RA 5-9 and the Detachment 24 each have one boiler. The Battalion HQ and the RA 10-15 have two pieces of equipment under the "Heating plant – 002"—both of which are labeled as boilers ("Boiler – 002" and "Boiler – 003"). The two-boiler plants are set so TRACE sizes them to 60% of the total heating load.

Design Alternative 2

The plant used in the second design alternative is an "Air-Cooled Chiller." Since a chiller is modeled as the primary plant, a Micro-Chiller is not required for the alternative.

Secondly, the loads satisfied by the Micro-Chiller in the first design alternative are distinguished. There are two "air-cooled unitary" units with "air-cooled condenser" units – one of which applies to the Evidence Depository and the other to the Telecommunications Room 2, as these systems are using direct expansion cooling. These are labeled as "Air-cooled condenser – Evid Dep" and "Air-cooled condenser – TR#2." These units' equipment types are set to "90.1-07 Min Room AC w/o louvers < 8MBh."

#### **Base Utilities**

Base utilities are used to model loads that are not otherwise calculated by the TRACE program. These loads include exterior lighting and domestic hot water load. To model these loads, the hourly demand, plant (source), and load schedule is specified.

#### **Exterior Lighting**

The ext lighting is defined through creating a new "base utility" in TRACE. The requirement for ASHRAE/LEED is to calculate power consumption for the year. ASHRAE requires that the lighting is controlled by a combination of photo sensors and time switches, depending on whether the system is set for dusk-to-dawn operation. This will be handled by creating a new schedule for this base utility. The schedule parameters will be based on the Equinox, so the average amount of daylight for each hour through the span of 24 hours will be proportional to the amount of energy consumed by the ext lighting in the same span of 24 on each hour on a daily basis for an entire year. Using this approach will give accurate energy consumption by the ext lighting for the year, but the estimated energy consumption on a monthly basis is constant, which is not accurate.

The domestic hot water load is modeled as a base utility labeled "Domestic Hot Water Load." In the Design Alternative, the plant satisfying the load is "Heating plant – 002." This plant uses a combination of the boiler and solar hot water system to satisfy the load. The Baseline Building uses a separate plant to represent the domestic hot water heater. This equipment type is labeled as "90.1-04 Min (Res) 300-2,500 Mbh." In both the Baseline Building and the Design Alternative, the hourly demand is the same and the schedules are both set to the occupancy schedule, "People – CIC Det24 Full Year."

The solar hot water (SHW) system is modeled as a base utility with a negative demand—the domestic water load and heating load covered by the "Heating plant – 002" is credited by the base utility. The maximum capacity of the SHW system is determined based on highest solar insolation value for a fixed number of solar hot water panels. The subsequent monthly capacities are determined based on month's solar insolation value, the total hours of daylight in a day (determined by parallel for the 20<sup>th</sup> of each month, based on the solstice), and the number of panels. After the capacity of the SHW system is determined for each month, each month is represented as a percentage of the maximum capacity and is input in a "Utilization Schedule." Each month is modeled with approximate times of sunrise and sunset for the respective month with the percentage of maximum capacity—the percent capacity is defined

between sunrise and sunset and zero from sunset to sunrise. This schedule is applied to the base utility to credit the "Heating plant $-002$ " the appropriate amount of load throughout the year.
End of Summary

Collector Info	Collector Info				Domestic Hot Water	Hot Water				Spac	Space Heating				Renewable En	Renewable Energy Production
Day to DHW flat plate System Effective System Domestic Hot Water Domestic Hot Water Extra	System Effective System Domestic Hot Water Domestic Hot Water	System Effective System Domestic Hot Water Domestic Hot Water	Domestic Hot Water Domestic Hot Water	Domestic Hot Water		Extra	Extra Capacity not				Outdoor Air	Heating	Heating Requirment	DHW + Space Heating	SHW Capacity Credited	SHW Capacity Credited Extra Capacity Credited to
Month collector area Capacity Capacity Load per Day Load per Month used	Capacity Capacity Load per Day Load per Month	Capacity Capacity Load per Day Load per Month	Load per Day Load per Month	Load per Month		nsed	used by DHW Load	Peak Heating	HDD per	Assumed Indoor	Temperature	Requirement	for the Month	Requirement	to DHW Load	Space Heating
Month (BTU/sf*day) Conversion (sf) (BTU/month) (BTU/month) (BTU/month) (BTU/month)	(sf) (BTU/month) (BTU/month) (BTU/day) (BTU/month)	(BTU/month) (BTU/day) (BTU/month)	(BTU/month) (BTU/day) (BTU/month)	(BTU/month)			(BTU/month)	Load (BTU/h)	Month	Month Temperature (°F)	(°F)	(BTU/month)	(kBTU)	(BTU/month)	(BTU/month)	(BTU/month)
26 240.9 4977524 4479772 133106 3460756	240.9 4977524 4479772 133106	4977524 4479772 133106	4 4479772 133106				1019016	38000	480	89	27.1	10703178	10703	14163934	3460756	1019016
24 240.9 6034834 5431351 133106 3194544	6034834 5431351 133106	6034834 5431351 133106	5431351 133106			_	2236807	38000	350	89	27.1	7804401	7804	10998945	3194544	2236807
27 240.9 9096264 8186637 133106 3593862	9096264 8186637 133106	9096264 8186637 133106	8186637 133106			_	4592775	38000	202	89	27.1	4504254	4504	8098116	3593862	4504254
25 240.9 10608032 9547228 133106 3327650	10608032 9547228 133106	10608032 9547228 133106	9547228 133106	133106			6219578	38000	74	89	27.1	1650073	1650	4977723	3327650	1650073
27 240.9 12047915 10843123 133106 3593862	12047915 10843123 133106	12047915 10843123 133106	5 10843123 133106		3593862	_	7249261	38000	7	89	27.1	156088	156	3749950	3593862	156088
26 240.9 11551589 10396430 133106 3460756	240.9 11551589 10396430 133106	11551589 10396430 133106	10396430	133106		_	6935674	38000	0	89	27.1	0	0	3460756	3460756	0
26 240.9 11170774 10053697 133106 3460756	240.9 11170774 10053697 133106	11170774 10053697 133106	10053697	133106	0.00		6592941	38000	0	89	27.1	0	0	3460756	3460756	0
27 240.9 10542820 9488538 133106 3593862	10542820 9488538 133106	10542820 9488538 133106	9488538 133106				5894676	38000	0	89	27.1	0	0	3593862	3593862	0
25 240.9 8212883 7391595 133106 3327650	8212883 7391595 133106	8212883 7391595 133106	3 7391595 133106			0	4063945	38000	2	89	27.1	44597	45	3372247	3327650	44597
27 240.9 7913782 7122404 133106 3593862	7913782 7122404 133106	7913782 7122404 133106	2 7122404 133106		359386	25	3528542	38000	57	89	27.1	1271002	1271	4864864	3593862	1271002
26 240.9 5894486 5305037 133106 3460756	5894486 5305037 133106	5894486 5305037 133106	5305037 133106	2020	2020	9	1844281	38000	211	89	27.1	4704939	4705	8165695	3460756	1844281
26 240.9 4720725 4248652 133106 3460756	4720725 4248652 133106	4720725 4248652 133106	5 4248652 133106			99	787896	38000	416	89	27.1	9276088	9276	12736844	3460756	787896

Fotal System Use	per Unit Total System Use Energy Conversion (1	per Unit Total System Use Energy Conversion (1	Fotal System Use Energy Conversion (1
Fotal System Use	per Unit Total System Use	per Unit Total System Use	System Information System Heat Price per Unit Total System Use
Total System Use	Total System Use	Fotal System Use	System Heat Price per Unit Total System Use
	per Unit	per Unit	System Heat Price per Unit
	Price per Unit	System Heat Price per Unit	5

55043	8172	6.74 kBTU/sf
Total System Use (kBTU)	Building Conditioned Area (sf)	Annual Renewable Energy Production

#### **CIC RA 5-9 Adapt-Build Prototype**

Location Fort Stewart, GA

Building owner US Army Corp of Engineers

Program user JPB

Company Parsons Brinckerhoff

Comments TRACE 700 v6\_2\_7 - gbXML imported on Thursday, May

03, 2012 at 02:39 PM

By PB

Dataset name C:\DOCUMENTS AND

SETTINGS\BOULEY\DESKTOP\TRACE DOCS\CIDC\RA

5-9\120416\5-9\_120817.TRC

Calculation time **08:27 AM on 08/20/2012** 

TRACE® 700 version 6.2.7

Location

Hunter AAF, GA

Latitude 32.0 deg Longitude 81.2 deg

Time Zone 5
Elevation 0

Elevation 0 ft
Barometric pressure 30.3 in. Hg

Air density 0.0770 lb/cu ft
Air specific heat 0.2444 Btu/lb·°F
Density-specific heat product 1.1299 Btu/h·cfm·°F

Latent heat factor 4,973.7 Btu·min/h·cu ft
Enthalpy factor 4.6224 lb·min/hr·cu ft

Summer design dry bulb 93 °F Summer design wet bulb 78 °F Winter design dry bulb 29 °F

Summer clearness number 1.00
Winter clearness number 1.00
Summer ground reflectance 0.20
Winter ground reflectance 0.20

Carbon Dioxide Level 400 ppm

Design simulation period January - December

Cooling load methodology TETD-TA1
Heating load methodology UATD





#### Single Zone **Default System**

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 5/9 : 73/61/5	59	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design 9	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0		0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	-8	-8	-4	0	0		0	-55	3.28
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	136	68	204	107 ;	173	91		-1,271	-1,613	96.59
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0	0		0	0	0.00
Adjacent Floor	0	0	0	0 }	0	0		0	0	0
Infiltration	-6		-6	-3	-3	-2		-11	-11	0.66
Sub Total ==>	130	60	189	100	170	89	Sub Total ==>	-1,282	-1,679	100.53
Internal Loads							Internal Loads			
Lights	0	0	0	0 :	0	0	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	0	0	0	0	0	0	Sub Total ==>	0	0	0.00
Ceiling Load	-31	31	0	0	21	11	Ceiling Load	-388	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	· ·	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0:	0	0	Exhaust Heat	· ·	9	-0.53
Exhaust Heat	U	1	1	0 :	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		1	0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0:			Additional Neneal		U	0.00
Underfir Sup Ht Pku	ın	O	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	99	91	190	100.00	191	100.00	Grand Total ==>	-1,670	-1,670	100.00

TEMPE	RATURE	s
	Cooling	Heating
SADB	80.0	55.0
Ra Plenum	78.3	33.6
Return	78.3	33.6
Ret/OA	78.3	33.6
Fn MtrTD	0.0	0.0
Fn BldTD	0.1	0.0
Fn Frict	0.2	0.0

AIRFI	Lows	
	Cooling	Heating
Diffuser	0	0
Terminal Main Fan	0 0	0 0
Sec Fan	0	0
Nom Vent	0	0
AHU Vent	0	0
Infil	0	0
MinStop/Rh	0	0
Return	0	0
Exhaust	0	0
Rm Exh	0	0
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGIN	EERING CI	KS
	Cooling	Heating
% OA	0.0	0.0
cfm/ft <sup>2</sup>	0.00	0.00
cfm/ton	0.00	
ft²/ton	0.00	
Btu/hr·ft²	0.00	0.00
No. People	0	
•		

			COOLING	COIL SELI	ECTIO	N				
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Ente °F	er DB/W °F	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	0.0 0.0	0.0 0.0	0.0 0.0	0	0.0	0.0	56.8 0.0	0.0 0.0	0.0	56.8 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.0	0.0								

Gro	AREAS oss Total	Glass	s (%)
Floor Part	57 5,742		
Int Door ExFIr	0		
Roof Wall	57 384	0	0 0
Ext Door	0	0	0

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	0.0	0	0.0	0.0				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	33.6	79.7				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	0.0							

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 002 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HI	lr: 7 / 14 R: 93 / 77 / 1	13	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads				` ' ;		` ,	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,813	1,813	8	0	0	Roof Cond	0	-1,112	6.09
Glass Solar	895	0	895	4	2,169	24	Glass Solar	0	0	0.00
Glass/Door Cond	274	0	274	1	154	2	Glass/Door Cond	-742	-742	4.06
Wall Cond	1,191	716	1,907	8 :	1,428	16	Wall Cond	-1,094	-1,772	9.71
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	225		225	1	53	1	Infiltration	-181	-181	0.99
Sub Total ==>	2,586	2,528	5,114	22	3,804	43	Sub Total ==>	-2,017	-3,807	20.86
Internal Loads				:			Internal Loads			
Lights	1,732	433	2,165	9	1,732	19	Lights	0	0	0.00
People	1,800	0	1,800	8	1,000	11	People	0	0	0.00
Misc	1,534	0	1,534	7	1,534	17	Misc	0	0	0.00
Sub Total ==>	5,066	433	5,499	24	4,266	48	Sub Total ==>	0	0	0.00
Ceiling Load	802	-802	0	0	651	7	Ceiling Load	-482	0	0.00
Ventilation Load	0	0	13,029	56	0	0	Ventilation Load	0	-6,004	32.89
Adj Air Trans Heat	188	· ·	188	1	188	•	Adj Air Trans Heat	-331	-331	2
Dehumid. Ov Sizing	100		0	0	100	_	Ov/Undr Sizing	-4,259	-4.259	23.33
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	-4,200	352	-1.93
Exhaust Heat	U	-1,073	-1,073	-5 :	U	U	OA Preheat Diff.		-2,859	15.66
Sup. Fan Heat		-1,073	180	-3 , 1 ;			RA Preheat Diff.		-1,345	7.37
Ret. Fan Heat		133	133	1			Additional Reheat		-1,545	0.00
Duct Heat Pkup		0	0	0			Additional Nemeat		O	0.00
Underfir Sup Ht Pku	n	0	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	۲	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	8,642	1,219	23,070	100.00	8,910	100.00	Grand Total ==>	-7,089	-18,253	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	85.0					
Ra Plenum	79.2	67.5					
Return	79.5	67.5					
Ret/OA	86.0	56.7					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	461	461						
Terminal	461	461						
Main Fan	461	461						
Sec Fan	0	0						
Nom Vent	224	128						
AHU Vent	224	128						
Infil	4	4						
MinStop/Rh	0	0						
Return	450	456						
Exhaust	212	123						
Rm Exh	49	29						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

Cooling         Heating           % OA         48.4         27.8           cfm/ft²         0.77         0.77           cfm/ton         208.69         69           ft²/ton         271.11         8tu/hr-ft²         44.26         -31.63           No. People         4         4         4         4	ENGINEERING CKS						
cfm/ft²         0.77         0.77           cfm/ton         208.69         69           ft²/ton         271.11         8tu/hr·ft²         44.26         -31.63	Cooling Heating						
cfm/ton         208.69           ft²/ton         271.11           Btu/hr·ft²         44.26         -31.63	% OA	48.4	27.8				
ft²/ton 271.11 Btu/hr·ft² 44.26 -31.63	cfm/ft <sup>2</sup>	0.77	0.77				
Btu/hr·ft² 44.26 -31.63	cfm/ton	208.69					
	ft²/ton	271.11					
No. People 4	Btu/hr·ft²	44.26	-31.63				
	No. People	4					

COOLING COIL SELECTION												
	Total Capacity									Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb		
Main Clg	2.2	26.5	15.7	461	86.0	70.5	86.0	55.0	52.7	54.9		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	2.2	26.5										

Gro	AREAS oss Total	Glass	s (%)
Floor Part	599 3,456		
Int Door	0		
ExFlr Roof	0 599	0	0
Wall	392	40	10
Ext Door	0	0	0

HEATING COIL SELECTION							
	Capacity	Coil Airflow	<b>Ent</b>	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-19.0	461	48.6	85.0			
Aux Htg	0.0	0	0.0	0.0			
Preheat	-4.2	461	48.6	55.0			
Humidif	0.0	0	0.0	0.0			
Opt Vent	0.0	0	0.0	0.0			
Total	-19.0						

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 003 Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads				` ':		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	971	971	8	0	0	Roof Cond	0	-561	6.36
Glass Solar	733	0	733	6	1,325	25	Glass Solar	0	0	0.00
Glass/Door Cond	443	0	443	3	299	6	Glass/Door Cond	-1,113	-1,113	12.61
Wall Cond	1,094	638	1,732	14 :	1,228	23	Wall Cond	-1,405	-2,277	25.79
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	122		122	1	32	1	Infiltration	-94	-94	1.06
Sub Total ==>	2,392	1,609	4,002	31	2,884	55	Sub Total ==>	-2,612	-4,045	45.82
Internal Loads							Internal Loads			
Lights	932	233	1,165	9	932	18	Lights	0	0	0.00
People	450	0	450	4	250	5	People	0	0	0.00
Misc	794	0	794	6	794	15	Misc	0	0	0.00
Sub Total ==>	2,177	233	2,410	19	1,977	38	Sub Total ==>	0	0	0.00
Ceiling Load	443	-443	0	0	405	8	Ceiling Load	-345	0	0.00
Ventilation Load	0	0	6,810	53	0	0	Ventilation Load	0	-2,998	33.96
Adj Air Trans Heat	0	· ·	0,010	0 :	0	•	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0 :	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	· ·	261	-2.96
Exhaust Heat	U	-612	-612	-5:	U	U	OA Preheat Diff.		-1,428	16.17
Sup. Fan Heat		٠.ــ	107	1			RA Preheat Diff.		-619	7.01
Ret. Fan Heat		81	81	1			Additional Reheat		0.0	0.00
Duct Heat Pkup		0	0	0					Ŭ	3.30
Underfir Sup Ht Pku	D	,	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	5,012	868	12,797	100.00	5,266	100.00	Grand Total ==>	-2,957	-8,829	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	82.0					
Ra Plenum	79.5	66.5					
Return	79.8	66.5					
Ret/OA	85.3	57.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	273	273						
Terminal Main Fan	273 273	273 273						
Sec Fan	0	0						
Nom Vent	112	64						
AHU Vent	112	64						
Infil	2	2						
MinStop/Rh	0	0						
Return	275	275						
Exhaust	114	66						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS									
Cooling Heating									
% OA	40.9	23.4							
cfm/ft²	0.88	0.88							
cfm/ton	222.36								
ft²/ton	253.06								
Btu/hr·ft <sup>2</sup>	47.42	-30.83							
No. People	1								

	COOLING COIL SELECTION										
		Total Capacity		Coil Airflow		er DB/W				WB/HR	
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb	
Main Clg	1.2	14.7	9.2	273	85.3	69.6	81.8	55.0	52.6	54.5	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	1.2	14.7									

Gro	AREAS	Glass	-
		ft²	(%)
Floor	310		
Part	1,236		
Int Door	0		
ExFlr	0		
Roof	310	0	0
Wall	517	60	12
Ext Door	0	0	0

HEATING COIL SELECTION										
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F						
Main Htg	-9.6	273	50.9	82.0						
Aux Htg	0.0	0	0.0	0.0						
Preheat	-1.6	273	50.9	55.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent	0.0	0	0.0	0.0						
Total	-9.6									

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 004 Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/F OADB/WB/HI	lr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	2,199	2,199	8	0	0	Roof Cond	0	-1,375	7.35
Glass Solar	1,084	0	1,084	4 ;	1,085	11	Glass Solar	0	0	0.00
Glass/Door Cond	682	0	682	2 ;	713	7		-1,855	-1,855	9.92
Wall Cond	1,351	779	2,130	8 ;	1,411	14		-2,131	-3,484	18.63
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	284		284	1	99	1	Infiltration	-229	-229	1.22
Sub Total ==>	3,402	2,977	6,379	23	3,307	34	Sub Total ==>	-4,215	-6,943	37.12
Internal Loads							Internal Loads			
Lights	2,272	568	2,840	10	2,272	23	Lights	0	0	0.00
People	2,250	0	2,250	8	1,250	13	People	0	0	0.00
Misc	1,937	0	1,937	7:	1,937	20	Misc	0	0	0.00
Sub Total ==>	6,459	568	7,027	25	5,459	56	Sub Total ==>	0	0	0.00
Ceiling Load	1,037	-1,037	0	0	1,048	11	Ceiling Load	-798	0	0.00
Ventilation Load	0	0	15,917	56	0		Ventilation Load	0	-7,335	39.21
Adj Air Trans Heat	0	· ·	0	0 :	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0		-	Ov/Undr Sizing	-3	-3	0.02
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	-	607	-3.24
Exhaust Heat	Ū	-1.441	-1,441	-5	o o	· ·	OA Preheat Diff.		-3.493	18.67
Sup. Fan Heat		.,	199	1			RA Preheat Diff.		-1,538	8.22
Ret. Fan Heat		152	152	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					· ·	0.50
Underfir Sup Ht Pku	D	,	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	۲	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	10,897	1,219	28,232	100.00	9,814	100.00	Grand Total ==>	-5,016	-18,706	100.00

TEMPERATURES									
	Cooling	Heating							
SADB	55.4	80.9							
Ra Plenum	79.3	66.7							
Return	79.6	66.7							
Ret/OA	87.0	54.9							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS										
	Cooling	Heating								
Diffuser	508	508								
Terminal Main Fan	508 508	508 508								
Sec Fan	0	0								
Nom Vent	273	156								
AHU Vent	273	156								
Infil	5	5								
MinStop/Rh	0	0								
Return	513	513								
Exhaust	278	161								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS									
Cooling Heating									
% OA	53.7	30.8							
cfm/ft <sup>2</sup>	0.67	0.67							
cfm/ton	187.84								
ft²/ton	279.62								
Btu/hr·ft²	42.92	-26.38							
No. People	5								

			COOLING	COIL SEL	ECTIC	N				
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/ <b>WB/HR</b> gr/lb
Main Clg Aux Clg	2.7 0.0	32.5 0.0	19.3 0.0	508 0	87.0 0.0	71.7 0.0	90.9 0.0	55.0 0.0	52.1 0.0	52.5 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	2.7	32.5								

	AREA	S	
Gro	ss Total	Glass ft <sup>2</sup>	
	11	(%)	
Floor	757		
Part	6,245		
Int Door	0		
ExFlr	0		
Roof	757	0	0
Wall	799	100	13
Ext Door	0	0	0

HEATING COIL SELECTION										
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-20.0	508	46.2	80.9						
Aux Htg	0.0	0	0.0	0.0						
Preheat	-6.4	508	46.2	55.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent	0.0		0.0	0.0						
Total	-20.0									

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 005 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads				` ' ;		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,244	1,244	9	0	0	Roof Cond	0	-724	7.02
Glass Solar	185	0	185	1	178	4	Glass Solar	0	0	0.00
Glass/Door Cond	516	0	516	4	526	11	Glass/Door Cond	-1,313	-1,313	12.72
Wall Cond	835	452	1,286	9 ;	868	18	Wall Cond	-1,242	-1,992	19.30
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	156		156	1	52	1	Infiltration	-121	-121	1.17
Sub Total ==>	1,692	1,695	3,388	23	1,624	33	Sub Total ==>	-2,676	-4,151	40.22
Internal Loads				:			Internal Loads			
Lights	1,641	410	2,051	14	1,641	33	Lights	0	0	0.00
People	0	0	2,001	0	0	0	People	0	0	0.00
Misc	1,025	0	1,025	7:	1,025	21	Misc	0	0	0.00
Sub Total ==>	2,666	410	3,076	21	2,666	54	Sub Total ==>	0	0	0.00
Ceiling Load	639	-639	0	0	632	13	Ceiling Load	-448	0	0.00
Ventilation Load	0	0	8,682	60	0	0	Ventilation Load	0	-3,869	37.49
Adj Air Trans Heat	0	· ·	0,002	0:	0	•	Adj Air Trans Heat	0	0,000	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	ŭ	339	-3.29
Exhaust Heat	U	-878	-878	-6 ·	U	U	OA Preheat Diff.		-1,843	17.85
Sup. Fan Heat		5.5	100	1			RA Preheat Diff.		-798	7.73
Ret. Fan Heat		76	76	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					Ŭ	0.50
Underfir Sup Ht Pku	D	,	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r <del>.</del>	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	4,998	664	14,443	100.00	4,922	100.00	Grand Total ==>	-3,124	-10,321	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	83.6					
Ra Plenum	80.0	66.5					
Return	66.5						
Ret/OA	87.7	54.2					
Fn MtrTD	0.0	0.0					
<b>Fn BldTD</b> 0.1 0.0							
Fn Frict	0.2	0.0					

AIRFLOWS									
Cooling Heating									
Diffuser	255	255							
Terminal Main Fan	255 255	255 255							
Sec Fan	0	0							
Nom Vent	144	83							
AHU Vent	144	83							
Infil	3	3							
MinStop/Rh	0	0							
Return	258	258							
Exhaust	147	85							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	56.5	32.4					
cfm/ft <sup>2</sup>	0.64	0.64					
cfm/ton	184.17						
ft²/ton	289.40						
Btu/hr·ft²	41.47	-27.72					
No. People	0						

COOLING COIL SELECTION										
	<b>Total</b> (	Capacity MBh	<b>Sens Cap.</b> MBh	Coil Airflow cfm	Ent °F	er DB/W °F	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	1.4 0.0	16.6 0.0	10.0 0.0	255 0	87.7 0.0	71.9 0.0	91.1 0.0	55.0 0.0	51.9 0.0	52.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.4	16.6								

	AREAS	3	
Gro	ss Total	Glas ft²	s (%)
Floor	401		
Part	1,779		
Int Door	0		
ExFlr	0		
Roof	401	0	0
Wall	400	0	0
Ext Door	45	45	100

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F					
Main Htg Aux Htg	-11.1 0.0	255 0	45.0 0.0	83.6 0.0					
Preheat	-3.6	255	45.0	55.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-11.1	Ü	0.0	3.0					

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 006 Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads					_		Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	399	399	8	0	0	Roof Cond	0	-250	6.60
Glass Solar	94	0	94	2 ;	94	5	Glass Solar	0	0	0.00
Glass/Door Cond	251	0	251	5;	262	15	Glass/Door Cond	-691	-691	18.27
Wall Cond	257	153	410	8 ;	268	15	Wall Cond	-405	-674	17.81
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	54		54	1 ;	18	1		-42	-42	1.10
Sub Total ==>	655	552	1,206	24	642	36	Sub Total ==>	-1,138	-1,656	43.78
Internal Loads							Internal Loads			
Lights	565	141	706	14	565	32	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	353	0	353	7	353	20	Misc	0	0	0.00
Sub Total ==>	918	141	1,060	21	918	52	Sub Total ==>	0	0	0.00
Ceiling Load	204	-204	0	0 :	207	12	Ceiling Load	-153	0	0.00
Ventilation Load	0	0	2,994	59	0	0	Ventilation Load	0	-1,333	35.23
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0;	-		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	116	-3.06
Exhaust Heat	Ü	-282	-282	-6 ·	O .	U	OA Preheat Diff.		-635	16.78
Sup. Fan Heat			36	1			RA Preheat Diff.		-275	7.28
Ret. Fan Heat		27	27	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			x		· ·	2.30
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 }			Supply Air Leakage		0	0.00
Grand Total ==>	1,778	234	5,042	100.00	1,767	100.00	Grand Total ==>	-1,291	-3,783	100.00

TEMPERATURES							
Cooling Heating							
55.4	85.6						
79.7	66.5						
79.9	66.5						
87.2	54.7						
0.0	0.0						
<b>Fn BldTD</b> 0.1 0.0							
0.2	0.0						
	55.4 79.7 79.9 87.2 0.0 0.1						

AIRFLOWS						
7	Cooling	Heating				
Diffuser	92	92				
Terminal Main Fan	92 92	92 92				
Sec Fan	0	0				
Nom Vent	50	28				
AHU Vent	50	28				
Infil	1	1				
MinStop/Rh	0	0				
Return	92	92				
Exhaust	51	29				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS							
Cooling Heating							
% OA	54.2	31.1					
cfm/ft²	0.66	0.66					
cfm/ton	189.42						
ft²/ton	285.57						
Btu/hr·ft²	42.02	-29.76					
No. People	0						

COOLING COIL SELECTION										
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB/ °F	WB/HR gr/lb
Main Clg	0.5	5.8	3.5	92	87.2	71.6	89.8	55.0	52.1	52.5
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	5.8								

Gro	AREAS	Glas	s (%)
Floor Part	138 1,207		
Int Door ExFIr	0 0		
Roof Wall	138 135	0	0
Ext Door	24	24	100

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F				
Main Htg Aux Htg	-4.1 0.0	92 0	45.9 0.0	85.6 0.0				
Preheat	-1.2	92	45.9	55.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-4.1							

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 007 Single Zone

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	I at Time: itside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	477	477	10 :	0	0	Roof Cond	0	-296	10.32
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	61		61	1	21	2	Infiltration	-48	-48	1.67
Sub Total ==>	61	477	538	11	21	2	Sub Total ==>	-48	-344	12.00
Internal Loads							Internal Loads			
Lights	650	162	812	17	650	49	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	406	0	406	8	406	31	Misc	0	0	0.00
Sub Total ==>	1,056	162	1,218	25	1,056	80	Sub Total ==>	0	0	0.00
Ceiling Load	249	-249	0	0	249	19	Ceiling Load	-115	0	0.00
Ventilation Load	0	0	3,387	70	0	0	Ventilation Load	0	-1,533	53.42
Adj Air Trans Heat	0	· ·	0,00.	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat		87	-3.05
Exhaust Heat	·	-342	-342	-7	· ·	ŭ	OA Preheat Diff.		-730	25.44
Sup. Fan Heat			27	1			RA Preheat Diff.		-350	12.20
Ret. Fan Heat		21	21	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					-	
Underfir Sup Ht Pku	0		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 }			Supply Air Leakage		0	0.00
Grand Total ==>	1,366	69	4,848	100.00	1,326	100.00	Grand Total ==>	-163	-2,869	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	72.6					
Ra Plenum	80.0	67.7					
Return	80.2	67.7					
Ret/OA	91.2	49.1					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	69	69						
Terminal Main Fan	69 69	69 69						
Sec Fan	0	0						
Nom Vent	57	33						
AHU Vent	57	33						
Infil	1	1						
MinStop/Rh	0	0						
Return	70	70						
Exhaust	58	34						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	83.1	47.6					
cfm/ft <sup>2</sup>	0.43	0.43					
cfm/ton	147.84						
ft²/ton	341.50						
Btu/hr·ft²	35.14	-18.34					
No. People	0						

COOLING COIL SELECTION										
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>/B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/ <b>WB/HR</b> gr/lb
Main Clg Aux Clg	0.5 0.0	5.6 0.0	3.0 0.0	69 0	91.2 0.0	75.4 0.0	106.1 0.0	55.0 0.0	51.5 0.0	50.4 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	5.6								

AREAS Gross Total Glass ft² (%)							
Floor Part	159 952						
Int Door ExFir	0 0						
Roof Wall	159 0	0 0	0 0				
Ext Door	0	0	0				

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F					
Main Htg Aux Htg	-2.9 0.0	69 0	35.1 0.0	72.6 0.0					
Preheat	-1.9	69	35.1	55.0					
Humidif Opt Vent	0.0	0	0.0	0.0 0.0					
Total	-2.9	U	0.0	0.0					

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 008 Single Zone

•	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	at Time: tside Air:	Mo/H OADB/WB/HI	lr: 7 / 16 R: 93 / 77 / 1	13	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,520	1,520	4	0	0	Roof Cond	0	-1,085	4.19
Glass Solar	4,272	0	4,272	12	5,383	43	Glass Solar	0	0	0.00
Glass/Door Cond	1,409	0	1,409	4	1,309	10	Glass/Door Cond	-3,584	-3,584	13.84
Wall Cond	2,123	1,450	3,573	10 :	2,299	18	Wall Cond	-1,909	-3,235	12.49
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0:	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	209		209	1	64	1	Infiltration	-177	-177	0.68
Sub Total ==>	8,013	2,970	10,983	32	9,055	73	Sub Total ==>	-5,671	-8,082	31.21
Internal Loads							Internal Loads			
Lights	1,281	320	1,601	5	1,281	10	Lights	0	0	0.00
People	0	0	0	0:	0	0	People	0	0	0.00
Misc	1,501	0	1,501	4	1,501	12		0	0	0.00
Sub Total ==>	2,781	320	3,101	9	2,781	22	Sub Total ==>	0	0	0.00
Ceiling Load	648	-648	0	0	652	5	Ceiling Load	-486	0	0.00
Ventilation Load	0	0	21,911	63	0	0	Ventilation Load	0	-10,772	41.60
Adj Air Trans Heat	0	O	21,311	0:	0	•	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	-205	-205	0.79
Ov/Undr Sizing	0		0	0 :	0	٥	Exhaust Heat	200	691	-2.67
Exhaust Heat	U	-1.764	-1,764	-5 :	U	U	OA Preheat Diff.		-5,130	19.81
Sup. Fan Heat		1,70-7	253	1			RA Preheat Diff.		-2,397	9.26
Ret. Fan Heat		193	193	1			Additional Reheat		-2,337	0.00
Duct Heat Pkup		0	0	0			, Additional Ronout		O	0.00
Underfir Sup Ht Pkup	,	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	-	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	11,442	1,070	34,677	100.00	12,488	100.00	Grand Total ==>	-6,363	-25,894	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.4	80.8							
Ra Plenum	78.5	67.4							
Return	78.9	67.4							
Ret/OA	87.6	53.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS										
Cooling Heating										
Diffuser	647	647								
Terminal	647	647								
Main Fan	647	647								
Sec Fan	0	0								
Nom Vent	401	230								
AHU Vent	401	230								
Infil	4	4								
MinStop/Rh	0	0								
Return	651	651								
Exhaust	405	234								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS								
Cooling Heating								
% OA	62.0	35.5						
cfm/ft <sup>2</sup>	1.10	1.10						
cfm/ton	194.61							
ft²/ton	176.41							
Btu/hr·ft²	68.02	-46.79						
No. People	0							

			COOLING	G COIL SEL	ECTIC	N				
	Total Capacity ton MBh				<b>Enter DB/WB/HR</b> °F °F gr/lb			<b>Leave DB/WB/HF</b> °F °F gr/lb		
Main Clg	3.3	39.9	23.2	647	86.8	71.5	90.3		52.6	54.5 0.0
Aux Clg Opt Vent	0.0 0.0	0.0 0.0	0.0	0	0.0	0.0 0.0	0.0 0.0	0.0	0.0	0.0
Total	3.3	39.9								

AREAS Gross Total Glass ft² (%)							
Floor Part	586 2,742						
Int Door ExFIr	0						
Roof Wall	586 645	0 0	0 0				
Ext Door	124	124	100				

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F					
Main Htg Aux Htg	-27.4 0.0	647 0	43.3 0.0	80.8 0.0					
Preheat	-10.7	647	43.3	55.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-27.4								

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 009 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING C	OIL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	7 / 16 1: 93 / 77 / 1	13	Mo/Hr: OADB:			Mo/Hr: H OADB: 2	eating Design 29	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i e	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				` ':		` '	Envelope Loads			, ,
Skylite Solar	0	0	0	0:	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	484	484	7	0	0	Roof Cond	0	-307	7.84
Glass Solar	515	0	515	8	909	31	Glass Solar	0	0	0.00
Glass/Door Cond	143	0	143	2	125	4	Glass/Door Cond	-371	-371	9.47
Wall Cond	361	239	600	9 :	504	17	Wall Cond	-339	-570	14.54
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0:	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	63		63	1	15	1	Infiltration	-50	-50	1.27
Sub Total ==>	1,081	723	1,804	27	1,552	53	Sub Total ==>	-759	-1,298	33.13
Internal Loads							Internal Loads			
Lights	496	124	620	9	496	17	Lights	0	0	0.00
People	450	0	450	7:	250	9	, 5	0	0	0.00
Misc	423	0	423	6	423	15		0	0	0.00
Sub Total ==>	1,368	124	1,492	23	1,168	40		0	0	0.00
Ceiling Load	198	-198	0	0	182	6	Ceiling Load	-126	0	0.00
Ventilation Load	0	0	3,487	53	0		Ventilation Load	0	-1,595	40.71
Adj Air Trans Heat	0	· ·	0, 101	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	Ü		0	0	ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	o:	0	٥	Exhaust Heat	· ·	96	-2.44
Exhaust Heat	U	-277	-277	-4	U	U	OA Preheat Diff.		-759	19.39
Sup. Fan Heat			59	1			RA Preheat Diff.		-361	9.21
Ret. Fan Heat		45	45	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	o:					ŭ	0.00
Underfir Sup Ht Pku	p	-	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	2,648	416	6,611	100.00	2,903	100.00	Grand Total ==>	-886	-3,917	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.4	76.5							
Ra Plenum	78.8	67.6							
Return	79.1	67.6							
Ret/OA	84.5	58.8							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS										
Cooling Heating										
Diffuser	150	150								
Terminal Main Fan	150 150	150 150								
Sec Fan	0	0								
Nom Vent	59	34								
AHU Vent	59	34								
Infil	1	1								
MinStop/Rh	0	0								
Return	151	151								
Exhaust	60	35								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS									
Cooling Heating									
% OA	39.5	22.6							
cfm/ft <sup>2</sup>	0.91	0.91							
cfm/ton	237.27								
ft²/ton	260.58								
Btu/hr·ft²	46.05	-25.07							
No. People	1								

			COOLING	COIL SEL	ECTIC	N				
	Total (	Capacity	Sens Cap.	<b>Coil Airflow</b>	Ent	Leave DB/WB/HR				
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.6	7.6	4.7	150	84.5	69.1	80.5	55.0	53.2	56.6
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.6	7.6								

Gro	AREAS	Glass	s (%)
Floor Part	165 1,438		
Int Door ExFIr	0		
Roof Wall	165 133	0 20	0 15
Ext Door	0	0	0

HEATING COIL SELECTION						
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F		
Main Htg Aux Htg	-4.1 0.0	150 0	52.2 0.0	76.5 0.0		
Preheat	-0.6	150	52.2	55.0		
Humidif	0.0	0	0.0	0.0		
Opt Vent	0.0	0	0.0	0.0		
Total	-4.1					

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 010 Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	i i	Btu/h	Btu/h	(%)
Envelope Loads				(,0)		(70)	Envelope Loads			(,,,
Skylite Solar	0	0	0	0:	0	0		0	0	0.00
Skylite Cond	0	0	0	0 :	0	0		0	0	0.00
Roof Cond	0	1,327	1,327	10	0	0	Roof Cond	0	-763	8.22
Glass Solar	0	0	0	0 :	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	1,256	602	1,858	13	1,354	32	Wall Cond	-1,257	-1,893	20.40
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0:	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 ;	0	0	Adjacent Floor	0	0	0
Infiltration	163		163	1	55	1		-128	-128	1.38
Sub Total ==>	1,419	1,930	3,349	24	1,409	34	Sub Total ==>	-1,385	-2,784	29.99
Internal Loads							Internal Loads			
Lights	925	231	1.156	8	925	22	Lights	0	0	0.00
People	0	0	0	0;	0.20	0		0	0	0.00
Misc	1,084	0	1,084	8	1,084	26	Misc	0	0	0.00
Sub Total ==>	2,009	231	2,240	16	2,009	48	Sub Total ==>	0	0	0.00
Ceiling Load	760	-760	0	0 :	751	18	Ceiling Load	-492	0	0.00
Ventilation Load	0	0	9,108	66	0		Ventilation Load	0	-4,090	44.07
Adj Air Trans Heat	0	•	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	Ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	· ·	373	-4.02
Exhaust Heat	U	-1,039	-1,039	-8:	U	U	OA Preheat Diff.		-1.948	20.99
Sup. Fan Heat		1,000	84	1:			RA Preheat Diff.		-833	8.97
Ret. Fan Heat		65	65	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			Additional Notical		O	0.00
Underfir Sup Ht Pku	n	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	۲	0	0	0 ;			Supply Air Leakage		0	0.00
Grand Total ==>	4,189	426	13,807	100.00	4,170	100.00	Grand Total ==>	-1,877	-9,282	100.00

TEMPERATURES						
Cooling Heating						
55.4	79.6					
80.7	66.3					
80.9	66.3					
89.7	51.1					
0.0	0.0					
0.1	0.0					
0.2	0.0					
	<b>Cooling</b> 55.4 80.7 80.9 89.7 0.0 0.1					

AIRFLOWS						
	Cooling	Heating				
Diffuser	216	216				
Terminal Main Fan	216 216	216 216				
Sec Fan	0	0				
Nom Vent	152	87				
AHU Vent	152	87				
Infil	3	3				
MinStop/Rh	0	0				
Return	219	219				
Exhaust	155	90				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

	Cooling 70.5	Heating
	70.5	
% OA	70.5	40.4
cfm/ft <sup>2</sup>	0.51	0.51
cfm/ton	163.18	
ft²/ton	320.02	
Btu/hr·ft²	37.50	-23.03
No. People	0	

<b>Leave DB/WB/HF</b> °F °F gr/lb
°F °F ar/lh
1 1 91/15
55.0 51.8 51.6
0.0 0.0 0.0
0.0 0.0 0.0
)

Gros	AREAS ss Total	Glass	s (%)
Floor Part	423 909		
Int Door ExFIr	0 0		
Roof Wall	423 379	0 0	0 0
Ext Door	0	0	0

HEATING COIL SELECTION						
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F		
Main Htg	-9.8	216	39.7	79.6		
Aux Htg	0.0	0	0.0	0.0		
Preheat	-4.7	216	39.7	55.0		
Humidif	0.0	0	0.0	0.0		
Opt Vent	0.0	0	0.0	0.0		
Total	-9.8					

Project Name: CIC RA 5-9 Adapt-Build Prototype

Single Zone System - 011

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	l at Time: itside Air:	Mo/Hi OADB/WB/HR	7 / 15 : 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	858	858	9	0	0	Roof Cond	0	-551	9.71
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	109		109	1 ;	40	2		-90	-90	1.58
Sub Total ==>	109	858	966	10	40	2	Sub Total ==>	-90	-641	11.29
Internal Loads							Internal Loads			
Lights	666	167	833	9 :	666	31	Lights	0	0	0.00
People	450	0	450	5 :	250	12	People	0	0	0.00
Misc	759	0	759	8	759	35	Misc	0	0	0.00
Sub Total ==>	1,875	167	2,042	21	1,675	78	Sub Total ==>	0	0	0.00
Ceiling Load	433	-433	0	0	433	20	Ceiling Load	-233	0	0.00
Ventilation Load	0	0	7,318	76	0	0	Ventilation Load	0	-3,455	60.87
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	•		0	0;	-		Ov/Undr Sizing	-126	-126	2.21
Ov/Undr Sizing	5		5	0	5	0	Exhaust Heat		212	-3.73
Exhaust Heat	3	-813	-813	-8	3	U	OA Preheat Diff.		-1,131	19.94
Sup. Fan Heat			44	0			RA Preheat Diff.		-535	9.42
Ret. Fan Heat		39	39	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			x		· ·	2.30
Underfir Sup Ht Pkup	)		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,422	-184	9,600	100.00	2,153	100.00	Grand Total ==>	-449	-5,675	100.00

TEMPERATURES						
Cooling Heating						
SADB	55.4	74.2				
Ra Plenum	79.6	67.5				
Return	79.9	67.5				
Ret/OA	93.4	41.7				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.1	0.0				
Fn Frict	0.2	0.0				

AIRFLOWS								
Cooling Heating								
Diffuser	111	111						
Terminal	111	111						
Main Fan	111	111						
Sec Fan	0	0						
Nom Vent	129	74						
AHU Vent	129	74						
Infil	2	2						
MinStop/Rh	0	0						
Return	131	113						
Exhaust	148	76						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS									
Cooling Heating									
% OA	100.0	66.1							
cfm/ft²	0.38	0.38							
cfm/ton	121.17								
ft²/ton	322.43								
Btu/hr·ft²	37.22	-21.96							
No. People	1								

	COOLING COIL SELECTION											
	<b>Total (</b> ton	Capacity   Sens Cap.   Coil Airflow   Enter DB/WB/HR   MBh   Cfm   °F   °F   gr/lb						<b>Leave DB/WB/HR</b> °F °F gr/lb				
Main Clg Aux Clg	0.9 0.0	11.0 0.0	5.4 0.0	111 0	93.4 0.0	77.5 0.0	115.3 0.0	55.0 0.0	48.1 0.0	38.4 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.9	11.0										

	AREAS	3	
Gro	Glass ft <sup>2</sup>	s (%)	
Floor	297		(,,,
Part	2,693		
Int Door	0		
ExFlr	0		
Roof	297	0	0
Wall	0	0	0
Ext Door	0	0	0

HEATING COIL SELECTION									
	Capacity	Coil Airflow	<b>Ent</b>	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-6.5	111	22.5	74.2					
Aux Htg	0.0	0	0.0	0.0					
Preheat	-4.2	111	28.5	55.0					
Humidif	0.0	0	0.0	0.0					
Opt Vent	0.0		0.0	0.0					
Total	-6.5								

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 012 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design 9	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i .	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads						( /	Envelope Loads			( /
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	3,540	3,540	8	0	0	Roof Cond	0	-2,400	6.37
Glass Solar	0	0	0	0 :	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0	0	0		0	0	0.00
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0:	0	0		0	0	0.00
Adjacent Floor	0	0	0	0:	0	0	Adjacent Floor	0	0	0
Infiltration	460		460	1	168	2		-390	-390	1.04
Sub Total ==>	460	3,540	4,000	9	168	2		-390	-2,790	7.41
Internal Loads							Internal Loads			
Lights	2,644	661	3,305	7	2,644	25	Lights	0	0	0.00
People	4,500	0	4,500	10	2,500	24		0	0	0.00
Misc	3,301	0	3,301	7	3,301	31		0	0	0.00
Sub Total ==>	10,445	661	11,106	24	8,445	80	1	0	0	0.00
Ceiling Load	1.749	-1,749	0	0	1,770	17	Ceiling Load	-988	0	0.00
Ventilation Load	0	0	34,065	73	0		Ventilation Load	0	-16,558	43.98
Adj Air Trans Heat	191	ŭ	191	0	191	-	Adj Air Trans Heat	-518	-518	1
Dehumid. Ov Sizing			0	0 :		_	Ov/Undr Sizing	-10,012	-10,012	26.60
Ov/Undr Sizing	28		28	0 :	28	٥	Exhaust Heat	10,012	878	-2.33
Exhaust Heat	20	-2,949	-2,949	-6 :	20	U	OA Preheat Diff.		-5,862	15.57
Sup. Fan Heat		2,010	215	0;			RA Preheat Diff.		-2,783	7.39
Ret. Fan Heat		150	150	0:			Additional Reheat		2,700	0.00
Duct Heat Pkup		0	0	0:			, Additional Ronout		O	0.00
Underfir Sup Ht Pku	ın	J	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	12,873	-347	46,805	100.00	10,603	100.00	Grand Total ==>	-11,908	-37,645	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.4	90.0							
Ra Plenum	79.3	67.6							
Return	79.5	67.6							
Ret/OA	93.4	42.4							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS										
	Cooling	Heating								
Diffuser	549	549								
Terminal	549	549								
Main Fan	549	549								
Sec Fan	0	0								
Nom Vent	616	353								
AHU Vent	616	353								
Infil	8	8								
MinStop/Rh	0	0								
Return	507	517								
Exhaust	575	321								
Rm Exh	50	40								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS									
Cooling Heating									
% OA	100.0	64.3							
cfm/ft <sup>2</sup>	0.43	0.43							
cfm/ton	122.38								
ft²/ton	287.53								
Btu/hr·ft²	41.73	-31.87							
No. People	10								

	COOLING COIL SELECTION											
	<b>Total Capacity</b>		Sens Cap.	Coil Airflow		er DB/W				/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb		
Main Clg	4.5	53.8	26.8	549	93.4	77.5	115.3	55.0	48.5	39.7		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	4.5	53.8										

Gr	Glass	s (%)			
Floor	1,290				
Int Door	Part 14,789				
ExFlr	0				
Roof	1,290	0	0		
Wall	0	0	0		
Ext Door	0	0	0		

HEATING COIL SELECTION										
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F						
Main Htg Aux Htg	-41.1 0.0	549 0	23.7 0.0	90.0						
Preheat	-20.5	549	28.5	55.0						
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0						
Total	-41.1									

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 013 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HI	lr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,429	1,429	6	0	0	Roof Cond	0	-1,053	6.43
Glass Solar	1,036	0	1,036	4	2,185	24	Glass Solar	0	0	0.00
Glass/Door Cond	236	0	236	1	43	0	Glass/Door Cond	-742	-742	4.53
Wall Cond	1,636	901	2,536	10 ;	1,930	21	Wall Cond	-1,893	-2,976	18.18
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	226		226	1	36	0	Infiltration	-174	-174	1.06
Sub Total ==>	3,133	2,330	5,463	22	4,193	46	Sub Total ==>	-2,809	-4,944	30.21
Internal Loads							Internal Loads			
Lights	1,588	397	1,984	8	1,588	17	Lights	0	0	0.00
People	2,250	0	2,250	9:	1,250	14	People	0	0	0.00
Misc	1,469	0	1,469	6	1,469	16	Misc	0	0	0.00
Sub Total ==>	5,307	397	5,704	23	4,307	47		0	0	0.00
Ceiling Load	691	-691	0	0	592	7	Ceiling Load	-541	0	0.00
Ventilation Load	0	0	14,694	59	0		Ventilation Load	0	-6,464	39.50
Adj Air Trans Heat	0	· ·	0	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	Ū	· ·	Ov/Undr Sizing	-958	-958	5.85
Ov/Undr Sizing	0		0	0:	0	٥	Exhaust Heat	300	476	-2.91
Exhaust Heat	U	-1,093	-1,093	-4	U	U	OA Preheat Diff.		-3.078	18.81
Sup. Fan Heat		1,000	184	1			RA Preheat Diff.		-1,397	8.54
Ret. Fan Heat		141	141	1			Additional Reheat		-1,597	0.00
Duct Heat Pkup		0	0	0			- Additional Monout		O	0.00
Underfir Sup Ht Pku	n	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	٣	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	9,131	1,083	25,092	100.00	9,092	100.00	Grand Total ==>	-4,307	-16,366	100.00

TEMPERATURES							
	Cooling	Heating					
SADB	55.4	79.7					
Ra Plenum	78.8	67.0					
Return	79.0	67.0					
Ret/OA	86.3	55.8					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS						
	Cooling	Heating				
Diffuser	471	471				
Terminal	471	471				
Main Fan	471	471				
Sec Fan	0	0				
Nom Vent	241	138				
AHU Vent	241	138				
Infil	4	4				
MinStop/Rh	0	0				
Return	475	475				
Exhaust	244	142				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS							
Cooling Heating							
51.1	29.3						
0.82	0.82						
195.80							
238.67							
50.28	-29.97						
5							
	Cooling 51.1 0.82 195.80 238.67 50.28						

	COOLING COIL SELECTION									
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/ <b>WB/HR</b> gr/lb
Main Clg Aux Clg	2.4 0.0	28.9 0.0	15.8 0.0	471 0	85.3 0.0	70.9 0.0	89.0 0.0	55.0 0.0	51.8 0.0	51.5 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	2.4	28.9								

AREAS Gross Total Glass ft² (%)							
Floor	574						
Part	4,902						
Int Door	0						
ExFlr	0						
Roof	574	0	0				
Wall	634	40	6				
Ext Door	0	0	0				

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F					
Main Htg Aux Htg	-17.2 0.0	471 0	47.3 0.0	79.7 0.0					
Preheat	-5.1	471	47.3	55.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-17.2								

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 014 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		<b>HEATING C</b>	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 8 / 15 R: 90 / 77 / 1	120	Mo/Hr: OADB:			Mo/Hr: H OADB: 2	leating Design 29	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i e	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` ,
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	934	934	4	0	0	Roof Cond	0	-791	6.48
Glass Solar	1,629	0	1,629	8	3,351	35	Glass Solar	0	0	0.00
Glass/Door Cond	366	0	366	2	80	1	Glass/Door Cond	-1,113	-1,113	9.13
Wall Cond	1,122	719	1,841	9 ;	1,309	14	Wall Cond	-1,261	-2,086	17.10
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	162		162	1	17	0	Infiltration	-128	-128	1.05
Sub Total ==>	3,279	1,653	4,931	23	4,756	49	Sub Total ==>	-2,502	-4,117	33.77
Internal Loads							Internal Loads			
Lights	1,272	318	1,590	8	1,272	13	Lights	0	0	0.00
People	4,050	0	4,050	19	2,250	23		0	0	0.00
Misc	1,084	0	1,084	5	1,084	11		0	0	0.00
Sub Total ==>	6,406	318	6,724	32	4,606	48	Sub Total ==>	0	0	0.00
Ceiling Load	375	-375	0	0	327	3	Ceiling Load	-308	0	0.00
Ventilation Load	0	0	9,717	46	0		Ventilation Load	0	-4,392	36.02
Adj Air Trans Heat	0	ŭ	0,	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0 :	· ·	·	Ov/Undr Sizing	-840	-840	6.89
Ov/Undr Sizing	0		0	0 :	0	٥	Exhaust Heat	0.0	250	-2.05
Exhaust Heat	O	-575	-575	-3	U	U	OA Preheat Diff.		-2,091	17.15
Sup. Fan Heat		0.0	196	1			RA Preheat Diff.		-1,003	8.22
Ret. Fan Heat		149	149	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					ŭ	3.50
Underfir Sup Ht Pku	D	-	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 ;			Supply Air Leakage		0	0.00
Grand Total ==>	10,060	1,170	21,144	100.00	9,689	100.00	Grand Total ==>	-3,650	-12,193	100.00

TEMPERATURES							
	Cooling	Heating					
SADB	55.4	77.7					
Ra Plenum	77.8	67.7					
Return	78.1	67.7					
Ret/OA	82.1	60.4					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS						
	Cooling	Heating				
Diffuser	502	502				
Terminal Main Fan	502 502	502 502				
Sec Fan	0	0				
Nom Vent	164	94				
AHU Vent	164	94				
Infil	3	3				
MinStop/Rh	0	0				
Return	505	505				
Exhaust	166	96				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS								
Cooling Heating								
% OA	32.6	18.7						
cfm/ft²	1.18	1.18						
cfm/ton	247.64							
ft²/ton	209.00							
Btu/hr·ft²	tu/hr·ft <sup>2</sup> 57.42 -30.45							
No. People	9							

COOLING COIL SELECTION										
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	2.0 0.0	24.3 0.0	14.2 0.0	502 0	82.1 0.0	68.2 0.0	79.9 0.0	55.0 0.0	52.8 0.0	55.1 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	2.0	24.3								

AREAS Gross Total Glass ft² (%)							
Floor Part	423 2,849						
Int Door	0						
ExFlr	0						
Roof	423	0	0				
Wall	474	60	13				
Ext Door	0	0	0				

HEATING COIL SELECTION							
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F			
Main Htg Aux Htg	-12.9 0.0	502 0	54.9 0.0	77.7 0.0			
Preheat	-0.1	502	54.9	55.0			
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0 0.0			
Total	-12.9						

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 015 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	I at Time: itside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,121	1,121	10	0	0	Roof Cond	0	-763	11.30
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	157		157	1 :	54	2		-126	-126	1.86
Sub Total ==>	157	1,121	1,279	11 ;	54	2	Sub Total ==>	-126	-889	13.17
Internal Loads							Internal Loads			
Lights	694	174	868	7 :	694	27	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	1,065	0	1,065	9 :	1,065	42	Misc	0	0	0.00
Sub Total ==>	1,760	174	1,933	17	1,760	69	Sub Total ==>	0	0	0.00
Ceiling Load	728	-728	0	0 :	737	29	Ceiling Load	-395	0	0.00
Ventilation Load	0	0	9,080	78	0	0	Ventilation Load	0	-4,161	61.64
Adj Air Trans Heat	0		. 0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	•		0	0;	-		Ov/Undr Sizing	-34	-34	0.50
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	•	222	-3.28
Exhaust Heat	U	-742	-742	-6	0	· ·	OA Preheat Diff.		-1,299	19.25
Sup. Fan Heat		=	52	0		,	RA Preheat Diff.		-589	8.72
Ret. Fan Heat		27	27	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					_	
Underfir Sup Ht Pkuj	0		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0		;	Supply Air Leakage		0	0.00
Grand Total ==>	2,645	-148	11,629	100.00	2,551	100.00	Grand Total ==>	-554	-6,750	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	74.6					
Ra Plenum	80.5	67.0					
Return	80.8	67.0					
Ret/OA	93.4	41.2					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS							
Cooling	Heating						
132	132						
132 132	132 132						
0	0						
155	89						
155	89						
3	3						
0	0						
91	109						
113	66						
0	0						
0	0						
0	0						
0	0						
	Cooling 132 132 132 0 155 155 3 0 91 113 0 0 0						

ENGINEERING CKS						
% OA	Cooling 100.0	Heating 67.2				
cfm/ft²	0.32	0.32				
cfm/ton	118.55	0.02				
ft²/ton	373.43					
Btu/hr·ft²	32.13	-18.91				
No. People	0					
No. People	0					

	COOLING COIL SELECTION									
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Ent °F	er DB/W °F	<b>/B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/ <b>WB/HR</b> gr/lb
Main Clg Aux Clg	1.1 0.0	13.4 0.0	6.5 0.0	132 0	93.4 0.0	77.5 0.0	115.3 0.0	55.0 0.0	47.2 0.0	35.3 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.1	13.4								

Gro	AREAS	Glass	
O.C	,33 Total	ft²	(%)
Floor	416		
Part	5,001		
Int Door	0		
ExFlr	0		
Roof	416	0	0
Wall	0	0	0
Ext Door	0	0	0

HEATING COIL SELECTION							
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F			
Main Htg Aux Htg	-7.9 0.0	132 0	21.9 0.0	74.6 0.0			
Preheat	-4.9	132	28.5	55.0			
Humidif	0.0	0	0.0	0.0			
Opt Vent	0.0	0	0.0	0.0			
Total	-7.9						

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 016 Single Zone

	COOLING	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	at Time: tside Air:	Mo/H OADB/WB/HF	lr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	2,723	2,723	7	0	0	Roof Cond	0	-1,685	7.35
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	311		311	1	120	1	Infiltration	-272	-272	1.18
Sub Total ==>	311	2,723	3,034	8 ;	120	1	Sub Total ==>	-272	-1,957	8.53
Internal Loads							Internal Loads			
Lights	2,138	534	2,672	7:	2,138	25	Lights	0	0	0.00
People	5,400	0	5,400	15	3,000	34	People	0	0	0.00
Misc	2,300	0	2,300	6	2,300	26	Misc	0	0	0.00
Sub Total ==>	9,837	534	10,372	28	7,437	85	Sub Total ==>	0	0	0.00
Ceiling Load	1.157	-1,157	0	0 :	1,157	13	Ceiling Load	-599	0	0.00
Ventilation Load	0	0	26,005	70	0	0	Ventilation Load	0	-13,018	56.77
Adj Air Trans Heat	0	· ·	0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	Ü		0	0	· ·	Ü	Ov/Undr Sizing	-885	-885	3.86
Ov/Undr Sizing	5		5	0 :	5	0	Exhaust Heat	000	673	-2.94
Exhaust Heat	5	-2,560	-2,560	-7 :	5	U	OA Preheat Diff.		-5,208	22.71
Sup. Fan Heat		2,000	177	0			RA Preheat Diff.		-2,535	11.05
Ret. Fan Heat		145	145	0:			Additional Reheat		2,333	0.00
Duct Heat Pkup		0	0	0:					O	0.00
Underfir Sup Ht Pkup	,	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	o :			Supply Air Leakage		0	0.00
Grand Total ==>	11,311	-314	37,178	100.00	8,720	100.00	Grand Total ==>	-1,755	-22,928	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.4	73.9					
Ra Plenum	79.1	67.9					
Return	79.3	67.9					
Ret/OA	93.4	43.7					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.1	0.0					
Fn Frict	0.2	0.0					

AIRFLOWS						
	Cooling	Heating				
Diffuser	452	452				
Terminal Main Fan	452 452	452 452				
Sec Fan	0	0				
Nom Vent	485	278				
AHU Vent	485	278				
Infil	6	6				
MinStop/Rh	0	0				
Return	490	457				
Exhaust	524	283				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS						
Cooling Heating						
% OA	100.0	61.5				
cfm/ft <sup>2</sup>	0.50	0.50				
cfm/ton	126.74					
ft²/ton	252.14					
Btu/hr·ft²	47.59	-27.41				
No. People	12					

COOLING COIL SELECTION										
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>/B/HR</b> gr/lb	<b>Lea</b> °F	ve DB °F	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	3.6 0.0	42.8 0.0	21.5 0.0	452 0	93.4 0.0	77.5 0.0	115.3 0.0	55.0 0.0	49.9 0.0	44.4 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	3.6	42.8								

Gro	AREAS oss Total	Glass	s (%)
Floor Part	898 6,751		
Int Door ExFIr	0		
Roof Wall	898 0	0 0	0 0
Ext Door	0	0	0

HEA	TING COIL	. SELECTIO	ON	
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F
Main Htg Aux Htg	-24.6 0.0	452 0	25.6 0.0	73.9 0.0
Preheat	-16.9	452	28.5	55.0
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0 0.0
Total	-24.6			

Project Name: CIC RA 5-9 Adapt-Build Prototype

Single Zone System - 017

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: Ho OADB: 2	eating Design 9	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i e	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				(/		( /	Envelope Loads			( /
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,280	1,280	7 :	0	0	Roof Cond	0	-838	6.65
Glass Solar	0	0	0	0	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	919	441	1,360	8	1,093	26		-1,037	-1,565	12.42
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	174		174	1	47	1	Infiltration	-140	-140	1.11
Sub Total ==>	1,093	1,721	2,814	16	1,140	27	Sub Total ==>	-1,177	-2,543	20.18
Internal Loads							Internal Loads			
Lights	983	246	1,229	7	983	23	Lights	0	0	0.00
People	428	0	428	2	238	6		0	0	0.00
Misc	1,184	0	1,184	7	1,184	28		0	0	0.00
Sub Total ==>	2,595	246	2,841	16	2,405	57	!	0	0	0.00
Ceiling Load	738	-738	0	0	650	15	Ceiling Load	-508	0	0.00
Ventilation Load	0	0	13,255	75	0		Ventilation Load	0	-6,114	48.53
Adj Air Trans Heat	61	Ü	61	0	61	-	Adj Air Trans Heat	-107	-107	1
Dehumid. Ov Sizing	01		0	0	01		Ov/Undr Sizing	-472	-472	3.75
Ov/Undr Sizing	0		0	0 :	0	٥	Exhaust Heat	712	505	-4.01
Exhaust Heat	U	-1,336	-1,336	-8 :	U	U	OA Preheat Diff.		-2,696	21.39
Sup. Fan Heat		1,000	-1,556	0 :			RA Preheat Diff.		-1,173	9.31
Ret. Fan Heat		64	64	0:			Additional Reheat		0,170	0.00
Duct Heat Pkup		0	0	0					O	0.00
Underfir Sup Ht Pku	n	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	F	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	4,487	-43	17,785	100.00	4,256	100.00	Grand Total ==>	-2,264	-12,600	100.00

TEMPERATURES								
Cooling Heating								
SADB	55.4	80.9						
Ra Plenum	80.0	66.5						
Return	80.3	66.5						
Ret/OA	93.4	44.0						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.1	0.0						
Fn Frict	0.2	0.0						

AIRFLOWS								
	Cooling	Heating						
Diffuser	220	220						
Terminal Main Fan	220 220	220 220						
Sec Fan	0	0						
Nom Vent	228	130						
AHU Vent	228	130						
Infil	3	3						
MinStop/Rh	0	0						
Return	216	219						
Exhaust	223	129						
Rm Exh	18	11						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS								
Cooling Heating								
% OA	100.0	59.2						
cfm/ft <sup>2</sup>	0.48	0.48						
cfm/ton	129.32							
ft²/ton	271.46							
Btu/hr·ft²	Btu/hr·ft <sup>2</sup> 44.20 -28.87							
No. People	1							

			COOLING	G COIL SEL	ECTIC	N				
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/V °F	<b>VB/HR</b> gr/lb	<b>Lea</b> °F	ve DB °F	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	1.7 0.0	20.5 0.0	10.3 0.0	220 0	93.4 0.0	77.5 0.0	115.3 0.0	55.0 0.0	50.6 0.0	47.1 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.7	20.5								

Gro	AREAS oss Total	Glass	s (%)
Floor Part	463 4,759		(,,,
Int Door ExFIr	0 0		
Roof Wall	463 313	0 0	0 0
Ext Door	0	0	0

HEA	TING COIL	SELECTION	ON	
	Capacity	Coil Airflow	<b>Ent</b>	Lvg
	MBh	cfm	°F	°F
Main Htg	-13.4	220	27.3	80.9
Aux Htg	0.0	0	0.0	0.0
Preheat	-8.3	220	28.5	55.0
Humidif	0.0	0	0.0	0.0
Opt Vent	0.0		0.0	0.0
Total	-13.4			

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 018 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: H OADB: 2	eating Design 9	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i e	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	716	716	7	0	0	Roof Cond	0	-432	6.91
Glass Solar	353	0	353	3	889	19	Glass Solar	0	0	0.00
Glass/Door Cond	142	0	142	1	93	2	Glass/Door Cond	-371	-371	5.93
Wall Cond	1,057	574	1,631	15 ;	924	20	Wall Cond	-1,086	-1,698	27.16
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	88		88	1	21	0	Infiltration	-71	-71	1.14
Sub Total ==>	1,640	1,290	2,930	27	1,927	42	Sub Total ==>	-1,528	-2,572	41.14
Internal Loads							Internal Loads			
Lights	837	209	1,046	10	837	18	Lights	0	0	0.00
People	1,800	0	1,800	16	1,000	22		0	0	0.00
Misc	603	0	603	5	603	13		0	0	0.00
Sub Total ==>	3,240	209	3,449	31	2,440	53	!	0	0	0.00
Ceiling Load	323	-323	0	0 :	252	5	Ceiling Load	-225	0	0.00
Ventilation Load	0	0	4,899	45	0		Ventilation Load	0	-2,277	36.41
Adj Air Trans Heat	0	Ŭ	0	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	·	170	-2.73
Exhaust Heat	U	-447	-447	-4	U	U	OA Preheat Diff.		-1,084	17.34
Sup. Fan Heat		• • •	94	1			RA Preheat Diff.		-490	7.84
Ret. Fan Heat		71	71	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					Ü	3.50
Underfir Sup Ht Pku	q	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0 }			Supply Air Leakage		0	0.00
Grand Total ==>	5,203	800	10,996	100.00	4,619	100.00	Grand Total ==>	-1,753	-6,253	100.00

TEMPERATURES								
Cooling Heating								
SADB	55.4	78.1						
Ra Plenum	79.3	67.0						
Return	79.6	67.0						
Ret/OA	84.5	59.2						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.1	0.0						
Fn Frict	0.2	0.0						

4100	0.440							
AIRF	LOWS							
Cooling Heating								
Diffuser	239	239						
Terminal	239	239						
Main Fan	239	239						
Sec Fan	0	0						
Nom Vent	85	49						
AHU Vent	85	49						
Infil	2	2						
MinStop/Rh	0	0						
Return	241	241						
Exhaust	86	50						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	35.4	20.3					
cfm/ft²	1.01	1.01					
cfm/ton	226.98						
ft²/ton	223.65						
Btu/hr·ft <sup>2</sup>	53.66	-28.39					
No. People	4						

COOLING COIL SELECTION										
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	1.1 0.0	12.7 0.0	8.1 0.0	239 0	84.5 0.0	69.3 0.0	81.6 0.0	55.0 0.0	52.6 0.0	54.5 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.1	12.7								

AREAS Gross Total Glass ft² (%)							
Floor Part	236 1,288						
Int Door ExFIr	0						
Roof Wall	236 359	0 20	0 6				
Ext Door	0	0	0				

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	-6.7	239	53.4	78.1				
Aux Htg	0.0	0	0.0	0.0				
Preheat	-0.6	239	53.4	55.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-6.7							

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 019 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! ! !	Btu/h	Btu/h	(%)
Envelope Loads				` ';		` ,	Envelope Loads			` ,
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	200	200	8	0	0	Roof Cond	0	-138	5.83
Glass Solar	84	0	84	3	79	9	Glass Solar	0	0	0.00
Glass/Door Cond	200	0	200	8	218	25	Glass/Door Cond	-608	-608	25.76
Wall Cond	145	96	241	9 ;	157	18	Wall Cond	-243	-419	17.75
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	30		30	1	9	1	Infiltration	-23	-23	0.99
Sub Total ==>	459	296	755	29	463	53	Sub Total ==>	-874	-1,187	50.33
Internal Loads							Internal Loads			
Lights	106	26	132	5	106	12	Lights	0	0	0.00
People	0	0	0	0;	0	0	People	0	0	0.00
Misc	198	0	198	7	198	23	Misc	0	0	0.00
Sub Total ==>	303	26	330	12	303	35	Sub Total ==>	0	0	0.00
Ceiling Load	104	-104	0	0 :	106	12	Ceiling Load	-101	0	0.00
Ventilation Load	0	0	1,675	63	0		Ventilation Load	0	-747	31.65
Adj Air Trans Heat	0	· ·	0	0	0	•	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	Ū		0	0	Ū	O	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0:	0	٥	Exhaust Heat	· ·	76	-3.24
Exhaust Heat	U	-144	-144	-5 :	U	U	OA Preheat Diff.		-356	15.07
Sup. Fan Heat		177	18	1			RA Preheat Diff.		-146	6.19
Ret. Fan Heat		14	14	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			, Additional Ronout		O	0.00
Underfir Sup Ht Pku	n	ŭ	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	F	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	866	88	2,647	100.00	872	100.00	Grand Total ==>	-975	-2,359	100.00

TEMPERATURES							
Cooling Heating							
55.4	93.9						
79.2	65.9						
79.5	65.9						
88.1	52.7						
0.0	0.0						
0.1	0.0						
0.2	0.0						
	55.4 79.2 79.5 88.1 0.0 0.1						

AIRFLOWS								
Cooling Heating								
Diffuser	45	45						
Terminal Main Fan	45 45	45 45						
Sec Fan	0	0						
Nom Vent	28	16						
AHU Vent	28	16						
Infil	1	1						
MinStop/Rh	0	0						
Return	46	46						
Exhaust	28	16						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	61.5	35.2					
cfm/ft <sup>2</sup>	0.58	0.58					
cfm/ton	178.05						
ft²/ton	304.63						
Btu/hr·ft²	39.39	-33.68					
No. People	0						

	COOLING COIL SELECTION									
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.3 0.0	3.0 0.0	1.8 0.0	45 0	88.1 0.0	72.5 0.0	93.9 0.0	55.0 0.0	52.0 0.0	52.3 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.0								

AREAS							
Gros	ss Total	Glas ft²	s (%)				
Floor	77						
Part	979						
Int Door	0						
ExFlr	0						
Roof	77	0	0				
Wall	85	0	0				
Ext Door	21	21	100				

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F				
Main Htg Aux Htg	-2.6 0.0	45 0	42.9 0.0	93.9 0.0				
Preheat	-0.8	45	42.9	55.0				
Humidif Opt Vent	0.0	0	0.0	0.0				
Total	-2.6	U	0.0	0.0				

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 020 Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	l at Time: itside Air:	Mo/H OADB/WB/HF	r: 7 / 17 R: 92 / 76 / 1	09	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	174	174	6	0	0	Roof Cond	0	-124	5.75
Glass Solar	402	0	402	14 ;	588	42		0	0	0.00
Glass/Door Cond	218	0	218	8 :	199	14		-608	-608	28.14
Wall Cond	232	186	418	15 ;	263	19		-193	-350	16.19
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0		0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	24		24	1 :	6	0	Infiltration	-20	-20	0.94
Sub Total ==>	876	360	1,236	44	1,057	76	Sub Total ==>	-821	-1,102	51.01
Internal Loads							Internal Loads			
Lights	92	23	115	4	92	7	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	172	0	172	6	172	12		0	0	0.00
Sub Total ==>	264	23	287	10	264	19	Sub Total ==>	0	0	0.00
Ceiling Load	79	-79	0	0	76	5	Ceiling Load	-58	0	0.00
Ventilation Load	0	0	1,357	48	0	0	Ventilation Load	0	-649	30.06
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	o :	0	0	Exhaust Heat	•	44	-2.03
Exhaust Heat	Ū	-110	-110	-4	· ·	· ·	OA Preheat Diff.		-309	14.32
Sup. Fan Heat			28	1			RA Preheat Diff.		-143	6.64
Ret. Fan Heat		22	22	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					Ŭ	3.30
Underfir Sup Ht Pku	)	-	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,219	216	2,820	100.00	1,396	100.00	Grand Total ==>	-879	-2,160	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.4	83.4							
Ra Plenum	78.7	67.3							
Return	79.0	67.3							
Ret/OA	83.2	59.9							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS									
Cooling Heatin									
Diffuser	72	72							
Terminal Main Fan	72 72	72 72							
Sec Fan	0	0							
Nom Vent	24	14							
AHU Vent	24	14							
Infil	0	0							
MinStop/Rh	0	0							
Return	73	73							
Exhaust	25	14							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS								
Cooling Heating								
% OA	33.4	19.1						
cfm/ft <sup>2</sup>	1.08	1.08						
cfm/ton	267.59							
ft²/ton	248.72							
Btu/hr·ft²	48.25	-35.40						
No. People	0							

	COOLING COIL SELECTION									
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.3 0.0	3.2 0.0	2.2 0.0	72 0	83.2 0.0	67.4 0.0	74.0 0.0	55.0 0.0	53.0 0.0	56.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.2								

	AREAS	3	
Gros	ss Total	Glas	s (%)
			(70)
Floor	67		
Part	948		
Int Door	0		
ExFlr	0		
Roof	67	0	0
Wall	70	0	0
Ext Door	21	21	100

HEAT	HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-2.4	72	54.3	83.4						
Aux Htg	0.0	0	0.0	0.0						
Preheat	-0.1	72	54.3	55.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent	0.0		0.0	0.0						
Total	-2.4									

Project Name: CIC RA 5-9 Adapt-Build Prototype

System - 021 Single Zone

	COOLING C	OIL PEAK		(	CLG SPACE	PEAK		HEATING C	OIL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	: 7 / 12 :: 89 / 74 / 1	01	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: F OADB: :	Heating Design 29	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i .	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` ,
Skylite Solar	0	0	0	0:	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	195	195	3	0	0	Roof Cond	0	-152	3.32
Glass Solar	2,221	0	2,221	40	2,598	70	Glass Solar	0	0	0.00
Glass/Door Cond	587	0	587	11	454	12	Glass/Door Cond	-2,208	-2,208	48.21
Wall Cond	336	360	696	12	288	8	Wall Cond	-431	-899	19.63
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0:	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	26		26	0	7	0	Infiltration	-25	-25	0.54
Sub Total ==>	3,170	555	3,725	67	3,347	90	Sub Total ==>	-2,663	-3,284	71.70
Internal Loads							Internal Loads			
Lights	112	28	140	3	112	3	Lights	0	0	0.00
People	0	0	0	0;	0	0	. 5	0	0	0.00
Misc	210	0	210	4	210	6		0	0	0.00
Sub Total ==>	322	28	350	6	322	9	Sub Total ==>	0	0	0.00
Ceiling Load	62	-62	0	0 :	52	1	Ceiling Load	-66	0	0.00
Ventilation Load	0	0	1,466	26	0	0	Ventilation Load	0	-792	17.29
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	50	-1.09
Exhaust Heat	· ·	-90	-90	-2	· ·	· ·	OA Preheat Diff.		-377	8.23
Sup. Fan Heat			75	1			RA Preheat Diff.		-177	3.87
Ret. Fan Heat		57	57	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0						
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	3,554	488	5,584	100.00	3,720	100.00	Grand Total ==>	-2,729	-4,580	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.4	85.7							
Ra Plenum	77.4	67.5							
Return	77.7	67.5							
Ret/OA	79.4	64.1							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.1	0.0							
Fn Frict	0.2	0.0							

AIRFLOWS									
	Cooling	Heating							
Diffuser	193	193							
Terminal Main Fan	193 193	193 193							
Sec Fan	0	0							
Nom Vent	29	17							
AHU Vent	29	17							
Infil	1	1							
MinStop/Rh	0	0							
Return	193	193							
Exhaust	30	17							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS								
Cooling Heating								
% OA	15.3	8.8						
cfm/ft <sup>2</sup>	2.35	2.35						
cfm/ton	359.99							
ft²/ton	153.15							
Btu/hr·ft²	78.36	-64.21						
No. People	0							

COOLING COIL SELECTION										
	<b>Total</b> (	Capacity MBh	<b>Sens Cap.</b> MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	0.5 0.0	6.4 0.0	5.3 0.0	193 0	79.4 0.0	63.6 0.0	61.3 0.0	55.0 0.0	52.3 0.0	53.3 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	6.4								

Gro	AREAS ss Total	Glas	s (%)
Floor Part	82 200		
Int Door ExFir	0		
Roof Wall	82 220	0 40	0 18
Ext Door	51	51	100

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	-5.3	193	61.5	85.7				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-5.3							

Project Name: CIC RA 5-9 Adapt-Build Prototype

Single Zone **CUHs - Vestibules** 

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h		Sensible Btu/h			Btu/h	Btu/h	
Envelope Leads	Dlu/II	Dlu/II	Dlu/II	(%)	Dlu/II	(%)	Envelope Loads	Dlu/II	Dlu/II	(%)
Envelope Loads Skylite Solar	0	0	0	0	0	0		0	0	0.00
Skylite Cond	0	0	0	0:	0	0		0	0	0.00
Roof Cond	0	109	109	2	0	0		0	-144	4.48
Glass Solar	2,269	0	2.269	51	2,269	54	Glass Solar	0	-144	0.00
Glass/Door Cond	2,269 843	0	2,269 843		2,269 843		,	-	-	
Wall Cond	129	115	843 244	19 :	129	20 3		-2,652 -207	-2,652 -396	82.73 12.34
Partition/Door		115		5 ; 0 ;	129	0				0.00
	0		0		-			0	0	
Floor	0	•	0	0	0	0		0	0	0.00
Adjacent Floor	0	0	0	0	0	0		0	0	0
Infiltration	20		20	0 ;	6	0		-15	-15	0.47
Sub Total ==>	3,260	224	3,484	78	3,246	77	Sub Total ==>	-2,874	-3,207	100.01
Internal Loads							Internal Loads			
Lights	295	74	369	8 :	295	7	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	580	0	580	13	580	14	Misc	0	0	0.00
Sub Total ==>	875	74	948	21	875	21	Sub Total ==>	0	0	0.00
Ceiling Load	76	-76	0	0	76	2	Ceiling Load	-85	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0:	0	٥	Exhaust Heat	O .	0	-0.01
Exhaust Heat	U	0	0	0	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		U	22	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0;			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0;			Additional Nemeat		U	0.00
Underfir Sup Ht Pku	ın	· ·	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	4,210	221	4,454	100.00	4,196	100.00	Grand Total ==>	-2,959	-3,206	100.00

TEMPERATURES							
Cooling Heating							
SADB	55.0	84.1					
Ra Plenum	76.1	68.8					
Return	76.0	68.8					
Ret/OA	76.0	68.8					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.1	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	186	186						
Terminal	186	186						
Main Fan	186	186						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	0	0						
MinStop/Rh	0	0						
Return	186	186						
Exhaust	0	0						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft <sup>2</sup>	0.82	0.82				
cfm/ton	500.36					
ft²/ton	610.12					
Btu/hr·ft²	19.67	-14.16				
No. People	0					

COOLING COIL SELECTION										
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	0.4 0.0	4.5 0.0	4.4 0.0	186 0	76.0 0.0	58.0 0.0	42.3 0.0	54.9 0.0	49.1 0.0	41.9 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.4	4.5								

Gro	AREAS oss Total	Glas	s (%)
Floor Part	226 2,127		
Int Door ExFIr	0		
Roof Wall	226 375	0 30	0 8
Ext Door	93	93	100

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F				
Main Htg	-3.2	186	68.8	84.1				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-3.2							

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### DUMMY Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 5 / 1 R: 70 / 58 / 5	53	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	24	24	14	0	0	Roof Cond	0	-30	6.67
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	106	45	151	87 :	106	61		-287	-413	92.96
Partition/Door	0		0	0	0	0		0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	-2		-2	-1 ;	-1	-1		-2	-2	0.55
Sub Total ==>	104	69	173	100	105	61	Sub Total ==>	-289	-445	100.18
Internal Loads							Internal Loads			
Lights	0	0	0	0 :	0	0	Lights	0	0	0.00
People	0	0	0	0	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	0	0	0	0	0	0	Sub Total ==>	0	0	0.00
Ceiling Load	40	-40	0	0	68	39	Ceiling Load	-155	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0 :	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	1	-0.18
Exhaust Heat	· ·	0	ő	0 :	· ·	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-	0	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0						
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	144	29	173	100.00	173	100.00	Grand Total ==>	-445	-445	100.00

TEMPERATURES							
Cooling Heating							
80.0	55.0						
82.2	46.4						
82.2	46.4						
82.2	46.4						
0.0	0.0						
0.0	0.0						
0.0	0.0						
	80.0 82.2 82.2 82.2 0.0 0.0						

AIRFLOWS								
Cooling Heating								
Diffuser	0	0						
Terminal	0	0						
Main Fan	0	0						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	0	0						
MinStop/Rh	0	0						
Return	0	0						
Exhaust	0	0						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS									
Cooling Heating									
% OA	0.0	0.0							
cfm/ft <sup>2</sup>	0.00	0.00							
cfm/ton	0.00								
ft²/ton	0.00								
Btu/hr·ft²	0.00	0.00							
No. People	0								

	COOLING COIL SELECTION										
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Ente °F	er DB/W °F	<b>B/HR</b> gr/lb	<b>Lea</b> °F	ve DB/ °F	<b>WB/HR</b> gr/lb	
Main Clg	0.0	0.0	0.0	0	0.0	0.0	75.3	0.0	0.0	75.3	
Aux Clg Opt Vent	0.0 0.0	0.0 0.0	0.0	0	0.0	0.0	0.0 0.0	0.0	0.0	0.0	
Total	0.0	0.0									

AREAS								
Gro	Glass ft²	s (%)						
Floor	57							
Part	5,742							
Int Door	0							
ExFlr	0							
Roof	57	0	0					
Wall	Wall 384							
Ext Door	0	0	0					

HEATING COIL SELECTION										
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F						
Main Htg	0.0	0	0.0	0.0						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	0	46.4	80.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent	0.0	0	0.0	0.0						
Total	0.0									

Project Name: CIC RA 5-9 Adapt-Build Prototype

FCU - Elec Single Zone

c	COOLING	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
Peaked Out	at Time: side Air:	Mo/H OADB/WB/H	Hr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i i i	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				(,		(/	Envelope Loads			()
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	66	66	0	0	0	Roof Cond	0	-89	0.85
Glass Solar	95	0	95	0	95	9	Glass Solar	0	0	0.00
Glass/Door Cond	197	0	197	0	210	19	Glass/Door Cond	-593	-593	5.69
Wall Cond	38	27	65	0 :	50	5	Wall Cond	-91	-157	1.50
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	7		7	0	3	0	Infiltration	-9	-9	0.09
Sub Total ==>	338	93	431	0	359	33	Sub Total ==>	-693	-848	8.13
Internal Loads							Internal Loads			
Lights	349	87	437	0	349	32	Lights	0	0	0.00
People	0	0	0	0:	0	0	People	0	0	0.00
Misc	353	0	353	0:	353	32	Misc	0	0	0.00
Sub Total ==>	703	87	790	0	703	64		0	0	0.00
Ceiling Load	28	-28	0	0	30	3	Ceiling Load	-24	0	0.00
Ventilation Load	0	0	182,413	104	0		Ventilation Load	0	-9,705	93.11
Adj Air Trans Heat	0	O	0	0	0	-	Adj Air Trans Heat	0	0,0	0
Dehumid. Ov Sizing	U		0	0	U	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0		0	0	Exhaust Heat	U	130	-1.25
Exhaust Heat	U	-7,432	-7,432	0 : -4 :	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-1,432	-7, <del>4</del> 32 25	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0:			Auditional Neneal		U	0.00
Underfir Sup Ht Pkup		0	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,069	-7,280	176,227	100.00	1,091	100.00	Grand Total ==>	-718	-10,423	100.00

TEMPERATURES									
Cooling Heating									
SADB	70.3	73.1							
Ra Plenum	75.7	69.5							
Return	75.7	69.5							
Ret/OA	93.4	28.5							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.1	0.0							

AIRFLOWS									
	Cooling	Heating							
Diffuser	207	207							
Terminal Main Fan	207 207	207 207							
Sec Fan	0	0							
Nom Vent	5,174	207							
AHU Vent	5,174	207							
Infil	0	0							
MinStop/Rh	0	0							
Return	5,174	207							
Exhaust	10,142	207							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS									
Cooling Heating									
% OA	100.0	100.0							
cfm/ft²	1.50	1.50							
cfm/ton	14.09								
ft²/ton	9.40								
Btu/hr·ft²	1,277.18	-1,741.02							
No. People	0								

	COOLING COIL SELECTION										
	<b>Total</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>/B/HR</b> gr/lb	<b>Lea</b> °F	ve DB °F	<b>/WB/HR</b> gr/lb	
Main Clg Aux Clg	14.7 0.0	176.2 0.0	101.3 0.0	207 0	93.4 0.0	77.5 0.0	115.3 0.0	70.2 0.0	0.0	0.0 0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	14.7	176.2									

Gro	AREAS	Glas	- 1
		ft²	(%)
Floor	138		
Part	1,207		
Int Door	0		
ExFlr	0		
Roof	138	0	0
Wall	135	0	0
Ext Door	24	24	100

HEA	HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F						
Main Htg	-240.2	207-	954.2	73.1						
Aux Htg	0.0	0	0.0	0.0						
Preheat	-9.8	207	28.5	70.2						
Humidif	0.0	0	0.0	0.0						
Opt Vent	0.0	0	0.0	0.0						
Total	-240.2									

Project Name: CIC RA 5-9 Adapt-Build Prototype

Fan Coil FCU - Evid Dep

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	7 / 15 1: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	195	195	3	0	0	Roof Cond	0	-267	8.80
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	134	68	202	3 ;	264	10		-284	-436	14.38
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 }	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	35		35	1 ;	5	0	Infiltration	-28	-28	0.93
Sub Total ==>	169	263	431	7	268	10	Sub Total ==>	-312	-731	24.11
Internal Loads							Internal Loads			
Lights	1,160	290	1,450	25	1,160	42	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	1,084	0	1,084	19	1,084	39	Misc	0	0	0.00
Sub Total ==>	2,244	290	2,534	44	2,244	81	Sub Total ==>	0	0	0.00
Ceiling Load	248	-248	0	0 :	249	9	Ceiling Load	-188	0	0.00
Ventilation Load	0	0	2,909	50	0	0	Ventilation Load	0	-2,383	78.58
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0 :	-	-	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	·	82	-2.69
Exhaust Heat	O	-108	-108	-2	O .	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat			4	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					_	
Underfir Sup Ht Pku	р		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,661	197	5,771	100.00	2,761	100.00	Grand Total ==>	-500	-3,032	100.00

TEMPERATURES						
Cooling Heating						
SADB	58.1	73.1				
Ra Plenum	76.9	68.6				
Return	76.9	68.6				
Ret/OA	82.7	54.5				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS								
Cooling Heating								
Diffuser	145	145						
Terminal	145	145						
Main Fan	145	145						
Sec Fan	0	0						
Nom Vent	51	51						
AHU Vent	51	51						
Infil	1	1						
MinStop/Rh	0	0						
Return	145	145						
Exhaust	51	51						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	35.1	35.1					
cfm/ft²	0.34	0.34					
cfm/ton	301.19						
ft²/ton	880.55						
Btu/hr·ft²	13.63	-7.16					
No. People	0						

COOLING COIL SELECTION										
	<b>Total (</b> ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg	0.5	5.8	3.9	145	82.7	68.8	82.0	58.1	56.6	65.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	5.8								

AREAS Gross Total Glass ft² (%)							
Floor Part	423 909						
Int Door ExFIr	0 0						
Roof Wall	423 379	0 0	0 0				
Ext Door	0	0	0				

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F					
Main Htg Aux Htg	-3.0 0.0	145 0	54.5 0.0	73.1 0.0					
Preheat	-0.6	145	54.5	58.1					
Humidif Opt Vent	0.0	0	0.0	0.0 0.0					
Total	-3.0		0.0	0.0					

Project Name: CIC RA 5-9 Adapt-Build Prototype

FCU - Mech Single Zone

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/F OADB/WB/H	Hr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	192	192	0 ;	0	0	Roof Cond	0	-256	1.39
Glass Solar	181	0	181	0 ;	181	8	Glass Solar	0	0	0.00
Glass/Door Cond	375	0	375	0 :	399	17	Glass/Door Cond	-1,126	-1,126	6.11
Wall Cond	117	74	191	0 :	153	6		-280	-462	2.50
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	21		21	0	9	0	Infiltration	-27	-27	0.15
Sub Total ==>	694	266	960	0 :	743	31	Sub Total ==>	-1,433	-1,871	10.15
Internal Loads							Internal Loads			
Lights	524	131	655	0	524	22	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	1,025	0	1,025	1	1,025	43	Misc	0	0	0.00
Sub Total ==>	1,550	131	1,681	1	1,550	65	Sub Total ==>	0	0	0.00
Ceiling Load	94	-94	0	0	100	4	Ceiling Load	-104	0	0.00
Ventilation Load	0	0	199,558	103	0	0	Ventilation Load	0	-16,904	91.66
Adj Air Trans Heat	0	-	0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		334	-1.81
Exhaust Heat	Ü	-8,758	-8,758	-5	· ·	Ü	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-,	43	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		Ö	0	0					· ·	2.30
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,338	-8,456	193,484	100.00	2,393	100.00	Grand Total ==>	-1,537	-18,442	100.00

TEMPERATURES						
Cooling Heating						
SADB	69.1	73.8				
Ra Plenum	75.7	69.2				
Return	75.7	69.2				
Ret/OA	93.4	28.5				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.1	0.0				

AIRFLOWS								
Cooling Heating								
Diffuser	361	361						
Terminal Main Fan	361 361	361 361						
Sec Fan	0	0						
Nom Vent	5,408	361						
AHU Vent	5,408	361						
Infil	1	1						
MinStop/Rh	0	0						
Return	5,408	361						
Exhaust	10,455	361						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	100.0	100.0					
cfm/ft²	0.90	0.90					
cfm/ton	22.36						
ft²/ton	24.84						
Btu/hr·ft²	483.03	-625.21					
No. People	0						

COOLING COIL SELECTION										
	Total Capacity Sens Cap. Coil Airflow Enter DB/WB							Lea	ve DB	WB/HR
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	16.1	193.5	106.3	361	93.4	77.5	115.3	69.0	0.0	0.0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	16.1	193.5								

AREAS Gross Total Glass ft <sup>2</sup> (%)							
Floor Part	401 1,779						
Int Door ExFIr	0						
Roof Wall	401 400	0	0				
Ext Door	45	45	100				

HEATING COIL SELECTION							
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F			
Main Htg	-250.4	361-	541.1	73.8			
Aux Htg	0.0	0	0.0	0.0			
Preheat	-16.5	361	28.5	69.0			
Humidif	0.0	0	0.0	0.0			
Opt Vent	0.0	0	0.0	0.0			
Total	-250.4						

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### FCU - TR#1 Fan Coil

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 : 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	ii.	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	. ,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	75	75	6	0	0		0	-101	18.47
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	13		13	1	3	0	Infiltration	-11	-11	1.94
Sub Total ==>	13	75	87	7	3	0	Sub Total ==>	-11	-111	20.41
Internal Loads				:			Internal Loads			
Lights	161	40	201	16	161	25	Lights	0	0	0.00
People	0	0	0	0:	0	0		0	0	0.00
Misc	406	0	406	33	406	64		0	0	0.00
Sub Total ==>	567	40	608	50	567	89	Sub Total ==>	0	0	0.00
Ceiling Load	64	-64	0	0	67	10	Ceiling Load	-56	0	0.00
Ventilation Load	0	0	544	44	0		Ventilation Load	0	-446	81.86
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		12	-2.27
Exhaust Heat	-	-14	-14	-1	•	_	OA Preheat Diff.		0	0.00
Sup. Fan Heat			1	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0 :						
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	644	36	1,226	100.00	637	100.00	Grand Total ==>	-67	-545	100.00

TEMPERATURES						
Cooling Heating						
SADB	58.8	71.7				
Ra Plenum	76.3	68.9				
Return	76.3	68.9				
Ret/OA	81.0	57.8				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS							
Cooling Heating							
Diffuser	35	35					
Terminal Main Fan	35 35	35 35					
Sec Fan	0	0					
Nom Vent	10	10					
AHU Vent	10	10					
Infil	0	0					
MinStop/Rh	0	0					
Return	35	35					
Exhaust	10	10					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS							
Cooling Heating							
% OA	27.4	27.4					
cfm/ft²	0.22	0.22					
cfm/ton	339.70						
ft²/ton	1,552.91						
Btu/hr·ft <sup>2</sup>	7.73	-3.44					
No. People	0						

	COOLING COIL SELECTION									
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	0.1 0.0	1.2 0.0	0.9 0.0	35 0	81.0 0.0	67.5 0.0	78.1 0.0	58.8 0.0	56.6 0.0	64.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.2								

AREAS Gross Total Glass ft² (%)						
Floor Part	159 952					
Int Door ExFlr	0 0					
Roof Wall	159 0	0 0	0 0			
Ext Door	0	0	0			

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	-0.6		57.8	71.7				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	35	57.8	58.7				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-0.6							

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### Primary - VAV w/ BB

#### VAV w/Baseboard Skin Heating

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HI	lr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	t .	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0		0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	2,190	2,190	2	0	0		0	-2,923	8.56
Glass Solar	4,206	0	4,206	5	5,528	13		0	0	0.00
Glass/Door Cond	2,127	0	2,127	2 :	2,118	5		-6,314	-6,314	18.49
Wall Cond	1,240	779	2,019	2 ;	1,648	4		-2,240	-3,666	10.74
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0	0		0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	377		377	0	94	0	Infiltration	-313	-313	0.92
Sub Total ==>	7,950	2,969	10,919	12	9,387	23	Sub Total ==>	-8,867	-13,216	38.70
Internal Loads							Internal Loads			
Lights	8,532	2,133	10,665	12	8,532	21	Lights	0	0	0.00
People	15.872	0	15,872	18	8,818	21		0	0	0.00
Misc	12,003	0	12,003	13	12,003	29		0	0	0.00
Sub Total ==>	36,407	2,133	38,540	43	29,353	72	!	0	0	0.00
Ceiling Load	2,153	-2,153	0	0	2,245	5	Ceiling Load	-2.736	0	0.00
Ventilation Load	2,100	0	40,637	45	2,2.0		Ventilation Load	0	-21,852	63.99
Adj Air Trans Heat	60	· ·	60	0	60		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	919	-2.69
Exhaust Heat	Ū	-1,370	-1,370	-2	O .	J	OA Preheat Diff.		0.0	0.00
Sup. Fan Heat		.,0.0	708	1:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		532	532	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					O	0.00
Underfir Sup Ht Pku	n	J	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	F	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	46,571	2,111	90,026	100.00	41,045	100.00	Grand Total ==>	-11,604	-34,149	100.00

TEMPERATURES						
Cooling Heating						
SADB	55.8	0.0				
Ra Plenum	76.5	0.0				
Return	76.7	0.0				
Ret/OA	83.4	0.0				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.1	0.0				
Fn Frict	0.2	0.0				

AIRFLOWS							
AllXi							
	Cooling	Heating					
Diffuser	1,891	816					
Terminal	1,891	816					
Main Fan	1,891	816					
Sec Fan	0	0					
Nom Vent	721	466					
AHU Vent	721	466					
Infil	7	7					
MinStop/Rh	816	816					
Return	1,878	816					
Exhaust	708	0					
Rm Exh	19	7					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS						
Cooling Heating						
% OA	38.1	57.1				
cfm/ft²	0.40	0.17				
cfm/ton	252.00					
ft²/ton	625.01					
Btu/hr·ft <sup>2</sup>	19.20	-7.54				
No. People	35					

	COOLING COIL SELECTION											
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/WB/HR gr/lb		
Main Clg Aux Clg	7.5 0.0	90.0 0.0	57.1 0.0	1,809 0	83.4 0.0	69.6 0.0	85.2 0.0	55.4 0.0	54.2 0.0	59.9 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	7.5	90.0										

	AREA	S	
Gre	oss Total	Glas	-
		ft²	(%)
Floor	4,689		
Part	34,327		
Int Door	0		
ExFlr	0		
Roof	4,689	0	0
Wall	3,499	280	8
Ext Door	124	124	100

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	0.0	0	0.0	0.0					
Aux Htg	-11.6		0.0	0.0					
Preheat	-21.9	721	28.5	55.4					
Reheat	-13.4	816	55.4	70.0					
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0					
Total	-47.0								

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### Secondary - VAV w/ BB Skin

#### VAV w/Baseboard Skin Heating

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time:		lr: 7 / 15	:	Mo/Hr:				ating Design	
Oi	utside Air:	OADB/WB/HI	₹: 93 / 77 / 1	115	OADB:	78	i i i	OADB: 29	)	
	Space	Plenum	Net	Percent	Space	Percent	· ·	Space Peak	Coil Peak	
	Sens. + Lat.	Sens. + Lat	Total	Of Total	Sensible	Of Total	i i	Space Sens	Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads		0			•	•	Envelope Loads	0		0.00
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond Roof Cond	0	1,084	1,084	3	0	0	Skylite Cond Roof Cond	0	-1.460	0.00 11.16
Glass Solar	362	1,064	362	1	1,740	9	Glass Solar	0	-1, <del>4</del> 60	0.00
Glass/Door Cond	237	0	237	1	34	0	Glass/Door Cond	-694	-694	5.30
Wall Cond	244	142	386	11	397	2		-504	-807	6.16
Partition/Door	0	172	000	0	007	0	Partition/Door	0	0	0.00
Floor	0		0	0:	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0.00
Infiltration	189	ŭ	189	0;	12	0	Infiltration	-155	-155	1.19
Sub Total ==>	1,032	1,226	2,258	5	2,182	12		-1,353	-3,117	23.81
Internal Loads							Internal Loads			
Lights	5,159	1,290	6,449	15	5.159	28	Lights	0	0	0.00
People	7,650	1,290	7,650	18	4,250	23	People	0	0	0.00
Misc	5,952	0	5,952	14	5,952	32	Misc	0	0	0.00
	,	-	,		,	84		0	0	
Sub Total ==>	18,761	1,290	20,051	48	15,361	84	Sub Total ==>	U	U	0.00
Ceiling Load	1,109	-1,109	0	0	722	4	Ceiling Load	-1,132	0	0.00
Ventilation Load	0	0	19,487	47	0	0	Ventilation Load	0	-10,345	79.03
Adj Air Trans Heat	129		129	0:	129	1	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		372	-2.84
Exhaust Heat		-630	-630	-2			OA Preheat Diff.		0	0.00
Sup. Fan Heat			273	1:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		245	245	1:			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0 :						
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	21,031	1,021	41,812	100.00	18,395	100.00	Grand Total ==>	-2,486	-13,090	100.00

TEMPERATURES								
Cooling Heating								
SADB	56.8	0.0						
Ra Plenum	0.0							
Return	76.8	0.0						
Ret/OA	83.4	0.0						
Fn MtrTD	0.0	0.0						
Fn BldTD	<b>Fn BldTD</b> 0.1 0.0							
Fn Frict	0.2	0.0						

AIRFLOWS								
	Cooling	Heating						
Diffuser	896	377						
Terminal Main Fan	896 896	377 377						
Sec Fan	0	0						
Nom Vent	341	221						
AHU Vent	341	221						
Infil	3	3						
MinStop/Rh	377	377						
Return	870	380						
Exhaust	315	0						
Rm Exh	29	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS									
Cooling Heating									
% OA	38.1	58.5							
cfm/ft <sup>2</sup>	0.39	0.16							
cfm/ton	257.02								
ft²/ton	667.34								
Btu/hr·ft²	Btu/hr·ft <sup>2</sup> 17.98 -7.12								
No. People	17								

	COOLING COIL SELECTION											
		Capacity	Sens Cap.	Coil Airflow		er DB/W				/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb		
Main Clg	3.5	41.8	25.9	852	83.4	69.5	84.7	56.5	54.4	58.8		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	3.5	41.8										

	AREAS	3	
Gr	oss Total	Glass	-
		ft²	(%)
Floor	2,325		
Part	23,823		
Int Door	0		
ExFlr	0		
Roof	2,325	0	0
Wall	767	60	8
Ext Door	0	0	0

HEATING COIL SELECTION										
	Capacity	Coil Airflow	<b>Ent</b>	Lvg						
	MBh	cfm	°F	°F						
Main Htg	0.0	0	0.0	0.0						
Aux Htg	-2.5	0	0.0	0.0						
Preheat	-10.8	341	28.5	56.5						
Reheat	-5.7	377	56.5	70.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent <i>Total</i>	0.0 -19.0	0	0.0	0.0						

Project Name: CIC RA 5-9 Adapt-Build Prototype

Single Zone **CUHs - Vestibules** 

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	109	109	2	0	0	Roof Cond	0	-144	4.48
Glass Solar	2,269	0	2,269	51 ;	2,269	54		0	0	0.00
Glass/Door Cond	843	0	843	19 ;	843	20		-2,652	-2,652	82.73
Wall Cond	129	115	244	5 ;	129	3		-207	-396	12.34
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	20		20	0	6	0	Infiltration	-15	-15	0.47
Sub Total ==>	3,260	224	3,484	78 :	3,246	77	Sub Total ==>	-2,874	-3,207	100.01
Internal Loads							Internal Loads			
Lights	295	74	369	8 :	295	7	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	580	0	580	13	580	14		0	0	0.00
Sub Total ==>	875	74	948	21	875	21	Sub Total ==>	0	0	0.00
Ceiling Load	76	-76	0	0:	76	2	Ceiling Load	-85	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	· ·	0	-0.01
Exhaust Heat	U	0	0	0	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		v	22	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0					· ·	0.00
Underfir Sup Ht Pku	n	ŭ	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 ;			Supply Air Leakage		0	0.00
Grand Total ==>	4,210	221	4,454	100.00	4,196	100.00	Grand Total ==>	-2,959	-3,206	100.00

TEMPERATURES									
Cooling Heating									
SADB	55.0	84.1							
Ra Plenum	76.1	68.8							
Return	76.0	68.8							
Ret/OA	76.0	68.8							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.1	0.0							

AIRFLOWS							
Cooling Heating							
Diffuser	186	186					
Terminal	186	186					
Main Fan	186	186					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	0	0					
MinStop/Rh	0	0					
Return	186	186					
Exhaust	0	0					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft <sup>2</sup>	0.82	0.82					
cfm/ton	500.36						
ft²/ton	610.12						
Btu/hr·ft²	19.67	-14.16					
No. People	0						

			COOLING	COIL SEL	ECTIC	N				
	Total (	Capacity	Sens Cap.	<b>Coil Airflow</b>	Ent	er DB/W	B/HR	Lea	ve DB	/WB/HF
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.4	4.5	4.4	186	76.0	58.0	42.3	54.9	49.1	41.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.4	4.5								
TOtal	0.4	4.5								

AREAS Gross Total Glass ft <sup>2</sup> (%)						
Floor Part	226 2,127					
Int Door ExFIr	0					
Roof Wall	226 375	0 30	0 8			
Ext Door	93	93	100			

HEATING COIL SELECTION							
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F			
Main Htg	-3.2	186	68.8	84.1			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Humidif	0.0	0	0.0	0.0			
Opt Vent	0.0	0	0.0	0.0			
Total	-3.2						

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### DUMMY Single Zone

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
Peaked	d at Time:	Mo/Hr	: 5/1		Mo/Hr:	Sum of		Mo/Hr: He	ating Design	
Ou	utside Air:	OADB/WB/HR	: 70 / 58 / 5	3	OADB:	Peaks	· ·	OADB: 29		
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				` (;		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	24	24	14	0	0	Roof Cond	0	-30	6.67
Glass Solar	0	0	0	0	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	106	45	151	87 :	106	61	: Wall Cond	-287	-413	92.96
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	(
Infiltration	-2		-2	-1	-1	-1	Infiltration	-2	-2	0.55
Sub Total ==>	104	69	173	100	105	61	Sub Total ==>	-289	-445	100.18
Internal Loads							Internal Loads			
Lights	0	0	0	0 :	0	0	Lights	0	0	0.00
People	0	0	0	0	0	0		0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	0	0	0	0	0	0	Sub Total ==>	0	0	0.00
Ceiling Load	40	-40	0	0	68	39	Ceiling Load	-155	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	(
Dehumid. Ov Sizing	Ū		0	0	O .	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0:	0	٥	Exhaust Heat	· ·	1	-0.18
Exhaust Heat	U	0	0	0	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		v	0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			, Additional Honout		· ·	0.00
Underfir Sup Ht Pku	n	ŭ	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	144	29	173	100.00	173	100.00	Grand Total ==>	-445	-445	100.00

TEMPERATURES							
Cooling Heating							
SADB	80.0	55.0					
Ra Plenum	82.2	46.4					
Return	82.2	46.4					
Ret/OA	82.2	46.4					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS							
Cooling Heatin							
Diffuser	0	0					
Terminal	0	0					
Main Fan	0	0					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	0	0					
MinStop/Rh	0	0					
Return	0	0					
Exhaust	0	0					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft <sup>2</sup>	0.00	0.00					
cfm/ton	0.00						
ft²/ton	0.00						
Btu/hr·ft²	0.00	0.00					
No. People	0						

			COOLING	G COIL SELI	ECTIO	N				
	<b>Total</b> (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Ente °F	er DB/W °F	<b>B/HR</b> gr/lb	<b>Lea</b> °F	ve DB/ °F	<b>WB/HR</b> gr/lb
Main Clg	0.0	0.0	0.0	0	0.0	0.0	75.3	0.0	0.0	75.3
Aux Clg Opt Vent	0.0 0.0	0.0 0.0	0.0	0	0.0	0.0	0.0 0.0	0.0	0.0	0.0
Total	0.0	0.0								

AREAS Gross Total Glass ft² (%)						
Floor Part	57 5,742					
Int Door	0					
ExFlr Roof	0 57	0	0			
Wall	384	0	0			
Ext Door	0	0	0			

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	0.0	0	0.0	0.0				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	46.4	80.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	0.0							

Project Name: CIC RA 5-9 Adapt-Build Prototype

Single Zone FCU - Elec

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	l at Time: itside Air:	Mo/F OADB/WB/H	Hr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 ;	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	66	66	0 ;	0	0	Roof Cond	0	-89	0.85
Glass Solar	95	0	95	0 ;	95	9	Glass Solar	0	0	0.00
Glass/Door Cond	197	0	197	0 :	210	19	Glass/Door Cond	-593	-593	5.69
Wall Cond	38	27	65	0 ;	50	5		-91	-157	1.50
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 ;	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	7		7	0 ;	3	0	Infiltration	-9	-9	0.09
Sub Total ==>	338	93	431	0 :	359	33	Sub Total ==>	-693	-848	8.13
Internal Loads							Internal Loads			
Lights	349	87	437	0 :	349	32	Lights	0	0	0.00
People	0	0	0	0	0	0	People	0	0	0.00
Misc	353	0	353	0	353	32	Misc	0	0	0.00
Sub Total ==>	703	87	790	0	703	64	Sub Total ==>	0	0	0.00
Ceiling Load	28	-28	0	0	30	3	Ceiling Load	-24	0	0.00
Ventilation Load	0	0	182,413	104	0	0	Ventilation Load	0	-9,705	93.11
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat		130	-1.25
Exhaust Heat	ū	-7,432	-7,432	-4	· ·	ŭ	OA Preheat Diff.		0	0.00
Sup. Fan Heat		, -	25	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0 :			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0 :			· · · · · · · · · · · · · · · · · · ·			
Underfir Sup Ht Pku	<b>o</b>		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,069	-7,280	176,227	100.00	1,091	100.00	Grand Total ==>	-718	-10,423	100.00

TEMPERATURES									
Cooling Heating									
SADB	70.3	73.1							
Ra Plenum	75.7	69.5							
Return	75.7	69.5							
Ret/OA	93.4	28.5							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.1	0.0							

AIRFLOWS										
Cooling Heating										
Diffuser	207	207								
Terminal Main Fan	207 207	207 207								
Sec Fan	0	0								
Nom Vent	5,174	207								
AHU Vent	5,174	207								
Infil	0	0								
MinStop/Rh	0	0								
Return	5,174	207								
Exhaust	10,142	207								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS								
Cooling Heating								
% OA	100.0	100.0						
cfm/ft <sup>2</sup>	1.50	1.50						
cfm/ton	14.09							
ft²/ton	9.40							
Btu/hr·ft²	1,277.18	-1,741.02						
No. People	0							

			COOLING	G COIL SEL	ECTIC	N				
	Total Capacity ton MBh		Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>/B/HR</b> gr/lb	<b>Lea</b> °F	ve DB °F	<b>/WB/HR</b> gr/lb
Main Clg Aux Clg	14.7 0.0	176.2 0.0	101.3 0.0	207 0	93.4 0.0	77.5 0.0	115.3 0.0	70.2 0.0	0.0	0.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	14.7	176.2								

Gro	Glas	s (%)	
Floor Part	138 1,207		
Int Door ExFIr	0 0		
Roof Wall	138 135	0	0
Ext Door	24	24	100

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F					
Main Htg	-240.2	207-	954.2	73.1					
Aux Htg	0.0	0	0.0	0.0					
Preheat	-9.8	207	28.5	70.2					
Humidif	0.0	0	0.0	0.0					
Opt Vent	0.0	0	0.0	0.0					
Total	-240.2								

Project Name: CIC RA 5-9 Adapt-Build Prototype

Fan Coil FCU - Evid Dep

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING C	OIL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 15 R: 93 / 77 / 1	115	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: H OADB: 2	leating Design 29	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	- ,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	195	195	3	0	0		0	-267	8.80
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0 :		0	0	0.00
Wall Cond	134	68	202	3;	264	10 ;		-284	-436	14.38
Partition/Door	0		0	0 :	0	0 :		0	0	0.00
Floor	0		0	0	0	0		0	0	0.00
Adjacent Floor	0	0	0	0	0	0		0	0	0
Infiltration	35		35	1 ;	5	0	Infiltration	-28	-28	0.93
Sub Total ==>	169	263	431	7	268	10	Sub Total ==>	-312	-731	24.11
Internal Loads						;	Internal Loads			
Lights	1,160	290	1,450	25	1,160	42	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	1,084	0	1,084	19	1,084	39	Misc	0	0	0.00
Sub Total ==>	2,244	290	2,534	44	2,244	81	Sub Total ==>	0	0	0.00
Ceiling Load	248	-248	0	0 :	249	9	Ceiling Load	-188	0	0.00
Ventilation Load	0	0	2,909	50	0	0	Ventilation Load	0	-2,383	78.58
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :		- ;	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	ŭ	82	-2.69
Exhaust Heat	· ·	-108	-108	-2	· ·		OA Preheat Diff.		0	0.00
Sup. Fan Heat			4	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0 :		i				
Underfir Sup Ht Pku	р		0	0 :		:	Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,661	197	5,771	100.00	2,761	100.00	Grand Total ==>	-500	-3,032	100.00

TEMPERATURES									
Cooling Heating									
SADB	58.1	73.1							
Ra Plenum	76.9	68.6							
Return	76.9	68.6							
Ret/OA	82.7	54.5							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS										
Cooling Heating										
Diffuser	145	145								
Terminal Main Fan	145 145	145 145								
Sec Fan	0	0								
Nom Vent	51	51								
AHU Vent	51	51								
Infil	1	1								
MinStop/Rh	0	0								
Return	145	145								
Exhaust	51	51								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS								
Cooling Heating								
% OA	35.1	35.1						
cfm/ft <sup>2</sup>	0.34	0.34						
cfm/ton	301.19							
ft²/ton	880.55							
Btu/hr·ft²	13.63	-7.16						
No. People	0							

COOLING COIL SELECTION										
	<b>Total</b> (	Capacity MBh	Sens Cap. Coil Airflow Enter DB  MBh cfm °F °I				<b>'B/HR</b> gr/lb	<b>Lea</b> °F	<b>Leave DB</b> / °F °F	
Main Clg	0.5	5.8	3.9	145	82.7	68.8	82.0	58.1	56.6	65.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	5.8								

Gro	AREAS ss Total	Glass	s (%)
Floor Part	423 909		
Int Door ExFlr	0 0		
Roof Wall	423 379	0 0	0
Ext Door	0	0	0

HEATING COIL SELECTION									
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F					
Main Htg	-3.0	145	54.5	73.1					
Aux Htg	0.0	0	0.0	0.0					
Preheat	-0.6	145	54.5	58.1					
Humidif	0.0	0	0.0	0.0					
Opt Vent	0.0	0	0.0	0.0					
Total	-3.0								

Project Name: CIC RA 5-9 Adapt-Build Prototype

FCU - Mech Single Zone

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/F OADB/WB/H	Hr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	192	192	0 ;	0	0	Roof Cond	0	-256	1.39
Glass Solar	181	0	181	0 ;	181	8	Glass Solar	0	0	0.00
Glass/Door Cond	375	0	375	0 :	399	17	Glass/Door Cond	-1,126	-1,126	6.11
Wall Cond	117	74	191	0 ;	153	6		-280	-462	2.50
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	21		21	0	9	0	Infiltration	-27	-27	0.15
Sub Total ==>	694	266	960	0 :	743	31	Sub Total ==>	-1,433	-1,871	10.15
Internal Loads							Internal Loads			
Lights	524	131	655	0	524	22	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	1,025	0	1,025	1	1,025	43	Misc	0	0	0.00
Sub Total ==>	1,550	131	1,681	1	1,550	65	Sub Total ==>	0	0	0.00
Ceiling Load	94	-94	0	0	100	4	Ceiling Load	-104	0	0.00
Ventilation Load	0	0	199,558	103	0	0	Ventilation Load	0	-16,904	91.66
Adj Air Trans Heat	0	-	0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		334	-1.81
Exhaust Heat	Ü	-8,758	-8,758	-5	· ·	Ü	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-,	43	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		Ö	0	0					· ·	2.30
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,338	-8,456	193,484	100.00	2,393	100.00	Grand Total ==>	-1,537	-18,442	100.00

TEMPERATURES							
Cooling Heating							
SADB	69.1	73.8					
Ra Plenum	75.7	69.2					
Return	75.7	69.2					
Ret/OA	93.4	28.5					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.1	0.0					

AIRFLOWS									
Cooling Heating									
Diffuser	361	361							
Terminal Main Fan	361 361	361 361							
Sec Fan	0	0							
Nom Vent	5,408	361							
AHU Vent	5,408	361							
Infil	1	1							
MinStop/Rh	0	0							
Return	5,408	361							
Exhaust	10,455	361							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	100.0	100.0					
cfm/ft²	0.90	0.90					
cfm/ton	22.36						
ft²/ton	24.84						
Btu/hr·ft <sup>2</sup>	483.03	-625.21					
No. People	0						

COOLING COIL SELECTION										
		Capacity	Sens Cap.			er DB/W				/WB/HR
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	16.1	193.5	106.3	361	93.4	77.5	115.3	69.0	0.0	0.0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	16.1	193.5								
Total	16.1	193.5								

Gro	AREAS	Glas	s (%)
Floor Part	401 1,779		
Int Door ExFIr	0		
Roof Wall	401 400	0	0
Ext Door	45	45	100

HEATING COIL SELECTION								
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Htg	-250.4	361-	541.1	73.8				
Aux Htg	0.0	0	0.0	0.0				
Preheat	-16.5	361	28.5	69.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-250.4							

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### FCU - TR#1 Fan Coil

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	7 / 15 : 93 / 77 / 1	15	Mo/Hr: OADB:	Sum of Peaks		Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	75	75	6 :	0	0	Roof Cond	0	-101	18.47
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	13		13	1 ;	3	0	Infiltration	-11	-11	1.94
Sub Total ==>	13	75	87	7	3	0	Sub Total ==>	-11	-111	20.41
Internal Loads							Internal Loads			
Lights	161	40	201	16	161	25	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	406	0	406	33	406	64	Misc	0	0	0.00
Sub Total ==>	567	40	608	50	567	89	Sub Total ==>	0	0	0.00
Ceiling Load	64	-64	0	0	67	10	Ceiling Load	-56	0	0.00
Ventilation Load	0	0	544	44	0	0	Ventilation Load	0	-446	81.86
Adj Air Trans Heat	0	· ·	0	0	0	_	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		12	-2.27
Exhaust Heat		-14	-14	-1			OA Preheat Diff.		0	0.00
Sup. Fan Heat			1	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0 :			i i			
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	644	36	1,226	100.00	637	100.00	Grand Total ==>	-67	-545	100.00

TEMPERATURES							
Cooling Heating							
SADB	58.8	71.7					
Ra Plenum	76.3	68.9					
Return	76.3	68.9					
Ret/OA	81.0	57.8					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS									
Cooling Heating									
Diffuser	35	35							
Terminal Main Fan	35 35	35 35							
Sec Fan	0	0							
Nom Vent	10	10							
AHU Vent	10	10							
Infil	0	0							
MinStop/Rh	0	0							
Return	35	35							
Exhaust	10	10							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS										
	Cooling Heating									
% OA	27.4	27.4								
cfm/ft²	0.22	0.22								
cfm/ton	339.70									
ft²/ton	1,552.91									
Btu/hr·ft²	7.73	-3.44								
No. People	0									

	COOLING COIL SELECTION											
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb		
Main Clg Aux Clg	0.1 0.0	1.2 0.0	0.9 0.0	35 0	81.0 0.0	67.5 0.0	78.1 0.0	58.8 0.0	56.6 0.0	64.0 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.1	1.2										

Cra	AREAS	Glass	
Gros	ft²	(%)	
Floor Part	159 952		
Int Door ExFIr	0 0		
Roof Wall	159 0	0 0	0 0
Ext Door	0	0	0

HEATING COIL SELECTION									
	Capacity	Coil Airflow	<b>Ent</b>	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-0.6	35	57.8	71.7					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	35	57.8	58.7					
Humidif	0.0	0	0.0	0.0					
Opt Vent	0.0	0	0.0	0.0					
Total	-0.6								

Project Name: CIC RA 5-9 Adapt-Build Prototype

Primary - PFP w/ Reheat

#### Parallel Fan-Powered VAV, Htg Coil on Plenum Inlet

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/Hi	lr: 7 / 15 R: 93 / 77 / 1	115	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	- ,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	2,190	2,190	2	0	0	Roof Cond	0	-2,944	6.21
Glass Solar	4,206	0	4,206	5	5,528	13	Glass Solar	0	0	0.00
Glass/Door Cond	2,127	0	2,127	2 :	2,118	5		-6,314	-6,314	13.33
Wall Cond	1,240	779	2,019	2 :	1,648	4		-2,240	-3,689	7.79
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	(
Infiltration	377		377	0	94	0	Infiltration	-313	-313	0.66
Sub Total ==>	7,950	2,969	10,919	12	9,387	23	Sub Total ==>	-8,867	-13,261	27.99
Internal Loads							Internal Loads			
Lights	8,532	2,133	10,665	12	8,532	21	Lights	0	0	0.00
People	15,872	0	15,872	18	8,818	21	People	0	0	0.00
Misc	12,003	0	12,003	13	12,003	29	Misc	0	0	0.0
Sub Total ==>	36,407	2,133	38,540	43	29,353	72	Sub Total ==>	0	0	0.0
Ceiling Load	2.153	-2,153	0	0 :	2,245	5	Ceiling Load	-2,299	0	0.0
Ventilation Load	0	0	40,637	45	0	0	Ventilation Load	0	-33,800	71.3
Adj Air Trans Heat	60		60	0	60	0	Adj Air Trans Heat	-164	-164	
Dehumid. Ov Sizing			0	0			Ov/Undr Sizing	0	0	0.0
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		1,241	-2.6
Exhaust Heat	Ū	-1.370	-1,370	-2	· ·	· ·	OA Preheat Diff.		0	0.0
Sup. Fan Heat		1,010	708	1:			RA Preheat Diff.		-1,401	2.9
Ret. Fan Heat		532	532	1			Additional Reheat		0	0.0
Duct Heat Pkup		0	0	0					Ŭ	0.0
Underfir Sup Ht Pku	D	,	0	0			Underfir Sup Ht Pkup		0	0.0
Supply Air Leakage	r	0	0	0 ;			Supply Air Leakage		0	0.0
Grand Total ==>	46,571	2,111	90,026	100.00	41,045	100.00	Grand Total ==>	-11,329	-47,384	100.00

TEMPERATURES								
	Cooling	Heating						
SADB	55.8	78.3						
Ra Plenum	76.5	68.5						
Return	76.7	68.5						
Ret/OA	83.4	33.2						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.1	0.0						
Fn Frict	0.2	0.1						

AIRF	AIRFLOWS										
	Cooling	Heating									
Diffuser	1,891	1,209									
Terminal Main Fan	1,891 1,891	1,209 816									
Sec Fan	0	393									
Nom Vent	721	721									
AHU Vent	721	721									
Infil	7	7									
MinStop/Rh	816	816									
Return	1,878	805									
Exhaust	708	710									
Rm Exh	19	17									
Auxiliary	0	0									
Leakage Dwn	0	0									
Leakage Ups	0	0									

ENGINEERING CKS									
	Cooling Heating								
% OA	38.1	59.6							
cfm/ft²	0.40	0.08							
cfm/ton	252.00								
ft²/ton	625.01								
Btu/hr·ft <sup>2</sup>	19.20	-10.04							
No. People	35								

	COOLING COIL SELECTION										
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	/WB/HR gr/lb	
Main Clg Aux Clg	7.5 0.0	90.0 0.0	57.1 0.0	1,809 0	83.4 0.0	69.6 0.0	85.2 0.0	55.4 0.0	54.2 0.0	59.9 0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	7.5	90.0									

	AREA	S	
Gre	oss Total	Glas	- 1
	ft²	(%)	
Floor	4,689		
Part	34,327		
Int Door	0		
ExFlr	0		
Roof	4,689	0	0
Wall	3,499	280	8
Ext Door	124	124	100

HEATING COIL SELECTION										
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F						
Main Htg Aux Htg	-25.1 0.0	393 0	68.5 0.0	125.0 0.0						
Preheat	-21.9	721	28.5	55.4						
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0						
Total	-47.1									

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### Secondary - PFP w/ Reheat

#### Parallel Fan-Powered VAV, Htg Coil on Plenum Inlet

	COOLING C	OIL PEAK			<b>CLG SPACE</b>	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HI	lr: 7 / 15 R: 93 / 77 / 1	15	Mo/Hr: OADB:			Mo/Hr: He OADB: 29	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	i de la companya de	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads				111			Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,084	1,084	3	0	0	Roof Cond	0	-1,466	7.47
Glass Solar	362	0	362	1	1,740	9	Glass Solar	0	0	0.00
Glass/Door Cond	237	0	237	1:	34	0	Glass/Door Cond	-694	-694	3.54
Wall Cond	244	142	386	1;	397	2	Wall Cond	-504	-812	4.14
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0	0	Floor	0	0	0.00
Adjacent Floor	0	0	0	0 :	0	0	Adjacent Floor	0	0	0
Infiltration	189		189	0	12	0	Infiltration	-155	-155	0.79
Sub Total ==>	1,032	1,226	2,258	5	2,182	12	Sub Total ==>	-1,353	-3,128	15.95
Internal Loads							Internal Loads			
Lights	5,159	1,290	6,449	15	5,159	28	Lights	0	0	0.00
People	7,650	0	7,650	18	4,250	23		0	0	0.00
Misc	5,952	0	5,952	14	5,952	32		0	0	0.00
Sub Total ==>	18,761	1,290	20,051	48	15,361	84		0	0	0.00
Ceiling Load	1,109	-1,109	0	0	722	4	Ceiling Load	-1.019	0	0.00
Ventilation Load	0	0	19,487	47	0		Ventilation Load	0	-16,005	81.60
Adj Air Trans Heat	129	· ·	129	0	129		Adj Air Trans Heat	-483	-483	2
Dehumid. Ov Sizing			0	0;			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat		487	-2.48
Exhaust Heat	ŭ	-630	-630	-2	ŭ	ŭ	OA Preheat Diff.		0	0.00
Sup. Fan Heat			273	1:			RA Preheat Diff.		-485	2.47
Ret. Fan Heat		245	245	1			Additional Reheat		0	0.00
Duct Heat Pkup		0	0	0			x		ū	2.30
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r-	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	21,031	1,021	41,812	100.00	18,395	100.00	Grand Total ==>	-2,856	-19,614	100.00

TEMPERATURES										
	Cooling	Heating								
SADB	56.8	74.9								
Ra Plenum	76.5	68.6								
Return	76.8	68.6								
Ret/OA	83.4	32.3								
Fn MtrTD	0.0	0.0								
Fn BldTD	0.1	0.0								
Fn Frict	0.2	0.1								

AIRFLOWS										
	Cooling	Heating								
Diffuser	896	513								
Terminal Main Fan	896 896	513 377								
Sec Fan	0	136								
Nom Vent	341	341								
AHU Vent	341	341								
Infil	3	3								
MinStop/Rh	377	377								
Return	870	347								
Exhaust	315	311								
Rm Exh	29	33								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS									
	Cooling	Heating							
% OA	38.1	66.6							
cfm/ft²	0.39	0.06							
cfm/ton	257.02								
ft²/ton	667.34								
Btu/hr·ft²	17.98	-8.38							
No. People	17								

COOLING COIL SELECTION												
	Total (	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	<b>Ent</b> °F	er DB/W °F	<b>'B/HR</b> gr/lb	<b>Lea</b> °F	ve DB	<b>/WB/HR</b> gr/lb		
Main Clg Aux Clg	3.5 0.0	41.8 0.0	25.9 0.0	852 0	83.4 0.0	69.5 0.0	84.7 0.0	56.5 0.0	54.4 0.0	58.8 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	3.5	41.8										

AREAS Gross Total Glass ft² (%)								
Floor Part	2,325 23,823							
Int Door ExFIr	0 0							
Roof Wall	2,325 767	0 60	0 8					
Ext Door	0	0	0					

HEA.	<b>HEATING COIL SELECTION</b>											
	Capacity MBh	Coil Airflow cfm	<b>Ent</b> °F	Lvg °F								
Main Htg Aux Htg	-8.7 0.0	136 0	68.6 0.0	125.1 0.0								
Preheat	-10.8	341	28.5	56.5								
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0								
Total	-19.5											

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

#### **System Ventilation Requirements**

AHU Location	Description		∑ Vpz cfm	Ps People	∑ Pz People	D Ps / ∑Pz	Vou cfm	Vps cfm	Xs	Ev	Vot cfm	%OA Vot / Vps
Alternative 1												
Zone	Default System	Cooling	0	0	0	1.00	0	0	0.000	1.000	0	0.0
		Heating	0	0	0	1.00	0	0	0.000	1.000	0	0.0
Zone	System - 002	Cooling	461	4	4	1.00	123	461	0.268	0.964	128	27.8
		Heating	461	4	4	1.00	123	461	0.268	0.964	128	27.8
Zone	System - 003	Cooling	273	1	1	1.00	64	273	0.234	1.000	64	23.4
		Heating	273	1	1	1.00	64	273	0.234	1.000	64	23.4
Zone	System - 004	Cooling	508	5	5	1.00	156	508	0.307	0.996	156	30.8
		Heating	508	5	5	1.00	156	508	0.307	0.996	156	30.8
Zone	System - 005	Cooling	255	0	0	1.00	83	255	0.324	1.000	83	32.4
		Heating	255	0	0	1.00	83	255	0.324	1.000	83	32.4
Zone	System - 006	Cooling	92	0	0	1.00	28	92	0.311	1.000	28	31.1
		Heating	92	0	0	1.00	28	92	0.311	1.000	28	31.1
Zone	System - 007	Cooling	69	0	0	1.00	33	69	0.476	1.000	33	47.6
		Heating	69	0	0	1.00	33	69	0.476	1.000	33	47.6
Zone	System - 008	Cooling	647	0	0	1.00	121	647	0.187	0.526	230	35.5
		Heating	647	0	0	1.00	121	647	0.187	0.526	230	35.5
Zone	System - 009	Cooling	150	1	1	1.00	34	150	0.226	1.000	34	22.6
		Heating	150	1	1	1.00	34	150	0.226	1.000	34	22.6
Zone	System - 010	Cooling	216	0	0	1.00	87	216	0.404	1.000	87	40.4
		Heating	216	0	0	1.00	87	216	0.404	1.000	87	40.4
Zone	System - 011	Cooling	111	1	1	1.00	61	111	0.548	0.829	74	66.1
		Heating	111	1	1	1.00	61	111	0.548	0.829	74	66.1
Zone	System - 012	Cooling	549	10	10	1.00	266	549	0.484	0.752	353	64.3
		Heating	549	10	10	1.00	266	549	0.484	0.752	353	64.3
Zone	System - 013	Cooling	471	5	5	1.00	118	471	0.251	0.858	138	29.3
		Heating	471	5	5	1.00	118	471	0.251	0.858	138	29.3
Zone	System - 014	Cooling	502	9	9	1.00	87	502	0.174	0.931	94	18.7
		Heating	502	9	9	1.00	87	502	0.174	0.931	94	18.7

CIC RA 5-9 Adapt-Build Prototype Project Name: Dataset Name:

5-9\_120817.TRC

By PB

#### **System Ventilation Requirements**

AHU Location	Description		∑ Vpz cfm	Ps People	∑ Pz People	D Ps / ∑Pz	Vou cfm	Vps cfm	Xs	Ev	Vot cfm	%OA Vot / Vps
Alternative 1												
Zone	System - 015	Cooling	132	0	0	1.00	86	132	0.649	0.966	89	67.2
		Heating	132	0	0	1.00	86	132	0.649	0.966	89	67.2
Zone	System - 016	Cooling	452	12	12	1.00	185	452	0.410	0.667	278	61.5
		Heating	452	12	12	1.00	185	452	0.410	0.667	278	61.5
Zone	System - 017	Cooling	220	1	1	1.00	95	220	0.432	0.731	130	59.2
		Heating	220	1	1	1.00	95	220	0.432	0.731	130	59.2
Zone	System - 018	Cooling	239	4	4	1.00	49	239	0.203	1.000	49	20.3
		Heating	239	4	4	1.00	49	239	0.203	1.000	49	20.3
Zone	System - 019	Cooling	45	0	0	1.00	16	45	0.352	1.000	16	35.2
		Heating	45	0	0	1.00	16	45	0.352	1.000	16	35.2
Zone	System - 020	Cooling	72	0	0	1.00	14	72	0.191	1.000	14	19.1
		Heating	72	0	0	1.00	14	72	0.191	1.000	14	19.1
Zone	System - 021	Cooling	193	0	0	1.00	17	193	0.088	1.000	17	8.8
		Heating	193	0	0	1.00	17	193	0.088	1.000	17	8.8

Project Name: CIC RA 5-9 Adapt-Build Prototype
Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

						— Со	oling —	— Hea	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 1									
11 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
14 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
15 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
18 Space	0.00	0.00	0.00	8	0	1.00	0	1.00	0
20 Space	0.00	0.00	0.00	3	0	1.00	0	1.00	0
27 Space	0.00	0.00	0.00	11	0	1.00	0	1.00	0
28 Space	0.00	0.00	0.00	3	0	1.00	0	1.00	0
42 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
43 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
46 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
48 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
50 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
52 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
53 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
56 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
58 Space	0.00	0.00	0.00	1	0	1.00	0	1.00	0
59 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
61 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
64 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
67 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
70 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
71 Space	0.00	0.00	0.00	4	0	1.00	0	1.00	0
72 Space	0.00	0.00	0.00	8	0	1.00	0	1.00	0
74 Space	0.00	0.00	0.00	2	0	1.00	0	1.00	0
75 Space	0.00	0.00	0.00	0	0	1.00	0	1.00	0
Default	0.00	0.00	0.00	57	0		0		0
Default System	0.00	0.00	0.00	57	0		0		0
135 ADMINISTRATIVE/ OPERATIONS ROOM	0.00	4.00	0.21	516	106	1.00	106	1.00	106
134 RECYCLE CLOSET	0.00	0.00	0.21	84	17	1.00	17	1.00	17
ADMIN / OPS ROOM	0.00	4.00	0.21	599	123		123		123
System - 002	0.00	4.00	0.21	599	123		123		123

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

System Zone Room							— Co	oling —	— Hea	ating —
Alternative 1  133 SPECIAL AGENTS OFFICE		Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
133 SPECIAL AGENTS OFFICE 0.00 1.00 0.21 310 64 1.00 64 SPECIAL AGENTS OFFICE 0.00 1.00 0.21 310 64 64 SSYSIEM-103 0.00 1.00 0.21 313 28 CS 1.00 28 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.0	System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
SPECIAL AGENTS OFFICE   0.00	Alternative 1									
System - 003         0.00         1.00         0.21         310         64         64           128 RESIDENT AGENT CRIMINAL INTELLIGENY         0.00         1.00         0.21         161         31         1.00         28         1.00           129 TEAM CHIEF OFFICE         0.00         1.00         0.21         161         31         1.00         33         1.00           131 DRUG SUPPRESSION TEAM OFFICE         0.00         1.00         0.21         158         33         1.00         33         1.00           131 DRUG SUPPRESSION TEAM OFFICE         0.00         1.00         0.21         158         33         1.00         33         1.00           132 SPECIAL AGENTS OFFICE         0.00         1.00         0.21         158         33         1.00         33         1.00           NORTH OFFICES         0.00         5.00         0.21         757         156         156         156           System - 0.04         0.00         0.00         0.01         0.01         83         1.00         83         1.00           System - 0.05         0.00         0.00         0.01         0.21         401         83         1.00         83         1.00	133 SPECIAL AGENTS OFFICE	0.00	1.00	0.21	310	64	1.00	64	1.00	64
128 RESIDENT AGENT CRIMINAL INTELLIGEN  100  129 TEAM CHIEF OF FICE  000  100  021  151  31  100  31  31	SPECIAL AGENTS OFFICE	0.00	1.00	0.21	310	64		64		64
129 TEAM CHIEF OFFICE	System - 003	0.00	1.00	0.21	310	64		64		64
130 INVESTIGATIVE OPS TECH OFFICE	128 RESIDENT AGENT CRIMINAL INTELLIGEN(	0.00	1.00	0.21	138	28	1.00	28	1.00	28
131 DRUG SUPPRESSION TEAM OFFICE 0.00 1.00 0.21 151 31 1.00 31 1.00 132 SPECIAL AGENTS OFFICE 0.00 1.00 0.21 158 33 1.00 33 1.00 132 SPECIAL AGENTS OFFICE 0.00 5.00 0.21 757 156 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 550 156 156 550	129 TEAM CHIEF OFFICE	0.00	1.00	0.21	151	31	1.00	31	1.00	31
132 SPECIAL AGENTS OFFICE 0.00 1.00 0.21 158 33 1.00 33 1.00 NORTH OFFICES 0.00 5.00 0.21 757 156 156 System - 004 0.00 5.00 0.21 757 156 156 System - 004 1.00 0.00 5.00 0.21 757 156 156 System - 005 126 MECHANICAL ROOM 0.00 0.00 0.00 0.21 401 83 83 1.00 83 1.00 MECHANICAL ROOM 0.00 0.00 0.21 401 83 83 83 System - 005 0.00 0.00 0.00 0.21 401 83 83 83 System - 005 0.00 0.00 0.00 0.21 138 28 28 1.00 28 1.00 ELECTRICAL ROOM 0.00 0.00 0.01 138 28 28 28 28 System - 005 125 ELECTRICAL ROOM 0.00 0.00 0.01 138 28 28 28 28 System - 006 0.00 0.00 0.01 138 28 28 28 28 System - 006 0.00 0.00 0.01 138 28 28 28 28 System - 006 0.00 0.00 0.00 0.01 138 28 28 28 28 System - 006 0.00 0.00 0.00 0.01 159 33 1.00 33 1.00 0.00 121 159 33 3 1.00 33 1.00 133 1.00 121 121 121 121 121 122 ARMS VAULT 0.00 0.00 0.00 0.01 159 33 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	130 INVESTIGATIVE OPS TECH OFFICE	0.00	1.00	0.21	158	33	1.00	33	1.00	33
NORTH OFFICES 0.00 5.00 0.21 757 156 156 558 5914 156 5914 156 156 5914 156 156 5914 156 156 156 156 156 156 156 156 156 156	131 DRUG SUPPRESSION TEAM OFFICE	0.00	1.00	0.21	151	31	1.00	31	1.00	31
System - 004         0.00         5.00         0.21         757         156         156           126 MECHANICAL ROOM         0.00         0.00         0.021         401         83         1.00         83         1.00           MECHANICAL ROOM         0.00         0.00         0.01         401         83         1.00         83         1.00           System - 005         0.00         0.00         0.021         401         83         83         1.00         28         1.00         22         1.00         28         28 <t< td=""><td>132 SPECIAL AGENTS OFFICE</td><td>0.00</td><td>1.00</td><td>0.21</td><td>158</td><td>33</td><td>1.00</td><td>33</td><td>1.00</td><td>33</td></t<>	132 SPECIAL AGENTS OFFICE	0.00	1.00	0.21	158	33	1.00	33	1.00	33
126 MECHANICAL ROOM       0.00       0.00       0.00       0.21       401       83       1.00       83       1.00         MECHANICAL ROOM       0.00       0.00       0.00       0.21       401       83       83       83         System - 005       0.00       0.00       0.21       401       83       28       1.00       28       1.00         ELECTRICAL ROOM       0.00       0.00       0.21       138       28       1.00       28       1.00         ELECTRICAL ROOM       0.00       0.00       0.01       138       28       1.00       28       1.00         System - 006       0.00       0.00       0.21       138       28       1.00       28       1.00         System - 006       0.00       0.00       0.21       159       33       1.00       33       1.00         TELECOM ROOM       0.00       0.00       0.01       159       33       1.00       33       1.00         TELECOM ROOM       0.00       0.00       0.01       159       33       1.00       13       1.00       13       1.00       13       1.00       13       1.00       1.00       1.00       1.00	NORTH OFFICES	0.00	5.00	0.21	757	156		156		156
MECHANICAL ROOM	System - 004	0.00	5.00	0.21	757	156		156		156
System - 005         0.00         0.00         0.21         401         83         83           125 ELECTRICAL ROOM         0.00         0.00         0.21         138         28         1.00         28         1.00           ELECTRICAL ROOM         0.00         0.00         0.21         138         28         28         28           System - 006         0.00         0.00         0.21         138         28         28         28           124 TELECOM ROOM         0.00         0.00         0.21         159         33         1.00         33         1.00           TELECOM ROOM         0.00         0.00         0.21         159         33         1.00         33         1.00           TELECOM ROOM         0.00         0.00         0.21         159         33         1.00         33         1.00           TELECOM ROOM         0.00         0.00         0.01         159         33         1.00         33         1.00           TELECOM ROOM         0.00         0.00         0.01         159         33         1.00         33         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00 <td>126 MECHANICAL ROOM</td> <td>0.00</td> <td>0.00</td> <td>0.21</td> <td>401</td> <td></td> <td>1.00</td> <td>83</td> <td>1.00</td> <td>83</td>	126 MECHANICAL ROOM	0.00	0.00	0.21	401		1.00	83	1.00	83
125 ELECTRICAL ROOM	MECHANICAL ROOM	0.00	0.00	0.21	401	83		83		83
ELECTRICAL ROOM 0.00 0.00 0.21 138 28 28 28  System - 006 0.00 0.00 0.00 0.21 138 28 28 28  124 TELECOM ROOM 0.00 0.00 0.00 0.21 159 33 1.00 33 1.00  TELECOM ROOM 0.00 0.00 0.01 159 33 3 3.03  System - 007 0.00 0.00 0.01 159 33 3 3.03  System - 007 0.00 0.00 0.01 159 33 3 3.03  System - 007 0.00 0.00 0.01 159 33 3 3.03  122 TABLE OF ORGANIZATION AND EQUIPMEI 0.00 0.00 0.01 159 33 3 3.00  122 TABLE OF ORGANIZATION AND EQUIPMEI 0.00 0.00 0.01 159 103 1.00 103 1.00  123 ARMS VAULT 0.00 0.00 0.01 86 18 1.00 18 1.00  TOE STORAGE 0.00 0.00 0.00 0.21 86 18 1.00 18 1.00  System - 008 121 121 121  121 DUTY AGENT OFFICE 0.00 1.00 0.00 0.21 165 34 1.00 34 1.00  DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 34 34  System - 009 0.00 1.00 0.21 165 34 34 34  119 EVIDENCE DEPOSITORY ROOM 0.00 0.00 0.21 423 87 1.00 87 1.00  EVIDENCE DEPOSITORY ROOM 0.00 0.00 0.21 423 87 1.00 87 1.00  EVIDENCE DEPOSITORY 0.00 0.00 0.01 121 423 87 87  System - 010 0.00 0.00 0.01 121 423 87 87  System - 010 0.00 0.00 0.01 137 28 1.00 28 1.00	System - 005	0.00	0.00	0.21	401	83		83		83
System - 006         0.00         0.00         0.21         138         28         28           124 TELECOM ROOM         0.00         0.00         0.00         0.21         159         33         1.00         33         1.00           TELECOM ROOM         0.00         0.00         0.00         0.21         159         33         1.00         33         1.00           System - 007         0.00         0.00         0.01         159         33         33         33         1.00         133         1.00         103         1.00         100         1.00         1.00         0.00         0.21         159         33         1.00         103         1.00         100         1.00         1.00         0.00         0.21         159         33         1.00         103         1.00         100         1.00         1.00         0.00         0.21         159         33         1.00         100         1.00         1.00         1.00         0.21         158         18         1.00         103         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00         1.00	125 ELECTRICAL ROOM	0.00	0.00	0.21	138	28	1.00	28	1.00	28
124 TELECOM ROOM       0.00       0.00       0.00       0.21       159       33       1.00       33       1.00         TELECOM ROOM       0.00       0.00       0.00       0.21       159       33       33       33         System - 007       0.00       0.00       0.00       0.21       159       33       33       33         122 TABLE OF ORGANIZATION AND EQUIPME!       0.00       0.00       0.21       501       103       1.00       103       1.00       103       1.00       103       1.00       100       1.00       103       1.00       103       1.00       100       1.00       1.00       0.21       86       18       1.00       18       1.00       18       1.00       18       1.00       18       1.00       18       1.00       100       1.00       0.21       586       121	ELECTRICAL ROOM	0.00	0.00	0.21	138	28		28		28
TELECOM ROOM  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  122 TABLE OF ORGANIZATION AND EQUIPME!  0,00  0,00  0,00  0,00  0,00  0,00  0,00  0,00  123 ARMS VAULT  0,00  0,	System - 006	0.00	0.00	0.21	138	28		28		28
System - 007         0.00         0.00         0.21         159         33         33           122 TABLE OF ORGANIZATION AND EQUIPME!         0.00         0.00         0.21         501         103         1.00         103         1.00           123 ARMS VAULT         0.00         0.00         0.00         0.21         86         18         1.00         18         1.00           TOE STORAGE         0.00         0.00         0.21         586         121         121         121           System - 008         0.00         0.00         0.21         586         121         121         121           121 DUTY AGENT OFFICE         0.00         1.00         0.21         165         34         1.00         34         1.00           DUTY AGENT OFFICE         0.00         1.00         0.21         165         34         34         34           System - 009         0.00         1.00         0.21         165         34         34         34           119 EVIDENCE DEPOSITORY ROOM         0.00         0.00         0.21         423         87         1.00         87         1.00           EVIDENCE DEPOSITORY         0.00         0.00         0.01	124 TELECOM ROOM	0.00	0.00	0.21	159	33	1.00	33	1.00	33
122 TABLE OF ORGANIZATION AND EQUIPME! 0.00 0.00 0.01 501 103 1.00 103 1.00 123 ARMS VAULT 0.00 0.00 0.00 0.21 86 18 1.00 18 1.00 TOE STORAGE 0.00 0.00 0.00 0.21 586 121 121 System - 008 0.00 0.00 0.21 586 121 121 121 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 1.00 34 1.00 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 34 System - 009 0.00 1.00 0.21 165 34 34 System - 009 0.00 1.00 0.21 165 34 34 System - 009 0.00 1.00 0.21 165 34 34 System - 009 0.00 1.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 System - 009 0.00 0.00 0.21 165 34 34 34 System - 010 0.00 0.00 0.00 0.21 165 34 37 1.00 87 1.00 EVIDENCE DEPOSITORY O.00 0.00 0.00 0.21 162 162 162 162 162 162 162 162 162 1	TELECOM ROOM	0.00	0.00	0.21	159	33		33		33
123 ARMS VAULT 0.00 0.00 0.00 0.21 86 18 1.00 18 1.00  TOE STORAGE 0.00 0.00 0.01 586 121 121  System - 008 0.00 0.00 0.21 586 121 121  121 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 1.00 34 1.00  DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 34 34  System - 009 0.00 1.00 0.21 165 34 34 34  119 EVIDENCE DEPOSITORY ROOM 0.00 0.00 0.21 165 34 34 34  EVIDENCE DEPOSITORY ROOM 0.00 0.00 0.21 423 87 1.00 87 1.00  EVIDENCE DEPOSITORY 0.00 0.00 0.00 0.21 423 87 87  System - 010 0.00 0.00 0.00 0.21 423 87 87  117 CORRIDOR 0.00 0.00 0.00 0.21 137 28 1.00 28 1.00	System - 007	0.00	0.00	0.21	159	33		33		33
TOE STORAGE 0.00 0.00 0.21 586 121 121 System - 008 0.00 0.00 0.21 586 121 121  121 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 1.00 34 1.00  DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 34  System - 009 0.00 1.00 0.21 165 34 34  119 EVIDENCE DEPOSITORY ROOM 0.00 0.00 0.21 423 87 1.00 87 1.00  EVIDENCE DEPOSITORY O.00 0.00 0.00 0.21 423 87 87  System - 010 0.00 0.00 0.00 0.21 423 87 87  117 CORRIDOR 0.00 0.00 0.00 0.21 137 28 1.00 28 1.00	122 TABLE OF ORGANIZATION AND EQUIPMEN	0.00	0.00	0.21	501	103	1.00	103	1.00	103
System - 008       0.00       0.00       0.00       0.21       586       121       121         121 DUTY AGENT OFFICE       0.00       1.00       0.21       165       34       1.00       34       1.00         DUTY AGENT OFFICE       0.00       1.00       0.21       165       34       34       34         System - 009       0.00       1.00       0.21       165       34       34       34         119 EVIDENCE DEPOSITORY ROOM       0.00       0.00       0.21       423       87       1.00       87       1.00         EVIDENCE DEPOSITORY       0.00       0.00       0.21       423       87       87       87         System - 010       0.00       0.00       0.21       423       87       87       87         117 CORRIDOR       0.00       0.00       0.21       137       28       1.00       28       1.00	123 ARMS VAULT	0.00	0.00	0.21	86	18	1.00	18	1.00	18
121 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 1.00 34 1.00 DUTY AGENT OFFICE 0.00 1.00 0.21 165 34 34 34 34 34 34 34 34 34 34 34 34 34	TOE STORAGE	0.00	0.00	0.21	586	121		121		121
DUTY AGENT OFFICE       0.00       1.00       0.21       165       34       34         System - 009       0.00       1.00       0.21       165       34       34         119 EVIDENCE DEPOSITORY ROOM       0.00       0.00       0.21       423       87       1.00       87       1.00         EVIDENCE DEPOSITORY       0.00       0.00       0.21       423       87       87       87         System - 010       0.00       0.00       0.21       423       87       87       87         117 CORRIDOR       0.00       0.00       0.21       137       28       1.00       28       1.00	System - 008	0.00	0.00	0.21	586	121		121		121
DUTY AGENT OFFICE       0.00       1.00       0.21       165       34       34         System - 009       0.00       1.00       0.21       165       34       34         119 EVIDENCE DEPOSITORY ROOM       0.00       0.00       0.21       423       87       1.00       87       1.00         EVIDENCE DEPOSITORY       0.00       0.00       0.21       423       87       87       87         System - 010       0.00       0.00       0.21       423       87       87       87         117 CORRIDOR       0.00       0.00       0.21       137       28       1.00       28       1.00	121 DUTY AGENT OFFICE	0.00	1.00	0.21	165	34	1.00	34	1.00	34
119 EVIDENCE DEPOSITORY ROOM       0.00       0.00       0.21       423       87       1.00       87       1.00         EVIDENCE DEPOSITORY       0.00       0.00       0.00       423       87       87       87         System - 010       0.00       0.00       0.21       423       87       87       87         117 CORRIDOR       0.00       0.00       0.21       137       28       1.00       28       1.00	DUTY AGENT OFFICE	0.00	1.00	0.21	165	34		34		34
EVIDENCE DEPOSITORY         0.00         0.00         0.21         423         87         87           System - 010         0.00         0.00         0.21         423         87         87           117 CORRIDOR         0.00         0.00         0.21         137         28         1.00         28         1.00	System - 009	0.00	1.00	0.21	165	34		34		34
EVIDENCE DEPOSITORY       0.00       0.00       0.21       423       87       87         System - 010       0.00       0.00       0.21       423       87       87         117 CORRIDOR       0.00       0.00       0.21       137       28       1.00       28       1.00	119 EVIDENCE DEPOSITORY ROOM	0.00	0.00	0.21	423		1.00	87	1.00	87
System - 010     0.00     0.00     0.21     423     87     87       117 CORRIDOR     0.00     0.00     0.21     137     28     1.00     28     1.00	EVIDENCE DEPOSITORY	0.00	0.00	0.21	423			87		87
117 CORRIDOR 0.00 0.00 0.21 137 28 1.00 28 1.00	System - 010	0.00	0.00	0.21	423			87		87
	117 CORRIDOR	0.00	0.00	0.21	137		1.00	28	1.00	28
	120 EVIDENCE PROCESSING ROOM	0.00	1.00	0.21	159	33	1.00	33	1.00	33

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

				_		— Со	oling —	— Не	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 1									
EVIDENCE PROCESSING	0.00	1.00	0.21	297	61		61		61
System - 011	0.00	1.00	0.21	297	61		61		61
112 POLYGRAPH OFFICE	0.00	2.00	0.21	110	23	1.00	23	1.00	23
113 POLYGRAPH EXAM ROOM	0.00	2.00	0.21	116	24	1.00	24	1.00	24
114 OBSERVATION ROOM	0.00	2.00	0.21	120	25	1.00	25	1.00	25
115 SUSPECT WAITING ROOM	0.00	4.00	0.21	150	31	1.00	31	1.00	31
117A CORRIDOR	0.00	0.00	0.21	384	79	1.00	79	1.00	79
127B CORRIDOR	0.00	0.00	0.21	345	71	1.00	71	1.00	71
116 SUSPECT TOILET	0.00	0.00	0.21	65	13	1.00	13	1.00	13
CORE SUSPECT AREA	0.00	10.00	0.21	1,290	266		266		266
System - 012	0.00	10.00	0.21	1,290	266		266		266
109 SMALL INTERVIEW ROOM #2	0.00	2.00	0.21	144	30	1.00	30	1.00	30
110 SMALL INTERVIEW ROOM #1	0.00	2.00	0.21	139	29	1.00	29	1.00	29
111 PHOTO ID ROOM	0.00	0.00	0.21	125	26	1.00	26	1.00	26
118 EVIDENCE CUSTODIAN OFFICE	0.00	1.00	0.21	166	34	1.00	34	1.00	34
SOUTHWEST OFFICES	0.00	5.00	0.21	574	118		118		118
System - 013	0.00	5.00	0.21	574	118		118		118
107 SPECIAL AGENT IN CHARGE OFFICE	0.00	1.00	0.21	192	40	1.00	40	1.00	40
108 LARGE INTERVIEW ROOM	0.00	8.00	0.21	231	48	1.00	48	1.00	48
SOUTH OFFICES	0.00	9.00	0.21	423	87		87		87
System - 014	0.00	9.00	0.21	423	87		87		87
105A CORRIDOR	0.00	0.00	0.21	136	28	1.00	28	1.00	28
127A CORRIDOR	0.00	0.00	0.21	165	34	1.00	34	1.00	34
136 SHOWER	0.00	0.00	0.21	116	24	1.00	24	1.00	24
SHOWER	0.00	0.00	0.21	416	86		86		86
System - 015	0.00	0.00	0.21	416	86		86		86
105 CORRIDOR	0.00	0.00	0.21	181	37	1.00	37	1.00	37
106 MULTI-PURPOSE LOUNGE	0.00	12.00	0.21	556	115	1.00	115	1.00	115
127 CORRIDOR	0.00	0.00	0.21	161	33	1.00	33	1.00	33
MULTI-PURPOSE ROOM	0.00	12.00	0.21	898	185		185		185
System - 016	0.00	12.00	0.21	898	185		185		185

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

						— Со	oling —	— Hea	ating —
System Zone Room	Rp cfm / p	Pz People	Ra cfm/ft²	Az ft²	Vbz cfm	Ez	Voz cfm	Ez	Voz cfm
Alternative 1									
102 CORRIDOR	0.00	0.00	0.21	131	27	1.00	27	1.00	27
103 MEN	0.00	0.47	0.21	145	30	1.00	30	1.00	30
104 WOMEN	0.00	0.48	0.21	147	30	1.00	30	1.00	30
137 JANITOR	0.00	0.00	0.21	40	8	1.00	8	1.00	8
RESTROOMS	0.00	0.95	0.21	463	95		95		95
System - 017	0.00	0.95	0.21	463	95		95		95
101 VISITOR WAITING AREA	0.00	4.00	0.21	236	49	1.00	49	1.00	49
VISITOR WAITING	0.00	4.00	0.21	236	49		49		49
System - 018	0.00	4.00	0.21	236	49		49		49
003 VESTIBULE NORTH	0.00	0.00	0.21	77	16	1.00	16	1.00	16
VESTIBULE NORTH	0.00	0.00	0.21	77	16		16		16
System - 019	0.00	0.00	0.21	77	16		16		16
002 VESTIBULE WEST	0.00	0.00	0.21	67	14	1.00	14	1.00	14
VESTIBULE WEST	0.00	0.00	0.21	67	14		14		14
System - 020	0.00	0.00	0.21	67	14		14		14
001 ENTRY VESTIBULE	0.00	0.00	0.21	82	17	1.00	17	1.00	17
ENTRY VESTIBULE	0.00	0.00	0.21	82	17		17		17
System - 021	0.00	0.00	0.21	82	17		17		17

Project Name: CIC RA 5-9 Adapt-Build Prototype
Dataset Name: 5-9\_120817.TRC

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
11 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
14 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
15 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
18 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
20 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
27 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
28 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
42 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
43 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
46 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
48 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
50 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
52 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
53 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
56 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
58 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
59 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
61 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
64 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
67 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
70 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
71 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
72 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
74 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
75 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
Default	-	0	0	0	0	0							1.000
Default System		0	0	0	0	0							1.000
135 ADMINISTRATIVE/ OPERATION	Single Fan CV	405	405	405	0	106	0.263	1.00	0.00	1.00	1.00	1.00	1.000
134 RECYCLE CLOSET	Single Fan CV	57	57	57	0	17	0.303	1.00	0.00	1.00	1.00	1.00	0.964 *
ADMIN / OPS ROOM		461	461	461	0	123							0.964
System - 002		461	461	461	0	123							0.964
133 SPECIAL AGENTS OFFICE	Single Fan CV	273	273	273	0	64	0.234	1.00	0.00	1.00	1.00	1.00	1.000 *
SPECIAL AGENTS OFFICE	-	273	273	273	0	64							1.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
System - 003		273	273	273	0	64							1.000
128 RESIDENT AGENT CRIMINAL	Single Fan CV	95	95	95	0	28	0.299	1.00	0.00	1.00	1.00	1.00	1.000
129 TEAM CHIEF OFFICE	Single Fan CV	102	102	102	0	31	0.307	1.00	0.00	1.00	1.00	1.00	1.000
130 INVESTIGATIVE OPS TECH (	Single Fan CV	105	105	105	0	33	0.310	1.00	0.00	1.00	1.00	1.00	0.996 *
131 DRUG SUPPRESSION TEAM	Single Fan CV	102	102	102	0	31	0.307	1.00	0.00	1.00	1.00	1.00	1.000
132 SPECIAL AGENTS OFFICE	Single Fan CV	105	105	105	0	33	0.310	1.00	0.00	1.00	1.00	1.00	0.996
NORTH OFFICES		508	508	508	0	156							0.996
System - 004		508	508	508	0	156							0.996
126 MECHANICAL ROOM	Single Fan CV	255	255	255	0	83	0.324	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		255	255	255	0	83							1.000
System - 005		255	255	255	0	83							1.000
125 ELECTRICAL ROOM	Single Fan CV	92	92	92	0	28	0.311	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM		92	92	92	0	28							1.000
System - 006		92	92	92	0	28							1.000
124 TELECOM ROOM	Single Fan CV	69	69	69	0	33	0.476	1.00	0.00	1.00	1.00	1.00	1.000 *
TELECOM ROOM		69	69	69	0	33							1.000
System - 007		69	69	69	0	33							1.000
122 TABLE OF ORGANIZATION A	Single Fan CV	620	620	620	0	103	0.166	1.00	0.00	1.00	1.00	1.00	1.000
123 ARMS VAULT	Single Fan CV	27	27	27	0	18	0.661	1.00	0.00	1.00	1.00	1.00	0.526 *
TOE STORAGE		647	647	647	0	121							0.526
System - 008		647	647	647	0	121							0.526
121 DUTY AGENT OFFICE	Single Fan CV	150	150	150	0	34	0.226	1.00	0.00	1.00	1.00	1.00	1.000 *
DUTY AGENT OFFICE		150	150	150	0	34							1.000
System - 009		150	150	150	0	34							1.000
119 EVIDENCE DEPOSITORY RC	Single Fan CV	216	216	216	0	87	0.404	1.00	0.00	1.00	1.00	1.00	1.000 *
EVIDENCE DEPOSITORY		216	216	216	0	87							1.000
System - 010		216	216	216	0	87							1.000
117 CORRIDOR	Single Fan CV	39	39	39	0	28	0.719	1.00	0.00	1.00	1.00	1.00	0.829 *
120 EVIDENCE PROCESSING RC	Single Fan CV	72	72	72	0	33	0.455	1.00	0.00	1.00	1.00	1.00	1.000
EVIDENCE PROCESSING		111	111	111	0	61							0.829
System - 011		111	111	111	0	61							0.829
112 POLYGRAPH OFFICE	Single Fan CV	66	66	66	0	23	0.342	1.00	0.00	1.00	1.00	1.00	1.000
113 POLYGRAPH EXAM ROOM	Single Fan CV	68	68	68	0	24	0.349	1.00	0.00	1.00	1.00	1.00	1.000

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
114 OBSERVATION ROOM	Single Fan CV	70	70	70	0	25	0.354	1.00	0.00	1.00	1.00	1.00	1.000
115 SUSPECT WAITING ROOM	Single Fan CV	107	107	107	0	31	0.289	1.00	0.00	1.00	1.00	1.00	1.000
117A CORRIDOR	Single Fan CV	108	108	108	0	79	0.732	1.00	0.00	1.00	1.00	1.00	0.752 *
127B CORRIDOR	Single Fan CV	97	97	97	0	71	0.732	1.00	0.00	1.00	1.00	1.00	0.752 *
116 SUSPECT TOILET	Single Fan CV	33	33	33	0	13	0.411	1.00	0.00	1.00	1.00	1.00	1.000
CORE SUSPECT AREA		549	549	549	0	266							0.752
System - 012		549	549	549	0	266							0.752
109 SMALL INTERVIEW ROOM #2	Single Fan CV	155	155	155	0	30	0.191	1.00	0.00	1.00	1.00	1.00	1.000
110 SMALL INTERVIEW ROOM #	Single Fan CV	152	152	152	0	29	0.188	1.00	0.00	1.00	1.00	1.00	1.000
111 PHOTO ID ROOM	Single Fan CV	66	66	66	0	26	0.393	1.00	0.00	1.00	1.00	1.00	0.858 *
118 EVIDENCE CUSTODIAN OFF	Single Fan CV	98	98	98	0	34	0.349	1.00	0.00	1.00	1.00	1.00	0.902
SOUTHWEST OFFICES		471	471	471	0	118							0.858
System - 013		471	471	471	0	118							0.858
107 SPECIAL AGENT IN CHARGE	Single Fan CV	163	163	163	0	40	0.242	1.00	0.00	1.00	1.00	1.00	0.931 *
108 LARGE INTERVIEW ROOM	Single Fan CV	338	338	338	0	48	0.141	1.00	0.00	1.00	1.00	1.00	1.000
SOUTH OFFICES		502	502	502	0	87							0.931
System - 014		502	502	502	0	87							0.931
105A CORRIDOR	Single Fan CV	41	41	41	0	28	0.683	1.00	0.00	1.00	1.00	1.00	0.966
127A CORRIDOR	Single Fan CV	50	50	50	0	34	0.683	1.00	0.00	1.00	1.00	1.00	0.966 *
136 SHOWER	Single Fan CV	41	41	41	0	24	0.575	1.00	0.00	1.00	1.00	1.00	1.000
SHOWER		132	132	132	0	86							0.966
System - 015		132	132	132	0	86							0.966
105 CORRIDOR	Single Fan CV	50	50	50	0	37	0.743	1.00	0.00	1.00	1.00	1.00	0.667
106 MULTI-PURPOSE LOUNGE	Single Fan CV	357	357	357	0	115	0.321	1.00	0.00	1.00	1.00	1.00	1.000
127 CORRIDOR	Single Fan CV	45	45	45	0	33	0.743	1.00	0.00	1.00	1.00	1.00	0.667 *
MULTI-PURPOSE ROOM		452	452	452	0	185							0.667
System - 016		452	452	452	0	185							0.667
102 CORRIDOR	Single Fan CV	38	38	38	0	27	0.701	1.00	0.00	1.00	1.00	1.00	0.731 *
103 MEN	Single Fan CV	80	80	80	0	30	0.373	1.00	0.00	1.00	1.00	1.00	1.000
104 WOMEN	Single Fan CV	85	85	85	0	30	0.355	1.00	0.00	1.00	1.00	1.00	1.000
137 JANITOR	Single Fan CV	17	17	17	0	8	0.496	1.00	0.00	1.00	1.00	1.00	0.936
RESTROOMS		220	220	220	0	95							0.731
System - 017		220	220	220	0	95							0.731

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
101 VISITOR WAITING AREA	Single Fan CV	239	239	239	0	49	0.203	1.00	0.00	1.00	1.00	1.00	1.000 *
VISITOR WAITING		239	239	239	0	49							1.000
System - 018		239	239	239	0	49							1.000
003 VESTIBULE NORTH	Single Fan CV	45	45	45	0	16	0.352	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		45	45	45	0	16							1.000
System - 019		45	45	45	0	16							1.000
002 VESTIBULE WEST	Single Fan CV	72	72	72	0	14	0.191	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		72	72	72	0	14							1.000
System - 020		72	72	72	0	14							1.000
001 ENTRY VESTIBULE	Single Fan CV	193	193	193	0	17	0.088	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		193	193	193	0	17							1.000
System - 021		193	193	193	0	17							1.000

By PB

## **Ventilation Calculations for Heating Design**

-		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
11 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
14 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
15 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
18 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
20 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
27 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
28 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
42 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
43 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
46 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
48 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
50 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
52 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
53 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
56 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
58 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
59 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
61 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
64 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
67 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
70 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
71 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
72 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
74 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
75 Space	Single Fan CV	0	0	0	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
Default		0	0	0	0	0							1.000
Default System		0	0	0	0	0							1.000
135 ADMINISTRATIVE/ OPERATION	Single Fan CV	405	405	405	0	106	0.263	1.00	0.00	1.00	1.00	1.00	1.000
134 RECYCLE CLOSET	Single Fan CV	57	57	57	0	17	0.303	1.00	0.00	1.00	1.00	1.00	0.964 *
ADMIN / OPS ROOM	- J	461	461	461	0	123							0.964
System - 002		461	461	461	0	123							0.964
133 SPECIAL AGENTS OFFICE	Single Fan CV	273	273	273	0	64	0.234	1.00	0.00	1.00	1.00	1.00	1.000 *
SPECIAL AGENTS OFFICE	5gio i dii 0 v	273	273	273	0	64	U.20T	1.00	0.00	1.00	1.00	1.00	1.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

-		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
System - 003		273	273	273	0	64							1.000
128 RESIDENT AGENT CRIMINAL	Single Fan CV	95	95	95	0	28	0.299	1.00	0.00	1.00	1.00	1.00	1.000
129 TEAM CHIEF OFFICE	Single Fan CV	102	102	102	0	31	0.307	1.00	0.00	1.00	1.00	1.00	1.000
130 INVESTIGATIVE OPS TECH (	Single Fan CV	105	105	105	0	33	0.310	1.00	0.00	1.00	1.00	1.00	0.996 *
131 DRUG SUPPRESSION TEAM	Single Fan CV	102	102	102	0	31	0.307	1.00	0.00	1.00	1.00	1.00	1.000
132 SPECIAL AGENTS OFFICE	Single Fan CV	105	105	105	0	33	0.310	1.00	0.00	1.00	1.00	1.00	0.996
NORTH OFFICES		508	508	508	0	156							0.996
System - 004		508	508	508	0	156							0.996
126 MECHANICAL ROOM	Single Fan CV	255	255	255	0	83	0.324	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		255	255	255	0	83							1.000
System - 005		255	255	255	0	83							1.000
125 ELECTRICAL ROOM	Single Fan CV	92	92	92	0	28	0.311	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM		92	92	92	0	28							1.000
System - 006		92	92	92	0	28							1.000
124 TELECOM ROOM	Single Fan CV	69	69	69	0	33	0.476	1.00	0.00	1.00	1.00	1.00	1.000 *
TELECOM ROOM		69	69	69	0	33							1.000
System - 007		69	69	69	0	33							1.000
122 TABLE OF ORGANIZATION A	Single Fan CV	620	620	620	0	103	0.166	1.00	0.00	1.00	1.00	1.00	1.000
123 ARMS VAULT	Single Fan CV	27	27	27	0	18	0.661	1.00	0.00	1.00	1.00	1.00	0.526 *
TOE STORAGE		647	647	647	0	121							0.526
System - 008		647	647	647	0	121							0.526
121 DUTY AGENT OFFICE	Single Fan CV	150	150	150	0	34	0.226	1.00	0.00	1.00	1.00	1.00	1.000 *
DUTY AGENT OFFICE		150	150	150	0	34							1.000
System - 009		150	150	150	0	34							1.000
119 EVIDENCE DEPOSITORY RO	Single Fan CV	216	216	216	0	87	0.404	1.00	0.00	1.00	1.00	1.00	1.000 *
EVIDENCE DEPOSITORY		216	216	216	0	87							1.000
System - 010		216	216	216	0	87							1.000
117 CORRIDOR	Single Fan CV	39	39	39	0	28	0.719	1.00	0.00	1.00	1.00	1.00	0.829 *
120 EVIDENCE PROCESSING RC	•	72	72	72	0	33	0.455	1.00	0.00	1.00	1.00	1.00	1.000
EVIDENCE PROCESSING	-	111	111	111	0	61							0.829
System - 011		111	111	111	0	61							0.829
112 POLYGRAPH OFFICE	Single Fan CV	66	66	66	0	23	0.342	1.00	0.00	1.00	1.00	1.00	1.000
113 POLYGRAPH EXAM ROOM	Single Fan CV	68	68	68	0	24	0.349	1.00	0.00	1.00	1.00	1.00	1.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
114 OBSERVATION ROOM	Single Fan CV	70	70	70	0	25	0.354	1.00	0.00	1.00	1.00	1.00	1.000
115 SUSPECT WAITING ROOM	Single Fan CV	107	107	107	0	31	0.289	1.00	0.00	1.00	1.00	1.00	1.000
117A CORRIDOR	Single Fan CV	108	108	108	0	79	0.732	1.00	0.00	1.00	1.00	1.00	0.752 *
127B CORRIDOR	Single Fan CV	97	97	97	0	71	0.732	1.00	0.00	1.00	1.00	1.00	0.752 *
116 SUSPECT TOILET	Single Fan CV	33	33	33	0	13	0.411	1.00	0.00	1.00	1.00	1.00	1.000
CORE SUSPECT AREA		549	549	549	0	266							0.752
System - 012		549	549	549	0	266							0.752
109 SMALL INTERVIEW ROOM #2	Single Fan CV	155	155	155	0	30	0.191	1.00	0.00	1.00	1.00	1.00	1.000
110 SMALL INTERVIEW ROOM #1	Single Fan CV	152	152	152	0	29	0.188	1.00	0.00	1.00	1.00	1.00	1.000
111 PHOTO ID ROOM	Single Fan CV	66	66	66	0	26	0.393	1.00	0.00	1.00	1.00	1.00	0.858 *
118 EVIDENCE CUSTODIAN OFF	Single Fan CV	98	98	98	0	34	0.349	1.00	0.00	1.00	1.00	1.00	0.902
SOUTHWEST OFFICES		471	471	471	0	118							0.858
System - 013		471	471	471	0	118							0.858
107 SPECIAL AGENT IN CHARGE	Single Fan CV	163	163	163	0	40	0.242	1.00	0.00	1.00	1.00	1.00	0.931 *
108 LARGE INTERVIEW ROOM	Single Fan CV	338	338	338	0	48	0.141	1.00	0.00	1.00	1.00	1.00	1.000
SOUTH OFFICES		502	502	502	0	87							0.931
System - 014		502	502	502	0	87							0.931
105A CORRIDOR	Single Fan CV	41	41	41	0	28	0.683	1.00	0.00	1.00	1.00	1.00	0.966
127A CORRIDOR	Single Fan CV	50	50	50	0	34	0.683	1.00	0.00	1.00	1.00	1.00	0.966 *
136 SHOWER	Single Fan CV	41	41	41	0	24	0.575	1.00	0.00	1.00	1.00	1.00	1.000
SHOWER		132	132	132	0	86							0.966
System - 015		132	132	132	0	86							0.966
105 CORRIDOR	Single Fan CV	50	50	50	0	37	0.743	1.00	0.00	1.00	1.00	1.00	0.667
106 MULTI-PURPOSE LOUNGE	Single Fan CV	357	357	357	0	115	0.321	1.00	0.00	1.00	1.00	1.00	1.000
127 CORRIDOR	Single Fan CV	45	45	45	0	33	0.743	1.00	0.00	1.00	1.00	1.00	0.667 *
MULTI-PURPOSE ROOM		452	452	452	0	185							0.667
System - 016		452	452	452	0	185							0.667
102 CORRIDOR	Single Fan CV	38	38	38	0	27	0.701	1.00	0.00	1.00	1.00	1.00	0.731 *
103 MEN	Single Fan CV	80	80	80	0	30	0.373	1.00	0.00	1.00	1.00	1.00	1.000
104 WOMEN	Single Fan CV	85	85	85	0	30	0.355	1.00	0.00	1.00	1.00	1.00	1.000
137 JANITOR	Single Fan CV	17	17	17	0	8	0.496	1.00	0.00	1.00	1.00	1.00	0.936
RESTROOMS		220	220	220	0	95							0.731
System - 017		220	220	220	0	95							0.731

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Вох Туре	cfm	cfm	cfm	cfm	cfm							
Alternative 1													
101 VISITOR WAITING AREA	Single Fan CV	239	239	239	0	49	0.203	1.00	0.00	1.00	1.00	1.00	1.000 *
VISITOR WAITING		239	239	239	0	49							1.000
System - 018		239	239	239	0	49							1.000
003 VESTIBULE NORTH	Single Fan CV	45	45	45	0	16	0.352	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		45	45	45	0	16							1.000
System - 019		45	45	45	0	16							1.000
002 VESTIBULE WEST	Single Fan CV	72	72	72	0	14	0.191	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		72	72	72	0	14							1.000
System - 020		72	72	72	0	14							1.000
001 ENTRY VESTIBULE	Single Fan CV	193	193	193	0	17	0.088	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		193	193	193	0	17							1.000
System - 021		193	193	193	0	17							1.000

By PB

#### **System Ventilation Requirements**

AHU Location	Description		∑ Vpz cfm	Ps People	∑ Pz People	D Ps / ∑Pz	Vou cfm	Vps cfm	Xs	Ev	Vot cfm	%OA Vot / Vps
Alternative 2												
System	Primary - VAV w/ BB	Cooling	2,061	35	35	1.00	466	1,891	0.246	0.646	721	38.1
		Heating	0	0	0	0.00	0	0	0.000	0.000	0	0.0
System	Secondary - VAV w/ BB Skin	Cooling	941	17	17	1.00	221	896	0.246	0.646	341	38.1
		Heating	0	0	0	0.00	0	0	0.000	0.000	0	0.0
Zone	DUMMY	Cooling	0	0	0	0.00	0	0	0.000	0.000	0	0.0
		Heating	0	0	0	0.00	0	0	0.000	0.000	0	0.0
Zone	CUHs - Vestibules	Cooling	186	0	0	1.00	0	186	0.000	1.000	0	0.0
		Heating	186	0	0	1.00	0	186	0.000	1.000	0	0.0
Zone	FCU - Elec	Cooling	207	0	0	1.00	207	207	1.000	1.000	207	100.0
		Heating	207	0	0	1.00	207	207	1.000	1.000	207	100.0
Room	FCU - Evid Dep	Cooling	145	0	0	1.00	51	145	0.351	1.000	51	35.1
		Heating	145	0	0	1.00	51	145	0.351	1.000	51	35.1
Room	FCU - TR#1	Cooling	35	0	0	1.00	10	35	0.274	1.000	10	27.4
		Heating	35	0	0	1.00	10	35	0.274	1.000	10	27.4
Zone	FCU - Mech	Cooling	361	0	0	1.00	361	361	1.000	1.000	361	100.0
		Heating	361	0	0	1.00	361	361	1.000	1.000	361	100.0

By PB

#### **Ventilation Parameters**

						— Со	oling —	— Hea	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 2									
101 VISITOR WAITING AREA	5.00	4.00	0.06	236	34	1.00	34	0.00	0
VISITOR WAITING	5.00	4.00	0.06	236	34		34		0
102 CORRIDOR	0.00	0.00	0.06	131	8	1.00	8	0.00	0
103 MEN	0.00	0.00	0.00	145	0	1.00	0	0.00	0
104 WOMEN	0.00	0.00	0.00	147	0	1.00	0	0.00	0
137 JANITOR	0.00	0.00	0.00	40	0	1.00	0	0.00	0
RESTROOMS	0.00	0.00	0.02	463	8		8		0
105 CORRIDOR	0.00	0.00	0.06	181	11	1.00	11	0.00	0
106 MULTI-PURPOSE LOUNGE	5.00	12.00	0.06	556	93	1.00	93	0.00	0
127 CORRIDOR	0.00	0.00	0.06	161	10	1.00	10	0.00	0
MULTI-PURPOSE ROOM	5.00	12.00	0.06	898	114		114		0
105A CORRIDOR	0.00	0.00	0.06	136	8	1.00	8	0.00	0
127A CORRIDOR	0.00	0.00	0.06	165	10	1.00	10	0.00	0
136 SHOWER	0.00	0.00	0.00	116	0	1.00	0	0.00	0
SHOWER	0.00	0.00	0.04	416	18		18		0
107 SPECIAL AGENT IN CHARGE OFFICE	5.00	1.00	0.06	192	17	1.00	17	0.00	0
108 LARGE INTERVIEW ROOM	5.00	8.00	0.06	231	54	1.00	54	0.00	0
SOUTH OFFICES	5.00	9.00	0.06	423	70		70		0
122 TABLE OF ORGANIZATION AND EQUIPMEN	0.00	0.00	0.12	501	60	1.00	60	0.00	0
123 ARMS VAULT	0.00	0.00	0.12	86	10	1.00	10	0.00	0
TOE STORAGE	0.00	0.00	0.12	586	70		70		0
128 RESIDENT AGENT CRIMINAL INTELLIGEN(	5.00	1.00	0.06	138	13	1.00	13	0.00	0
129 TEAM CHIEF OFFICE	5.00	1.00	0.06	151	14	1.00	14	0.00	0
130 INVESTIGATIVE OPS TECH OFFICE	5.00	1.00	0.06	158	14	1.00	14	0.00	0
131 DRUG SUPPRESSION TEAM OFFICE	5.00	1.00	0.06	151	14	1.00	14	0.00	0
132 SPECIAL AGENTS OFFICE	5.00	1.00	0.06	158	14	1.00	14	0.00	0
NORTH OFFICES	5.00	5.00	0.06	757	70		70		0
133 SPECIAL AGENTS OFFICE	5.00	1.00	0.06	310	24	1.00	24	0.00	0
SPECIAL AGENTS OFFICE	5.00	1.00	0.06	310	24		24		0
135 ADMINISTRATIVE/ OPERATIONS ROOM	5.00	4.00	0.06	516	51	1.00	51	0.00	0
134 RECYCLE CLOSET	5.00	0.27	0.06	84	6	1.00	6	0.00	0

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

				_	_	— Со	oling —	— He	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 2									
ADMIN / OPS ROOM	5.00	4.27	0.06	599	57		57		0
Primary - VAV w/ BB	5.00	35.27	0.06	4,689	466		466		0
109 SMALL INTERVIEW ROOM #2	5.00	2.00	0.06	144	19	1.00	19	0.00	0
110 SMALL INTERVIEW ROOM #1	5.00	2.00	0.06	139	18	1.00	18	0.00	0
111 PHOTO ID ROOM	5.00	0.00	0.06	125	8	1.00	8	0.00	0
118 EVIDENCE CUSTODIAN OFFICE	5.00	1.00	0.06	166	15	1.00	15	0.00	0
SOUTHWEST OFFICES	5.00	5.00	0.06	574	59		59		0
112 POLYGRAPH OFFICE	5.00	2.00	0.06	110	17	1.00	17	0.00	0
113 POLYGRAPH EXAM ROOM	5.00	2.00	0.06	116	17	1.00	17	0.00	0
114 OBSERVATION ROOM	5.00	2.00	0.06	120	17	1.00	17	0.00	0
115 SUSPECT WAITING ROOM	5.00	4.00	0.06	150	29	1.00	29	0.00	0
117A CORRIDOR	0.00	0.00	0.06	384	23	1.00	23	0.00	0
127B CORRIDOR	0.00	0.00	0.06	345	21	1.00	21	0.00	0
116 SUSPECT TOILET	0.00	0.00	0.00	65	0	1.00	0	0.00	0
CORE SUSPECT AREA	5.00	10.00	0.06	1,290	123		123		0
117 CORRIDOR	0.00	0.00	0.06	137	8	1.00	8	0.00	0
120 EVIDENCE PROCESSING ROOM	5.00	1.00	0.06	159	15	1.00	15	0.00	0
EVIDENCE PROCESSING	5.00	1.00	0.06	297	23		23		0
121 DUTY AGENT OFFICE	5.00	1.00	0.06	165	15	1.00	15	0.00	0
DUTY AGENT OFFICE	5.00	1.00	0.06	165	15		15		0
Secondary - VAV w/ BB Skin	5.00	17.00	0.06	2,325	221		221		0
Default	0.00	0.00	0.00	0	0		0		0
DUMMY	0.00	0.00	0.00	0	0		0		0
001 ENTRY VESTIBULE	0.00	0.00	0.00	82	0	1.00	0	1.00	0
ENTRY VESTIBULE	0.00	0.00	0.00	82	0		0		0
002 VESTIBULE WEST	0.00	0.00	0.00	67	0	1.00	0	1.00	0
VESTIBULE WEST	0.00	0.00	0.00	67	0		0		0
003 VESTIBULE NORTH	0.00	0.00	0.00	77	0	1.00	0	1.00	0
VESTIBULE NORTH	0.00	0.00	0.00	77	0		0		0
CUHs - Vestibules	0.00	0.00	0.00	226	0		0		0
125 ELECTRICAL ROOM	0.00	0.00	10.00	138	207	1.00	207	1.00	207

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

						<u>—</u> Со	oling —	— Hea	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 2									
ELECTRICAL ROOM	0.00	0.00	1.50	138	207		207		207
FCU - Elec	0.00	0.00	1.50	138	207		207		207
119 EVIDENCE DEPOSITORY ROOM	0.00	0.00	0.12	423	51	1.00	51	1.00	51
EVIDENCE DEPOSITORY	0.00	0.00	0.12	423	51		51		51
FCU - Evid Dep	0.00	0.00	0.12	423	51		51		51
124 TELECOM ROOM	0.00	0.00	0.06	159	10	1.00	10	1.00	10
TELECOM ROOM	0.00	0.00	0.06	159	10		10		10
FCU - TR#1	0.00	0.00	0.06	159	10		10		10
126 MECHANICAL ROOM	0.00	0.00	6.00	401	361	1.00	361	1.00	361
MECHANICAL ROOM	0.00	0.00	0.90	401	361		361		361
FCU - Mech	0.00	0.00	0.90	401	361		361		361

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
101 VISITOR WAITING AREA	Shutoff VAV	125	125	125	57	34	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
VISITOR WAITING		125	125	125	57	34							0.646
102 CORRIDOR	Shutoff VAV	25	25	25	13	8	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
103 MEN	Shutoff VAV	41	41	41	12	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000
104 WOMEN	Shutoff VAV	42	42	42	13	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000
137 JANITOR	Shutoff VAV	9	9	9	3	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000
RESTROOMS		116	116	116	41	8							0.646
105 CORRIDOR	Shutoff VAV	38	38	38	18	11	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
106 MULTI-PURPOSE LOUNGE	Shutoff VAV	261	261	261	156	93	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
127 CORRIDOR	Shutoff VAV	51	51	51	16	10	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
MULTI-PURPOSE ROOM		350	350	350	190	114							0.646
105A CORRIDOR	Shutoff VAV	19	19	19	14	8	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
127A CORRIDOR	Shutoff VAV	46	46	46	16	10	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
136 SHOWER	Shutoff VAV	20	20	20	6	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000
SHOWER		86	86	86	36	18							0.646
107 SPECIAL AGENT IN CHARGE	Shutoff VAV	93	93	93	28	17	0.594	1.00	0.00	1.00	1.00	1.00	0.653
108 LARGE INTERVIEW ROOM	Shutoff VAV	236	236	236	90	54	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
SOUTH OFFICES		329	329	329	118	70							0.646
122 TABLE OF ORGANIZATION A	Shutoff VAV	337	337	337	101	60	0.594	1.00	0.00	1.00	1.00	1.00	0.652
123 ARMS VAULT	Shutoff VAV	19	19	19	17	10	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
TOE STORAGE		356	356	356	118	70							0.646
128 RESIDENT AGENT CRIMINAL	Shutoff VAV	57	57	57	22	13	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
129 TEAM CHIEF OFFICE	Shutoff VAV	62	62	62	23	14	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
130 INVESTIGATIVE OPS TECH (	Shutoff VAV	63	63	63	24	14	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
131 DRUG SUPPRESSION TEAM	Shutoff VAV	62	62	62	23	14	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
132 SPECIAL AGENTS OFFICE	Shutoff VAV	63	63	63	24	14	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
NORTH OFFICES		308	308	308	117	70							0.646
133 SPECIAL AGENTS OFFICE	Shutoff VAV	147	147	147	44	24	0.537	1.00	0.00	1.00	1.00	1.00	0.710
SPECIAL AGENTS OFFICE		147	147	147	44	24							0.710
135 ADMINISTRATIVE/ OPERATION	Shutoff VAV	217	217	217	85	51	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
134 RECYCLE CLOSET	Shutoff VAV	28	28	28	11	6	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
ADMIN / OPS ROOM		244	244	244	96	57							0.646
Primary - VAV w/ BB		2,061	1,891	2,061	816	466							0.646

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
109 SMALL INTERVIEW ROOM #2	Shutoff VAV	105	105	105	32	19	0.591	1.00	0.00	1.00	1.00	1.00	0.655
110 SMALL INTERVIEW ROOM #	Shutoff VAV	104	104	104	31	18	0.586	1.00	0.00	1.00	1.00	1.00	0.660
111 PHOTO ID ROOM	Shutoff VAV	38	38	38	13	8	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
118 EVIDENCE CUSTODIAN OFF	Shutoff VAV	59	59	59	25	15	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
SOUTHWEST OFFICES		306	306	306	100	59							0.646
112 POLYGRAPH OFFICE	Shutoff VAV	58	58	58	28	17	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
113 POLYGRAPH EXAM ROOM	Shutoff VAV	59	59	59	28	17	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
114 OBSERVATION ROOM	Shutoff VAV	58	58	58	29	17	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
115 SUSPECT WAITING ROOM	Shutoff VAV	97	97	97	48	29	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
117A CORRIDOR	Shutoff VAV	58	58	58	38	23	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
127B CORRIDOR	Shutoff VAV	102	102	102	34	21	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
116 SUSPECT TOILET	Shutoff VAV	27	27	27	8	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000
CORE SUSPECT AREA		457	457	457	214	123							0.646
117 CORRIDOR	Shutoff VAV	44	44	44	14	8	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
120 EVIDENCE PROCESSING RC	Shutoff VAV	50	50	50	24	15	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
EVIDENCE PROCESSING		95	95	95	38	23							0.646
121 DUTY AGENT OFFICE	Shutoff VAV	82	82	82	25	15	0.600	1.00	0.00	1.00	1.00	1.00	0.646 *
DUTY AGENT OFFICE		82	82	82	25	15							0.646
Secondary - VAV w/ BB Skin		941	896	941	377	221							0.646
Default		0	0	0	0	0							0.000
DUMMY		0	0	0	0	0							0.000
001 ENTRY VESTIBULE	Single Fan CV	109	109	109	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		109	109	109	0	0							1.000
002 VESTIBULE WEST	Single Fan CV	49	49	49	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		49	49	49	0	0							1.000
003 VESTIBULE NORTH	Single Fan CV	28	28	28	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		28	28	28	0	0							1.000
CUHs - Vestibules		186	186	186	0	0							1.000
125 ELECTRICAL ROOM	Single Fan CV	207	207	207	0	207	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM		207	207	207	0	207							1.000
FCU - Elec		207	207	207	0	207							1.000
119 EVIDENCE DEPOSITORY RC	Single Fan CV	145	145	145	0	51	0.351	1.00	0.00	1.00	1.00	1.00	0.000
EVIDENCE DEPOSITORY		145	145	145	0	51							1.000

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
FCU - Evid Dep		145	145	145	0	51							1.000
124 TELECOM ROOM	Single Fan CV	35	35	35	0	10	0.274	1.00	0.00	1.00	1.00	1.00	0.000
TELECOM ROOM		35	35	35	0	10							1.000
FCU - TR#1		35	35	35	0	10							1.000
126 MECHANICAL ROOM	Single Fan CV	361	361	361	0	361	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		361	361	361	0	361							1.000
FCU - Mech		361	361	361	0	361							1.000

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
101 VISITOR WAITING AREA	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
VISITOR WAITING		0	0	0	0	0							0.000
102 CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
103 MEN	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
104 WOMEN	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
137 JANITOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
RESTROOMS		0	0	0	0	0							0.000
105 CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
106 MULTI-PURPOSE LOUNGE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
127 CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
MULTI-PURPOSE ROOM		0	0	0	0	0							0.000
105A CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
127A CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
136 SHOWER	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
SHOWER		0	0	0	0	0							0.000
107 SPECIAL AGENT IN CHARGE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
108 LARGE INTERVIEW ROOM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
SOUTH OFFICES		0	0	0	0	0							0.000
122 TABLE OF ORGANIZATION A	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
123 ARMS VAULT	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
TOE STORAGE		0	0	0	0	0							0.000
128 RESIDENT AGENT CRIMINAL	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
129 TEAM CHIEF OFFICE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
130 INVESTIGATIVE OPS TECH (	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
131 DRUG SUPPRESSION TEAM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
132 SPECIAL AGENTS OFFICE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
NORTH OFFICES		0	0	0	0	0							0.000
133 SPECIAL AGENTS OFFICE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
SPECIAL AGENTS OFFICE		0	0	0	0	0							0.000
135 ADMINISTRATIVE/ OPERATION	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
134 RECYCLE CLOSET	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
ADMIN / OPS ROOM		0	0	0	0	0							0.000
Primary - VAV w/ BB		0	0	0	0	0							0.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

-		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Вох Туре	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
109 SMALL INTERVIEW ROOM #2	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
110 SMALL INTERVIEW ROOM #1	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
111 PHOTO ID ROOM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
118 EVIDENCE CUSTODIAN OFF	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
SOUTHWEST OFFICES		0	0	0	0	0							0.000
112 POLYGRAPH OFFICE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
113 POLYGRAPH EXAM ROOM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
114 OBSERVATION ROOM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
115 SUSPECT WAITING ROOM	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
117A CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
127B CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
116 SUSPECT TOILET	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
CORE SUSPECT AREA		0	0	0	0	0							0.000
117 CORRIDOR	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
120 EVIDENCE PROCESSING RC	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
EVIDENCE PROCESSING		0	0	0	0	0							0.000
121 DUTY AGENT OFFICE	Induction	0	0	0	0	0	0.000	0.00	0.00	0.00	0.00	0.00	0.000
DUTY AGENT OFFICE		0	0	0	0	0							0.000
Secondary - VAV w/ BB Skin		0	0	0	0	0							0.000
Default		0	0	0	0	0							0.000
DUMMY		0	0	0	0	0							0.000
001 ENTRY VESTIBULE	Single Fan CV	109	109	109	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		109	109	109	0	0							1.000
002 VESTIBULE WEST	Single Fan CV	49	49	49	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		49	49	49	0	0							1.000
003 VESTIBULE NORTH	Single Fan CV	28	28	28	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		28	28	28	0	0							1.000
CUHs - Vestibules		186	186	186	0	0							1.000
125 ELECTRICAL ROOM	Single Fan CV	207	207	207	0	207	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM	-	207	207	207	0	207							1.000
FCU - Elec		207	207	207	0	207							1.000
119 EVIDENCE DEPOSITORY RO	Single Fan CV	145	145	145	0	51	0.351	1.00	0.00	1.00	1.00	1.00	0.000
EVIDENCE DEPOSITORY	-	145	145	145	0	51							1.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Вох Туре	cfm	cfm	cfm	cfm	cfm							
Alternative 2													
FCU - Evid Dep		145	145	145	0	51							1.000
124 TELECOM ROOM	Single Fan CV	35	35	35	0	10	0.274	1.00	0.00	1.00	1.00	1.00	0.000
TELECOM ROOM		35	35	35	0	10							1.000
FCU - TR#1		35	35	35	0	10							1.000
126 MECHANICAL ROOM	Single Fan CV	361	361	361	0	361	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		361	361	361	0	361							1.000
FCU - Mech		361	361	361	0	361							1.000

By PB

#### **System Ventilation Requirements**

AHU Location	Description		∑ Vpz cfm	Ps People	∑ Pz People	D Ps / ∑Pz	Vou cfm	Vps cfm	Xs	Ev	Vot cfm	%OA Vot / Vps
Alternative 3												
System	Primary - PFP w/ Reheat	Cooling	2,061	35	35	1.00	466	1,891	0.246	0.646	721	38.1
		Heating	816	35	35	1.00	466	816	0.571	0.971	480	58.8
System	Secondary - PFP w/ Reheat	Cooling	941	17	17	1.00	221	896	0.246	0.646	341	38.1
		Heating	377	17	17	1.00	221	377	0.585	0.985	224	59.4
Zone	DUMMY	Cooling	0	0	0	0.00	0	0	0.000	0.000	0	0.0
		Heating	0	0	0	0.00	0	0	0.000	0.000	0	0.0
Zone	CUHs - Vestibules	Cooling	186	0	0	1.00	0	186	0.000	1.000	0	0.0
		Heating	186	0	0	1.00	0	186	0.000	1.000	0	0.0
Zone	FCU - Elec	Cooling	207	0	0	1.00	207	207	1.000	1.000	207	100.0
		Heating	207	0	0	1.00	207	207	1.000	1.000	207	100.0
Room	FCU - Evid Dep	Cooling	145	0	0	1.00	51	145	0.351	1.000	51	35.1
		Heating	145	0	0	1.00	51	145	0.351	1.000	51	35.1
Room	FCU - TR#1	Cooling	35	0	0	1.00	10	35	0.274	1.000	10	27.4
		Heating	35	0	0	1.00	10	35	0.274	1.000	10	27.4
Zone	FCU - Mech	Cooling	361	0	0	1.00	361	361	1.000	1.000	361	100.0
		Heating	361	0	0	1.00	361	361	1.000	1.000	361	100.0

By PB

#### **Ventilation Parameters**

						— Со	oling —	— He	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 3									
101 VISITOR WAITING AREA	5.00	4.00	0.06	236	34	1.00	34	1.00	34
VISITOR WAITING	5.00	4.00	0.06	236	34		34		34
102 CORRIDOR	0.00	0.00	0.06	131	8	1.00	8	1.00	8
103 MEN	0.00	0.00	0.00	145	0	1.00	0	1.00	0
104 WOMEN	0.00	0.00	0.00	147	0	1.00	0	1.00	0
137 JANITOR	0.00	0.00	0.00	40	0	1.00	0	1.00	0
RESTROOMS	0.00	0.00	0.02	463	8		8		8
105 CORRIDOR	0.00	0.00	0.06	181	11	1.00	11	1.00	11
106 MULTI-PURPOSE LOUNGE	5.00	12.00	0.06	556	93	1.00	93	1.00	93
127 CORRIDOR	0.00	0.00	0.06	161	10	1.00	10	1.00	10
MULTI-PURPOSE ROOM	5.00	12.00	0.06	898	114		114		114
105A CORRIDOR	0.00	0.00	0.06	136	8	1.00	8	1.00	8
127A CORRIDOR	0.00	0.00	0.06	165	10	1.00	10	1.00	10
136 SHOWER	0.00	0.00	0.00	116	0	1.00	0	1.00	0
SHOWER	0.00	0.00	0.04	416	18		18		18
107 SPECIAL AGENT IN CHARGE OFFICE	5.00	1.00	0.06	192	17	1.00	17	1.00	17
108 LARGE INTERVIEW ROOM	5.00	8.00	0.06	231	54	1.00	54	1.00	54
SOUTH OFFICES	5.00	9.00	0.06	423	70		70		70
122 TABLE OF ORGANIZATION AND EQUIPMEN	0.00	0.00	0.12	501	60	1.00	60	1.00	60
123 ARMS VAULT	0.00	0.00	0.12	86	10	1.00	10	1.00	10
TOE STORAGE	0.00	0.00	0.12	586	70		70		70
128 RESIDENT AGENT CRIMINAL INTELLIGEN(	5.00	1.00	0.06	138	13	1.00	13	1.00	13
129 TEAM CHIEF OFFICE	5.00	1.00	0.06	151	14	1.00	14	1.00	14
130 INVESTIGATIVE OPS TECH OFFICE	5.00	1.00	0.06	158	14	1.00	14	1.00	14
131 DRUG SUPPRESSION TEAM OFFICE	5.00	1.00	0.06	151	14	1.00	14	1.00	14
132 SPECIAL AGENTS OFFICE	5.00	1.00	0.06	158	14	1.00	14	1.00	14
NORTH OFFICES	5.00	5.00	0.06	757	70		70		70
133 SPECIAL AGENTS OFFICE	5.00	1.00	0.06	310	24	1.00	24	1.00	24
SPECIAL AGENTS OFFICE	5.00	1.00	0.06	310	24		24		24
135 ADMINISTRATIVE/ OPERATIONS ROOM	5.00	4.00	0.06	516	51	1.00	51	1.00	51
134 RECYCLE CLOSET	5.00	0.27	0.06	84	6	1.00	6	1.00	6

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

						— Со	oling —	— Не	ating —
	Rp	Pz	Ra	Az	Vbz	Ez	Voz	Ez	Voz
System Zone Room	cfm / p	People	cfm/ft²	ft²	cfm		cfm		cfm
Alternative 3									
ADMIN / OPS ROOM	5.00	4.27	0.06	599	57		57		57
Primary - PFP w/ Reheat	5.00	35.27	0.06	4,689	466		466		466
109 SMALL INTERVIEW ROOM #2	5.00	2.00	0.06	144	19	1.00	19	1.00	19
110 SMALL INTERVIEW ROOM #1	5.00	2.00	0.06	139	18	1.00	18	1.00	18
111 PHOTO ID ROOM	5.00	0.00	0.06	125	8	1.00	8	1.00	8
118 EVIDENCE CUSTODIAN OFFICE	5.00	1.00	0.06	166	15	1.00	15	1.00	15
SOUTHWEST OFFICES	5.00	5.00	0.06	574	59		59		59
112 POLYGRAPH OFFICE	5.00	2.00	0.06	110	17	1.00	17	1.00	17
113 POLYGRAPH EXAM ROOM	5.00	2.00	0.06	116	17	1.00	17	1.00	17
114 OBSERVATION ROOM	5.00	2.00	0.06	120	17	1.00	17	1.00	17
115 SUSPECT WAITING ROOM	5.00	4.00	0.06	150	29	1.00	29	1.00	29
117A CORRIDOR	0.00	0.00	0.06	384	23	1.00	23	1.00	23
127B CORRIDOR	0.00	0.00	0.06	345	21	1.00	21	1.00	21
116 SUSPECT TOILET	0.00	0.00	0.00	65	0	1.00	0	1.00	0
CORE SUSPECT AREA	5.00	10.00	0.06	1,290	123		123		123
117 CORRIDOR	0.00	0.00	0.06	137	8	1.00	8	1.00	8
120 EVIDENCE PROCESSING ROOM	5.00	1.00	0.06	159	15	1.00	15	1.00	15
EVIDENCE PROCESSING	5.00	1.00	0.06	297	23		23		23
121 DUTY AGENT OFFICE	5.00	1.00	0.06	165	15	1.00	15	1.00	15
DUTY AGENT OFFICE	5.00	1.00	0.06	165	15		15		15
Secondary - PFP w/ Reheat	5.00	17.00	0.06	2,325	221		221		221
Default	0.00	0.00	0.00	0	0		0		0
DUMMY	0.00	0.00	0.00	0	0		0		0
001 ENTRY VESTIBULE	0.00	0.00	0.00	82	0	1.00	0	1.00	0
ENTRY VESTIBULE	0.00	0.00	0.00	82	0		0		0
002 VESTIBULE WEST	0.00	0.00	0.00	67	0	1.00	0	1.00	0
VESTIBULE WEST	0.00	0.00	0.00	67	0		0		0
003 VESTIBULE NORTH	0.00	0.00	0.00	77	0	1.00	0	1.00	0
VESTIBULE NORTH	0.00	0.00	0.00	77	0		0		0
CUHs - Vestibules	0.00	0.00	0.00	226	0		0		0
125 ELECTRICAL ROOM	0.00	0.00	10.00	138	207	1.00	207	1.00	207

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

#### **Ventilation Parameters**

						— Co	oling —	— Hea	ating —
System Zone Room	Rp cfm / p	Pz People	Ra cfm/ft²	Az ft²	Vbz cfm	Ez	Voz cfm	Ez	Voz cfm
Alternative 3									
ELECTRICAL ROOM	0.00	0.00	1.50	138	207		207		207
FCU - Elec	0.00	0.00	1.50	138	207		207		207
119 EVIDENCE DEPOSITORY ROOM	0.00	0.00	0.12	423	51	1.00	51	1.00	51
EVIDENCE DEPOSITORY	0.00	0.00	0.12	423	51		51		51
FCU - Evid Dep	0.00	0.00	0.12	423	51		51		51
124 TELECOM ROOM	0.00	0.00	0.06	159	10	1.00	10	1.00	10
TELECOM ROOM	0.00	0.00	0.06	159	10		10		10
FCU - TR#1	0.00	0.00	0.06	159	10		10		10
126 MECHANICAL ROOM	0.00	0.00	6.00	401	361	1.00	361	1.00	361
MECHANICAL ROOM	0.00	0.00	0.90	401	361		361		361
FCU - Mech	0.00	0.00	0.90	401	361		361		361

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
101 VISITOR WAITING AREA	PFP Reheat	125	125	125	57	34	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
VISITOR WAITING		125	125	125	57	34							0.646
102 CORRIDOR	PFP Reheat	25	25	25	13	8	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
103 MEN	PFP Reheat	41	41	41	12	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
104 WOMEN	PFP Reheat	42	42	42	13	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
137 JANITOR	PFP Reheat	9	9	9	3	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
RESTROOMS		116	116	116	41	8							0.646
105 CORRIDOR	PFP Reheat	38	38	38	18	11	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
106 MULTI-PURPOSE LOUNGE	PFP Reheat	261	261	261	156	93	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
127 CORRIDOR	PFP Reheat	51	51	51	16	10	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
MULTI-PURPOSE ROOM		350	350	350	190	114							0.646
105A CORRIDOR	PFP Reheat	19	19	19	14	8	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
127A CORRIDOR	PFP Reheat	46	46	46	16	10	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
136 SHOWER	PFP Reheat	20	20	20	6	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
SHOWER		86	86	86	36	18							0.646
107 SPECIAL AGENT IN CHARGE	PFP Reheat	93	93	93	28	17	0.594	1.00	0.30	1.00	1.00	1.00	0.653
108 LARGE INTERVIEW ROOM	PFP Reheat	236	236	236	90	54	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
SOUTH OFFICES		329	329	329	118	70							0.646
122 TABLE OF ORGANIZATION A	PFP Reheat	337	337	337	101	60	0.594	1.00	0.30	1.00	1.00	1.00	0.652
123 ARMS VAULT	PFP Reheat	19	19	19	17	10	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
TOE STORAGE		356	356	356	118	70							0.646
128 RESIDENT AGENT CRIMINAL	PFP Reheat	57	57	57	22	13	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
129 TEAM CHIEF OFFICE	PFP Reheat	62	62	62	23	14	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
130 INVESTIGATIVE OPS TECH (	PFP Reheat	63	63	63	24	14	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
131 DRUG SUPPRESSION TEAM	PFP Reheat	62	62	62	23	14	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
132 SPECIAL AGENTS OFFICE	PFP Reheat	63	63	63	24	14	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
NORTH OFFICES		308	308	308	117	70							0.646
133 SPECIAL AGENTS OFFICE	PFP Reheat	147	147	147	44	24	0.537	1.00	0.30	1.00	1.00	1.00	0.710
SPECIAL AGENTS OFFICE		147	147	147	44	24							0.710
135 ADMINISTRATIVE/ OPERATION	PFP Reheat	217	217	217	85	51	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
134 RECYCLE CLOSET	PFP Reheat	28	28	28	11	6	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
ADMIN / OPS ROOM		244	244	244	96	57							0.646
Primary - PFP w/ Reheat		2.061	1.891	2,061	816	466							0.646

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
109 SMALL INTERVIEW ROOM #2	PFP Reheat	105	105	105	32	19	0.591	1.00	0.30	1.00	1.00	1.00	0.655
110 SMALL INTERVIEW ROOM #	PFP Reheat	104	104	104	31	18	0.586	1.00	0.30	1.00	1.00	1.00	0.660
111 PHOTO ID ROOM	PFP Reheat	38	38	38	13	8	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
118 EVIDENCE CUSTODIAN OFF	PFP Reheat	59	59	59	25	15	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
SOUTHWEST OFFICES		306	306	306	100	59							0.646
112 POLYGRAPH OFFICE	PFP Reheat	58	58	58	28	17	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
113 POLYGRAPH EXAM ROOM	PFP Reheat	59	59	59	28	17	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
114 OBSERVATION ROOM	PFP Reheat	58	58	58	29	17	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
115 SUSPECT WAITING ROOM	PFP Reheat	97	97	97	48	29	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
117A CORRIDOR	PFP Reheat	58	58	58	38	23	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
127B CORRIDOR	PFP Reheat	102	102	102	34	21	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
116 SUSPECT TOILET	PFP Reheat	27	27	27	8	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
CORE SUSPECT AREA		457	457	457	214	123							0.646
117 CORRIDOR	PFP Reheat	44	44	44	14	8	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
120 EVIDENCE PROCESSING RC	PFP Reheat	50	50	50	24	15	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
EVIDENCE PROCESSING		95	95	95	38	23							0.646
121 DUTY AGENT OFFICE	PFP Reheat	82	82	82	25	15	0.600	1.00	0.30	1.00	1.00	1.00	0.646 *
DUTY AGENT OFFICE		82	82	82	25	15							0.646
Secondary - PFP w/ Reheat		941	896	941	377	221							0.646
Default		0	0	0	0	0							0.000
DUMMY		0	0	0	0	0							0.000
001 ENTRY VESTIBULE	Single Fan CV	109	109	109	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		109	109	109	0	0							1.000
002 VESTIBULE WEST	Single Fan CV	49	49	49	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		49	49	49	0	0							1.000
003 VESTIBULE NORTH	Single Fan CV	28	28	28	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		28	28	28	0	0							1.000
CUHs - Vestibules		186	186	186	0	0							1.000
125 ELECTRICAL ROOM	Single Fan CV	207	207	207	0	207	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM		207	207	207	0	207							1.000
FCU - Elec		207	207	207	0	207							1.000
119 EVIDENCE DEPOSITORY RC	Single Fan CV	145	145	145	0	51	0.351	1.00	0.00	1.00	1.00	1.00	0.000
EVIDENCE DEPOSITORY		145	145	145	0	51							1.000

CIC RA 5-9 Adapt-Build Prototype

Project Name: Dataset Name: 5-9\_120817.TRC

By PB

## **Ventilation Calculations for Cooling Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-clg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
FCU - Evid Dep		145	145	145	0	51							1.000
124 TELECOM ROOM	Single Fan CV	35	35	35	0	10	0.274	1.00	0.00	1.00	1.00	1.00	0.000
TELECOM ROOM		35	35	35	0	10							1.000
FCU - TR#1		35	35	35	0	10							1.000
126 MECHANICAL ROOM	Single Fan CV	361	361	361	0	361	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		361	361	361	0	361							1.000
FCU - Mech		361	361	361	0	361							1.000

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
101 VISITOR WAITING AREA	PFP Reheat	57	57	57	57	34	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
VISITOR WAITING		57	57	57	57	34							0.971
102 CORRIDOR	PFP Reheat	13	13	13	13	8	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
103 MEN	PFP Reheat	12	12	12	12	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
104 WOMEN	PFP Reheat	13	13	13	13	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
137 JANITOR	PFP Reheat	3	3	3	3	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
RESTROOMS		41	41	41	41	8							0.971
105 CORRIDOR	PFP Reheat	18	18	18	18	11	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
106 MULTI-PURPOSE LOUNGE	PFP Reheat	156	156	156	156	93	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
127 CORRIDOR	PFP Reheat	16	16	16	16	10	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
MULTI-PURPOSE ROOM		190	190	190	190	114							0.971
105A CORRIDOR	PFP Reheat	14	14	14	14	8	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
127A CORRIDOR	PFP Reheat	16	16	16	16	10	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
136 SHOWER	PFP Reheat	6	6	6	6	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
SHOWER		36	36	36	36	18							0.971
107 SPECIAL AGENT IN CHARGE	PFP Reheat	28	28	28	28	17	0.594	1.00	0.30	1.00	1.00	1.00	0.977
108 LARGE INTERVIEW ROOM	PFP Reheat	90	90	90	90	54	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
SOUTH OFFICES		118	118	118	118	70							0.971
122 TABLE OF ORGANIZATION A	PFP Reheat	101	101	101	101	60	0.594	1.00	0.30	1.00	1.00	1.00	0.977
123 ARMS VAULT	PFP Reheat	17	17	17	17	10	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
TOE STORAGE		118	118	118	118	70							0.971
128 RESIDENT AGENT CRIMINAL	PFP Reheat	22	22	22	22	13	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
129 TEAM CHIEF OFFICE	PFP Reheat	23	23	23	23	14	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
130 INVESTIGATIVE OPS TECH (	PFP Reheat	24	24	24	24	14	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
131 DRUG SUPPRESSION TEAM	PFP Reheat	23	23	23	23	14	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
132 SPECIAL AGENTS OFFICE	PFP Reheat	24	24	24	24	14	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
NORTH OFFICES		117	117	117	117	70							0.971
133 SPECIAL AGENTS OFFICE	PFP Reheat	44	44	44	44	24	0.537	1.00	0.30	1.00	1.00	1.00	1.000
SPECIAL AGENTS OFFICE		44	44	44	44	24							1.000
135 ADMINISTRATIVE/ OPERATION	PFP Reheat	85	85	85	85	51	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
134 RECYCLE CLOSET	PFP Reheat	11	11	11	11	6	0.600	1.00	0.30	1.00	1.00	1.00	0.971 *
ADMIN / OPS ROOM		96	96	96	96	57							0.971
Primary - PFP w/ Reheat		816	816	816	816	466							0.971

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
109 SMALL INTERVIEW ROOM #2	PFP Reheat	32	32	32	32	19	0.591	1.00	0.30	1.00	1.00	1.00	0.994
110 SMALL INTERVIEW ROOM #1	PFP Reheat	31	31	31	31	18	0.586	1.00	0.30	1.00	1.00	1.00	0.999
111 PHOTO ID ROOM	PFP Reheat	13	13	13	13	8	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
118 EVIDENCE CUSTODIAN OFF	PFP Reheat	25	25	25	25	15	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
SOUTHWEST OFFICES		100	100	100	100	59							0.985
112 POLYGRAPH OFFICE	PFP Reheat	28	28	28	28	17	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
113 POLYGRAPH EXAM ROOM	PFP Reheat	28	28	28	28	17	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
114 OBSERVATION ROOM	PFP Reheat	29	29	29	29	17	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
115 SUSPECT WAITING ROOM	PFP Reheat	48	48	48	48	29	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
117A CORRIDOR	PFP Reheat	38	38	38	38	23	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
127B CORRIDOR	PFP Reheat	34	34	34	34	21	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
116 SUSPECT TOILET	PFP Reheat	8	8	10	8	0	0.000	1.00	0.30	1.00	1.00	1.00	1.000
CORE SUSPECT AREA		214	214	216	214	123							0.985
117 CORRIDOR	PFP Reheat	14	14	14	14	8	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
120 EVIDENCE PROCESSING RC	PFP Reheat	24	24	24	24	15	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
EVIDENCE PROCESSING		38	38	38	38	23							0.985
121 DUTY AGENT OFFICE	PFP Reheat	25	25	25	25	15	0.600	1.00	0.30	1.00	1.00	1.00	0.985 *
DUTY AGENT OFFICE		25	25	25	25	15							0.985
Secondary - PFP w/ Reheat		377	377	379	377	221							0.985
Default		0	0	0	0	0							0.000
DUMMY		0	0	0	0	0							0.000
001 ENTRY VESTIBULE	Single Fan CV	109	109	109	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ENTRY VESTIBULE		109	109	109	0	0							1.000
002 VESTIBULE WEST	Single Fan CV	49	49	49	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE WEST		49	49	49	0	0							1.000
003 VESTIBULE NORTH	Single Fan CV	28	28	28	0	0	0.000	1.00	0.00	1.00	1.00	1.00	1.000 *
VESTIBULE NORTH		28	28	28	0	0							1.000
CUHs - Vestibules		186	186	186	0	0							1.000
125 ELECTRICAL ROOM	Single Fan CV	207	207	207	0	207	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
ELECTRICAL ROOM		207	207	207	0	207							1.000
FCU - Elec		207	207	207	0	207							1.000
119 EVIDENCE DEPOSITORY RO	Single Fan CV	145	145	145	0	51	0.351	1.00	0.00	1.00	1.00	1.00	0.000
EVIDENCE DEPOSITORY		145	145	145	0	51							1.000

Project Name: CIC RA 5-9 Adapt-Build Prototype

By PB

## **Ventilation Calculations for Heating Design**

		Vpz	Vfan	Vdz	Vpz-min	Voz-htg	Zd	Ep	Er	Fa	Fb	Fc	Evz
System Zone Room	Box Type	cfm	cfm	cfm	cfm	cfm							
Alternative 3													
FCU - Evid Dep		145	145	145	0	51							1.000
124 TELECOM ROOM	Single Fan CV	35	35	35	0	10	0.274	1.00	0.00	1.00	1.00	1.00	0.000
TELECOM ROOM		35	35	35	0	10							1.000
FCU - TR#1		35	35	35	0	10							1.000
126 MECHANICAL ROOM	Single Fan CV	361	361	361	0	361	1.000	1.00	0.00	1.00	1.00	1.00	1.000 *
MECHANICAL ROOM		361	361	361	0	361							1.000
FCU - Mech		361	361	361	0	361							1.000

## **MONTHLY ENERGY CONSUMPTION**

By PB

----- Monthly Energy Consumption ------

Utility		Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Total
Alternative: 1		ASHF	RAE 90_1-	2007 Base	line									
Electric														
On-Pk Cons. (	kWh)	7,432	7,242	8,305	8,836	13,222	15,201	17,759	16,354	13,686	10,437	7,898	7,656	134,027
On-Pk Demand	(kW)	22	31	33	31	46	51	56	55	50	40	37	20	56
Gas														
On-Pk Cons. (the	erms)	254	172	100	5	0	0	0	0	0	10	76	353	969
On-Pk Demand (therr	ms/hr)	3	3	3	1	0	0	0	0	0	2	3	3	3
Energy C	onsump	otion			E	nvironmer	ntal Impact	Analysis						
Building	65,852	Btu/(ft2-yea	ar)		CO	2	No Data Ava	lable						
Source	175,148	Btu/(ft2-yea	ar)		SO		No Data Ava							
					NO	X	No Data Ava	lable						
Floor Area	8,419	ft2												

Project Name: CIC RA 5-9 Adapt-Build Prototype

## **MONTHLY ENERGY CONSUMPTION**

By PB

----- Monthly Energy Consumption ------

Utility		Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Total
Alternative: 2		Self	Contained	VAV Units	w/ Clg To	wer								
Electric														
On-F	k Cons. (kWh)	8,723	8,275	9,488	9,474	11,295	12,024	13,186	12,692	11,346	10,371	9,124	8,997	124,996
On-P	k Demand (kW)	25	26	26	27	32	33	36	33	33	30	29	27	36
Gas														
On-Pk	Cons. (therms)	60	26	17	6	0	0	3	3	6	13	23	58	216
On-Pk Dem	and (therms/hr)	1	0	0	0	0	0	0	0	0	0	0	1	1
Water														
(	Cons. (1000gal)	2	3	4	5	10	12	14	13	10	6	3	1	82
Е	nergy Consum	ption			E	nvironme	ntal Impact	Analysis						
Building	53,239	Btu/(ft2-ye	ar)		СО	2	No Data Avai	lable						
Source	154,739	Btu/(ft2-ye	ar)		SO	2	No Data Avai							
					NO	X	No Data Avai	lable						
Floor Area	8,419	9 ft2												

Project Name: CIC RA 5-9 Adapt-Build Prototype

## **MONTHLY ENERGY CONSUMPTION**

By PB

----- Monthly Energy Consumption ------

Utility		Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Total
Alternative: 3		VAV	Fan Coil U	Inits w/ Aiı	Cooled C	hiller								
Electric														
On-Pk Cons.	(kWh)	8,253	8,334	9,683	10,422	13,541	14,460	15,948	15,304	13,686	11,645	9,308	8,265	138,851
On-Pk Demar	nd (kW)	27	29	29	33	38	40	43	39	39	38	37	31	43
Gas														
On-Pk Cons. (t	therms)	38	13	7	3	0	0	3	3	6	8	11	33	126
On-Pk Demand (the	erms/hr)	1	1	0	0	0	0	0	0	0	0	0	1	1
Energy	Consum	ption			E	invironme	ntal Impact	Analysis						
Building	57,784	Btu/(ft2-ye	ar)		СО	2	No Data Ava	lable						
Source	170,464	Btu/(ft2-ye	ar)		SO	2	No Data Ava							
					NO	X	No Data Ava	lable						
Floor Area	8,419	ft2												

Project Name: CIC RA 5-9 Adapt-Build Prototype

#### **ENERGY CONSUMPTION SUMMARY**

By PB

	Elect Cons. (kWh)	Gas Cons. (kBtu)	% of Total Building Energy	Total Building Energy (kBtu/yr)	Total Source Energy* (kBtu/yr)
Alternative 1					
Primary heating					
Primary heating		99,438	17.9 %	99,438	104,671
Other Htg Accessories			0.0 %	0	0
Heating Subtotal		99,438	17.9 %	99,438	104,671
Primary cooling					
Cooling Compressor	40,142		24.7 %	137,004	411,052
Tower/Cond Fans	2,814		1.7 %	9,604	28,814
Condenser Pump			0.0 %	0	0
Other Clg Accessories	343		0.2 %	1,170	3,511
Cooling Subtotal	43,299		<b>26.6</b> %	147,778	443,378
Auxiliary					
Supply Fans	23,770		14.6 %	81,126	243,401
Pumps			0.0 %	0	0
Stand-alone Base Utilities			0.0 %	0	0
Aux Subtotal	23,770		14.6 %	81,126	243,401
Lighting					
Lighting	38,244		23.5 %	130,526	391,618
Receptacle					
Receptacles	28,176		17.3 %	96,165	288,522
Cogeneration					
Cogeneration			0.0 %	0	0
Totals					
Totals**	133,488	99,438	100.0 %	555,032	1,471,591

Project Name: CIC RA 5-9 Adapt-Build Prototype

<sup>\*</sup> Note: Resource Utilization factors are included in the Total Source Energy value.

<sup>\*\*</sup> Note: This report can display a maximum of 7 utilities. If additional utilities are used, they will be included in the total.

#### **ENERGY CONSUMPTION SUMMARY**

By PB

	Elect Cons. (kWh)	Gas Cons. (kBtu)	Water Cons. (1000 gals)	% of Total Building Energy	Total Building Energy (kBtu/yr)	Total Source Energy* (kBtu/yr)
Alternative 2						
Primary heating						
Primary heating		21,581		4.8 %	21,581	22,717
Other Htg Accessories	2,186			1.7 %	7,459	22,380
Heating Subtotal	2,186	21,581		6.5 %	29,041	45,097
Primary cooling						
Cooling Compressor	22,470			17.1 %	76,692	230,098
Tower/Cond Fans	3,462		82	2.6 %	11,815	35,450
Condenser Pump				0.0 %	0	0
Other Clg Accessories	5,639			4.3 %	19,247	57,747
Cooling Subtotal	31,572		82	<b>24.0</b> %	107,754	323,294
Auxiliary						
Supply Fans	4,409			3.4 %	15,047	45,147
Pumps				0.0 %	0	0
Stand-alone Base Utilities	30,036			22.9 %	102,512	307,568
Aux Subtotal	34,445			26.2 %	117,560	352,715
Lighting						
Lighting	28,618			21.8 %	97,673	293,050
Receptacle						
Receptacles	28,176			21.5 %	96,165	288,522
Cogeneration						
Cogeneration				0.0 %	0	0
Totals						
Totals**	124,996	21,581	82	100.0 %	448,192	1,302,678

Project Name: CIC RA 5-9 Adapt-Build Prototype

<sup>\*</sup> Note: Resource Utilization factors are included in the Total Source Energy value.

<sup>\*\*</sup> Note: This report can display a maximum of 7 utilities. If additional utilities are used, they will be included in the total.

#### **ENERGY CONSUMPTION SUMMARY**

By PB

	Elect Cons. (kWh)	Gas Cons. (kBtu)	% of Total Building Energy	Total Building Energy (kBtu/yr)	Total Source Energy* (kBtu/yr)
Alternative 3					
Primary heating					
Primary heating		12,561	2.6 %	12,561	13,223
Other Htg Accessories	886		0.6 %	3,025	9,075
Heating Subtotal	886	12,561	3.2 %	15,586	22,297
Primary cooling					
Cooling Compressor	32,023		22.5 %	109,294	327,915
Tower/Cond Fans	2,072		1.5 %	7,071	21,215
Condenser Pump			0.0 %	0	0
Other Clg Accessories	1,614		1.1 %	5,509	16,529
Cooling Subtotal	35,709		<b>25.1</b> %	121,874	365,659
Auxiliary					
Supply Fans	4,127		2.9 %	14,086	42,263
Pumps	11,299		7.9 %	38,563	115,700
Stand-alone Base Utilities	30,036		21.1 %	102,512	307,568
Aux Subtotal	45,462		31.9 %	155,162	465,531
Lighting					
Lighting	28,618		20.1 %	97,673	293,050
Receptacle					
Receptacles	28,176		19.8 %	96,165	288,522
Cogeneration					
Cogeneration			0.0 %	0	0
Totals					
Totals**	138,851	12,561	100.0 %	486,460	1,435,060

Project Name: CIC RA 5-9 Adapt-Build Prototype

<sup>\*</sup> Note: Resource Utilization factors are included in the Total Source Energy value.

<sup>\*\*</sup> Note: This report can display a maximum of 7 utilities. If additional utilities are used, they will be included in the total.

Location
Building owner
Program user
Company
Comments

By PBHA

Dataset name C:\Users\agebrehana\Ft Stewart.trc

Calculation time 03:44 PM on 06/05/2012

TRACE® 700 version 6.2.8

Location Fort Stewart, Georgia Latitude 32.0 deg Longitude 81.5 deg Time Zone 5 Elevation 88 ft Barometric pressure 29.8 in. Hg

Air density

O.0758

Density-specific heat product
Latent heat factor

Enthalpy factor

O.0758

Btu/lb·°F

Btu/h·cfm·°F

Btu/h·cfm·°F

Btu/min/h·cu ft

Ib·min/h·cu ft

Summer design dry bulb 93 °F Summer design wet bulb 79 °F Winter design dry bulb 26 °F

Summer clearness number

Winter clearness number

Winter clearness number

Summer ground reflectance

Winter ground reflectance

0.20

Carbon Dioxide Level 400 ppm

Design simulation period January - December

Cooling load methodology TETD-TA1
Heating load methodology UATD





# System Checksums By PBHA

System - 001 Ventilation and Heating

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR		:	Mo/Hr: OADB:			Mo/Hr: He OADB: 26	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	0	0	0 :	0	0	Roof Cond	-1,959	-1,959	15.19
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0	Glass/Door Cond	-1,175	-1,175	9.11
Wall Cond	0	0	0	0 ;	0	0 ;		-2,849	-2,849	22.10
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0	0	Floor	-2,376	-2,376	18.43
Adjacent Floor	0	0	0	0	0	0	Adjacent Floor	0	0	0
Infiltration	0		0	0 ;	0	0	Infiltration	-2,790	-2,790	21.64
Sub Total ==>	0	0	0	0 ;	0	0	Sub Total ==>	-11,148	-11,148	86.47
Internal Loads							Internal Loads			
Lights	0	0	0	0 :	0	0	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	0	0	0	0	0	0	Sub Total ==>	0	0	0.00
Ceiling Load	0	0	0	0	0	0	Ceiling Load	0	0	0.00
Ventilation Load	0	0	0	0:	0	- ,	Ventilation Load	0	-1,744	13.53
Adj Air Trans Heat	0	Ü	0	0 :	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0 :	· ·		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	-	0	0.00
Exhaust Heat	Ü	0	Ö	o :	ŭ		OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		0	0.00
Duct Heat Pkup		Õ	Ö	0					· ·	2.30
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 :		:	Supply Air Leakage		0	0.00
Grand Total ==>	0	0	0	100.00	0	100.00	Grand Total ==>	-11,148	-12,892	100.00

TEMPE	RATURE	s
	Cooling	Heating
SADB	0.0	125.0
Ra Plenum	0.0	70.0
Return	0.0	70.0
Ret/OA	0.0	61.4
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS					
	Cooling	Heating			
Diffuser	0	182			
Terminal	0	182			
Main Fan	0	182			
Sec Fan	0	0			
Nom Vent	0	36			
AHU Vent	0	36			
Infil	0	57			
MinStop/Rh	0	0			
Return	0	239			
Exhaust	0	93			
Rm Exh	0	0			
Auxiliary	0	0			
Leakage Dwn	0	0			
Leakage Ups	0	0			

ENGINEERING CKS				
	Cooling	Heating		
% OA	0.0	19.6		
cfm/ft²	0.00	0.26		
cfm/ton	0.00			
ft²/ton	0.00			
Btu/hr·ft²	0.00	-18.08		
No. People	0			

COOLING COIL SELECTION										
	<b>Total Capacity</b>		Sens Cap.			Enter DB/WB/HR		Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.0	0.0								

AREAS Gross Total Glass ft² (%)				
Floor Part	713 0		(,,,	
Int Door ExFIr	0 108			
Roof Wall	713 1,853	0 0	0 0	
Ext Door	131	0	0	

HEATING COIL SELECTION							
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F			
Main Htg Aux Htg	-12.9 0.0	182 0	61.4 0.0	125.0 0.0			
Preheat	0.0	0	0.0	0.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-12.9	Ü	0.0	0.0			

Project Name: Ft Stewart, Ga Dataset Name: Ft Stewart.trc

## APPENDIX F ANSI/ASHRAE STANDARD 189.1 COMPLIANCE

	Indoor Environmental Quality (IEQ) Compliance Documentation – Mandatory			
Proj	Project Name: U.S. Army Criminal Investigations CommandRA 5-9			
Proj	ect A	Address:	Date: 12 September 2012	
Des	igne	r of Record:	Telephone:	
Con	tact	Person:	Telephone:	
City	:			
		Mandatory Provisions		
Complies	Not applicable	Requirement	Document Reference	
		Indoor Air Quality  89.3.1. The building complies with Section 4 of ANSI/ASHRAE Standard 63.1. Provide		
╵		§8.3.1: The building complies with Section 4 of ANSI/ASHRAE Standard 62.1. Provide ANSI/ASHRAE Standard 62.1-2007 Appendix H checklist to document compliance with		
	_	Section 4.3 requirements.		
		§8.3.1: The building complies with Section 5 of ANSI/ASHRAE Standard 62.1 except as noted below. When a requirement is provided below, it supersedes the requirement in ANSI/ASHRAE Standard 62.1. Provide ANSI/ASHRAE Standard 62.1-2007 Appendix H checklist to document Section 5.2.3 requirements.		
		§8.3.1.3a1: The particulate matter filters or air cleaners have a MERV of not less than 8, and comply with and are provided where required in Section 5.9 of ANSI/ASHRAE Standard 62.1. (Include document reference for specifications.)	Not provided at this level of detail.	
		§8.3.1.4a: Smoking is not allowed inside the building.	Sheet A-703; Sign is provided, but location is not indicated at this level of detail.	
		§8.3.1.4a: Signs stating that smoking is not allowed inside the building have been posted within 10 ft (3 m) of each building entrance.	Sheet A-703; Sign is provided, but location is not indicated at this level of detail.	
		§8.3.1.4b: Any exterior designated smoking areas are located a minimum of 25 ft (7.5 m) away from building entrances, outdoor air intakes, and operable windows.	Not provided at this level of detail.	
		§8.3.1: The building complies with Section 6 of ANSI/ASHRAE Standard 62.1 except as noted below. When a requirement is provided below, it supersedes the requirement in ANSI/ASHRAE Standard 62.1. Provide ANSI/ASHRAE Standard 62.1-2007 Appendix H checklist to document Section 6.2 compliance.		
		§8.3.1.1a: The Ventilation Rate Procedure of ANSI/ASHRAE Standard 62.1 was used to design each mechanical ventilation system in the building.	Design Narrative; Appendix E: Energy Modeling; ASHRAE Standard 62.1-2004/2007.	
		§8.3.1.3a1: (PM <sub>10</sub> ) The building is located in an area designated as the following (Attainment or Non-attainment) under the National Ambient Air Quality Standards for PM <sub>10</sub> , as determined by the AHJ:  Status (If 8.3.1.3a1 applies, PM <sub>10</sub> ):  Attainment  Non-attainment  Particulate matter filters and air cleaning devices with MERVs of not less than 8 have been provided to clean the air at any location prior to its introduction to occupied space, as required in Section 6.2.1.1 of ANSI/ASHRAE Standard 62.1. (Include document reference for specifications.)	Source of Information	
		§8.3.1.3a2: (PM2.5) The building is located in an area designated as the following under the National Ambient Air Quality Standards for PM2.5, as determined by the AHJ:  Status (If 8.3.1.3a2 applies, PM2.5):  Attainment  Non-attainment  Particulate matter filters and air-cleaning devices with MERVs of not less than 13 have been provided to clean the air at any location prior to its introduction to occupied space, as required in Section 6.2.1.1 of ANSI/ASHRAE Standard 62.1. (Include document reference for specifications.)	Source of Information	

		Indoor Environmental Quality (IEQ) Compliance Do	cumentation – Mandatory
Proj	ect l	Name: U.S. Army Criminal Investigations CommandRA 5-9	
		Address:	Date: 12 September 2012
	_	r of Record:	Telephone:
		Person:	Telephone:
City	:		
		Mandatory Provisions	
Complies	Not applicable	Requirement	Document Reference
§8.3	3.1:	Indoor Air Quality Cont.	
		§8.3.1.3b: (Ozone) The building is located in an area designated as the following under the National Ambient Air Quality Standards for ozone as determined by the AHJ:  Status (If 8.3.1.3b applies, Ozone):  Attainment  Non-attainment  Air cleaning devices with a volumetric ozone removal efficiencies of not less than 40% have been provided to clean the air at any location prior to its introduction to occupied space, as required in Section 6.2.1.1 of ANSI/ASHRAE Standard 62.1. (Include document reference for specifications.)	Source of Information
		§8.3.1.3c: All filter frames, air cleaner racks, access doors, and air cleaner cartridges are sealed. (Include document reference for specifications.)	Not provided at this level of detail.
		§8.3.1: The building complies with Section 7 of ANSI/ASHRAE Standard 62.1.	
		§8.3.1.2.1: A permanently mounted, direct total outdoor airflow measurement device has been provided that is capable of measuring the system outdoor airflow rate within an accuracy of ±15% of the minimum outdoor airflow rate. It is also capable of sending an alarm to the building operator or a signal to a building central monitoring system when flow rates are not in compliance.	Not provided at this level of detail.
		<ul> <li>Exception §8.3.1.2.1: Constant volume air supply systems that use a damper position feedback system are not required to have a direct total outdoor airflow measurement device.</li> <li>West-facing façade shading PF: 0.62</li> </ul>	A-604; vestibules indicate a walk-off-mat system with an absorption and finishing surface in the entry vestibules. Scraper surfaces shall be applied outside the first entry door per ASHRAE 189.1-2009, 8.3.1.5.1 Scraper Surface requirements.
		§8.3.1.5: Each scraper surface, absorption surface, and finishing surface is as wide as the entry opening, and has a minimum length of 10 ft, measured in the primary direction of travel.  Exceptions §8.3.1.5:  1) Entrances to individual dwelling units.  2) Length of entry mat surfaces is allowed to be reduced due to a barrier, such as a counter, artition, or wall, or local regulations prohibiting the use of scraper surfaces outside the entry. In this case entry mat surfaces have a minimum length of 3 ft (1 m) of indoor	Not provided at this level of detail.
		surface, with a minimum combined length of 6 ft (2 m).	
		2) South-facing façade shading PF: 0.62	Not provided at this level of detail.
		§8.3.1.5.1b: The scraper surface is either immediately outside or inside the entry.	Not provided at this level of detail.
		§8.3.1.5.1c: The scraper surface is a minimum of 3 ft (1 m) long.	Not provided at this level of detail.
		3) East-facing façade shading PF: 0.62	Not provided at this level of detail.
		§8.3.1.5.2a: The absorption surface is the second surface stepped on when entering the	Not provided at this level of detail.

	Indoor Environmental Quality (IEQ) Compliance Documentation – Mandatory				
Proj	Project Name: U.S. Army Criminal Investigations CommandRA 5-9				
Proj	Project Address: Date: 12 September 2012				
Des	igne	r of Record:	Telephone:		
Con	tact	Person:	Telephone:		
City	:				
		Mandatory Provisions			
Complies	Not applicable	Requirement	Document Reference		
0					
	_	§8.3.1.5.2b: The absorption surface is a minimum of 3 ft (1 m) long, and made from materials that can perform both a scraping action and a moisture wicking action.	Not provided at this level of detail.		
		§8.3.1.5.3a: The finishing surface is the third surface stepped on when entering the building.	Not provided at this level of detail.		
	_	§8.3.1.5.3b: The finishing surface is a minimum of 4 ft (1.2 m) long, and made from material that will both capture and hold any remaining particles or moisture.	Not provided at this level of detail.		

		ndoor Environmental Quality (IEQ) Compliance Do	cumentation - Mandatory
		Name: U.S. Army Criminal Investigations CommandRA 5-9	
_		Address:	Date: 12 September 2012
Des	igne	r of Record:	Telephone:
Contact Person: Telephone:			Telephone:
City			
		Mandatory Provisions	
	le		
"	Not applicable		
olies	ppli		
Complies	ot a	Doggiroment	Decument Reference
ŭ	Ž	Requirement	Document Reference
§8.3	.2:	Thermal Environmental Conditions for Human Occupancy	
J		§8.3.2: The building has been designed in compliance with ANSI/ASHRAE Standard 55,	
		Sections 6.1, "Design," and 6.2, "Documentation of ANSI/ASHRAE Standard 55." Provide	
		ANSI/ASHRAE Standard 55 compliance form (Addendum H) to document compliance with section 6.2.	
		Exception §8.3.2: Spaces with special requirements for processes, activities, or	
		contents that require a thermal environment outside that which humans find thermally	
		acceptable, such as food storage, natatoriums, shower rooms, saunas, and drying rooms.	
§8.3	.3:	Acoustical Control	
		§8.3.3.1: Wall and roof-ceiling assemblies that are part of the building envelope have a	
		composite OITC rating of 40 or greater or a composite STC rating of 50 or greater for any of the following conditions:	
		a. Buildings within 1000 ft (300 m) of expressways.	
		b. Buildings within 5 mi (8 km) of airports serving more than 10,000 commercial jets per year.	
		c. Where yearly average day-night average sound levels at the property line exceed 65 decibels	
		Composite STC or OITC rating of wall and roof-ceiling assemblies that are part of the	
		building envelope:	
	Ц	§8.3.3.1: Fenestration that is part of the building envelope shall have an OITC or STC rating of 30 or greater for any of the following conditions:	
		a. Buildings within 1000 ft (300 m) of expressways.	
		b. Buildings within 5 mi (8 km) of airports serving more than 10,000 commercial jets per year.	
		c. Where yearly average day-night average sound levels at the property line exceed 65 decibels.	
		aconsolo.	
		Composite STC or OITC rating of fenestration that are part of the building envelope:	
		☐ Exception §8.3.3.1: Buildings that may have to adhere to functional and operational	
		requirements such as factories, stadiums, storage, enclosed parking structure, and utility	
$\checkmark$		§8.3.3.2: Interior wall and floor/ceiling assemblies separating interior rooms and spaces have	Wall types are labeled on A-101. Wall type sound
		been designed in accordance with all of the following:  a. Wall and floor/ceiling assemblies separating adjacent dwelling units, dwelling units and	ratings are listed on A-601.
		public spaces, adjacent tenant spaces, tenant spaces and public places, and adjacent	
		classrooms have a composite STC rating of 50 or greater.	
		b. Wall and floor/ceiling assemblies separating hotel rooms, motel rooms, and patient rooms in nursing homes and hospitals have a composite STC rating of 45 or greater.	
		c. Wall and floor/ceiling assemblies separating classrooms from restrooms and showers have	
		a composite STC rating of 53 or greater.	
		d. Wall and floor/ceiling assemblies separating classrooms from music rooms, mechanical rooms, cafeteria, gymnasiums, and indoor swimming pools have a composite STC rating of 60	
		or greater.	
$\checkmark$		Composite STC rating of wall and floor/ceiling assemblies separating adjacent dwelling	Wall types are labeled on A-101. Wall type sound
		units, dwelling units and public spaces, adjacent tenant spaces, tenant spaces and public places, and adjacent classrooms: (Attach additional table if necessary.)	ratings are listed on A-601.

	Indoor Environmental Quality (IEQ) Compliance Documentation – Mandatory					
Proj	Project Name: U.S. Army Criminal Investigations CommandRA 5-9					
Proj	ect A	address:	Date: 12 September 2012			
Des	igneı	of Record:	Telephone:			
Con	tact	Person:	Telephone:			
City	:					
		Mandatory Provisions				
Complies	Not applicable	Requirement	Document Reference			
	<b>√</b>	Composite STC rating of wall and floor/ceiling assemblies separating hotel rooms, motel rooms, and patient rooms in nursing homes and hospitals: (Attach additional table if necessary.)				
✓		Composite STC rating of wall and floor-ceiling assemblies separating classrooms from restrooms and showers: (Attach additional table if necessary.)	Wall types are labeled on A-101. Wall type sound ratings are listed on A-601.			
✓		Composite STC rating of wall and floor/ceiling assemblies separating classrooms from music rooms, mechanical rooms, cafeteria, gymnasiums, and indoor swimming pools: (Attach additional table if necessary.)	Wall types are labeled on A-101. Wall type sound ratings are listed on A-601.			

Indoor Environmental Quality (IEQ) Compliance Documentation — Mandatory  Project Name: U.S. Army Criminal Investigations Command-RA 5-9  Project Address:  Date: 12 September 2012  Telephone:  Contact Person:  City:  Mandatory Provisions  Mandatory Provisions  Mandatory Provisions  Mandatory Provisions  Requirement  Document Reference  \$8.3.3: Acoustical Control Cont.  S8.3.3: OITC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E332. STC values for assemblies and components have been determined in accordance with ASTM E30 and ASTM E413.  \$8.3.4: Daylighting by Toplighting  S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 Wm² (5 db wm²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  S8.3.4: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/ft2) are in the daylight area.
Project Address: Designer of Record: Telephone: Contact Person: Telephone: City:  Mandatory Provisions  Requirement Document Reference  \$8.3.3: Acoustical Control Cont.
Designer of Record:  Contact Person:  Telephone:  Telephone:  Telephone:  Telephone:  Telephone:  Telephone:  Telephone:  Telephone:  Mandatory Provisions  Mandatory Provisions  Requirement  Document Reference  \$8.3.3: Acoustical Control Cont.  \$8.3.3: OTIT values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E30 and ASTM E413.  \$8.3.4: Daylighting by Toplighting  \$8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1 Disuldings in climate zones 7 or 8.  2 Auditional, theaters, museums, places of worship, and refrigerated warehouses.  \$8.3.4: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
Contact Person:  City:  Mandatory Provisions  Mandatory Provisions  Requirement  Document Reference  \$8.3.3: Acoustical Control Cont.  \$8.3.3: Acoustical Control Cont.  \$8.3.3: OTC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E1332. STC value
Sestion   Ses
Sa.3.3: Acoustical Control Cont.   Sa.3.3: OITC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E332. STC values for assemblies and components have been determined in accordance with ASTM E90 and ASTM E413.    Sa.3.4: Daylighting by Toplighting   Sa.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 tf (2000 m²) and directly under a roof with finished ceilling heights greater than 15 ft (4m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.    Exceptions §8.3.4:
Requirement   Document Reference
S8.3.3: OITC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E90 and ASTM E413.  S8.3.4: Daylighting by Toplighting  S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  S8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
S8.3.3: OITC values for assemblies and components have been determined in accordance with ASTM E1332. STC values for assemblies and components have been determined in accordance with ASTM E90 and ASTM E413.  S8.3.4: Daylighting by Toplighting  S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  S8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
§8.3.4: Daylighting by Toplighting
<ul> <li>S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.</li> <li>Exceptions §8.3.4:</li> <li>□ 1) Buildings in climate zones 7 or 8.</li> <li>□ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.</li> <li>□ √ \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.</li> </ul>
<ul> <li>S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.</li> <li>Exceptions §8.3.4:</li> <li>□ 1) Buildings in climate zones 7 or 8.</li> <li>□ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.</li> <li>□ √ \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.</li> </ul>
<ul> <li>S8.3.4: In buildings three stories or less above grade, conditioned or unconditioned enclosed spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.</li> <li>Exceptions §8.3.4:</li> <li>□ 1) Buildings in climate zones 7 or 8.</li> <li>□ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.</li> <li>□ √ \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.</li> </ul>
spaces that are greater than 20,000 ft² (2000 m²) and directly under a roof with finished ceiling heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  □ 1) Buildings in climate zones 7 or 8.  □ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  □ \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
heights greater than 15 ft (4 m), and that have a lighting power allowance for general lighting equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
equal to or greater than 0.5 W/ft² (5.5 W/m²), there is a minimum fenestration area providing daylighting by toplighting for large enclosed spaces.  Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m²) are in the daylight area.
Exceptions §8.3.4:  1) Buildings in climate zones 7 or 8.  2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  \$8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m2) are in the daylight area.
□ 1) Buildings in climate zones 7 or 8. □ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  ✓ §8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m2) are in the daylight area.
□ 2) Auditoria, theaters, museums, places of worship, and refrigerated warehouses.  §8.3.4.1: In buildings specified in §8.3.4, a minimum of 50% of the floor area directly under a roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m2) are in the daylight area.
Standard St
roof in spaces with a lighting power density or lighting power allowance greater than 0.5 W/ft2 (5.5 W/m2) are in the daylight area.
(5.5 W/m2) are in the daylight area.
See 2.4.1: In buildings specified in See 2.4. areas that are doublit have a minimum toplighting area
Second to the buildings specified in Second that are double have a minimum toplighting area.
No. 1/2 Sec. 2.4.1: In buildings specified in Sec. 2.4. areas that are doublit have a minimum toplighting area.
No. 2 A 1: In buildings specified in \$9.3.4 areas that are double have a minimum toplighting area
to daylight area ratio as shown in Table 8.3.4.1. For purposes of compliance with Table 8.3.4.1, the greater of the space lighting power density and the space lighting power allowance
has been used  √ §8.3.4.2: In buildings specified in §8.3.4, skylights used to comply with Section 8.3.4.1 have a
glazing material or diffuser that has a measured haze value greater than 90%, tested
according to ASTM D1003 (notwithstanding its scope) or other test method approved by the
Exceptions §8.3.4.2:  1) Skylights with a measured haze value less than or equal to 90% whose combined area
does not exceed 5% of the total skylight area.
<ul><li>2) Tubular daylighting devices with a diffuser.</li></ul>
□ 3) Skylights that are capable of preventing direct sunlight from entering the occupied space below the well during occupied hours. This shall be accomplished using one or more
of the following:
a. orientation
b. automated shading or diffusing devices c. diffusers
d. fixed internal or external baffles
4) Skylights in airline terminals, convention centers, and shopping malls.
§8.3.5: Isolation of the Building from Pollutants in Soil

		Indoor Environmental Quality (IEQ) Compliance Do	cumentation – Mandatory
Pro	ject l	Name: U.S. Army Criminal Investigations CommandRA 5-9	
Pro	ject /	Address:	Date: 12 September 2012
Des	signe	or of Record:	Telephone:
Cor	ntact	Person:	Telephone:
City	<b>/</b> :		
		Mandatory Provisions	
Complies	Not applicable	Requirement	Document Reference
		§8.3.5: Building projects that include construction or expansion of a ground-level foundation and that are located on brownfield sites or in "zone 1" counties for radon (those identified to have a significant probability of radon concentrations higher than 4 picocuries/liter on the EPA map of radon zones) have a soil gas retarding system installed between the newly constructed space and the soil.  Status (If 8.3.5 applies, Radon):  Brownfield site  Building has a soil gas retarding system installed between the newly constructed space and the soil. (Include document reference for specifications.)  Radon county in zone 1  Building has a soil gas retarding system installed between the newly constructed space and the soil. (Include document reference for specifications.)	Source of Information
		The proposed and baseline buildings comply with the mandatory requirements of ANSI/ASHRAE/USGBC/IES Standard 189.1-2009. Individual certifying authenticity of the data provided in this analysis:	
		Signature: Date:	
		Printed Name: License/Registration #:	
		Company Name:	

		Name: U.S. Army Criminal Investigations CommandRA 5-9	<u> </u>
		Address:	Date: 12 September 2012
	<u> </u>	r of Record:	Telephone:
		Person:	Telephone:
City	:		
		Prescriptive Option	T
Complies	Not applicable	Requirement	Document Reference
§8.4	l.1:	Daylighting by Sidelighting	
<u>√</u>		§8.4.1.1a: For office spaces and classrooms, all north-, south-, and east-facing facades have a minimum sidelighting effective aperture as prescribed in Table 8.4.1.1.	
		North-side facade sidelighting effective aperture: 0.167	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1a Part 1/2
		South-side façade sidelighting effective aperture: 0.232	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1a Part 1/2
./		East-side facade sidelighting effective aperture: 0.210  §8.4.1.1b: For office spaces and classrooms, the combined width of the primary sidelighted	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1a Part 1/2
V		areas is at least 75% of the length of the facade wall.	
		North-side combined width of the primary sidelighted areas: 48'-0"	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1b Part 1
		North-side length of the wall: 66'-3 5/8"	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1b Part 2
		South-side combined width of the primary sidelighted areas: 31'-3 7/8"  South-side length of the wall: 41'-3 1/4"	173133A_CIC_Det5-9_Architectural.rvt, Schedule: ASHRAE 189.1-2009, 8.4.1.1b Part 1 173133A_CIC_Det5-9_Architectural.rvt, Schedule:
		East-side combined width of the primary sidelighted areas: 24'-0"	ASHRAE 189.1-2009, 8.4.1.1b Part 2 173133A_CIC_Det5-9_Architectural.rvt, Schedule:
		East-side length of the wall: 32'-10 3/4"	ASHRAE 189.1-2009, 8.4.1.1b Part 1 173133A_CIC_Det5-9_Architectural.rvt, Schedule:
		§8.4.1.1c: Opaque interior surfaces of office spaces and classrooms in daylight areas have visible light reflectances greater than or equal to 80% for ceilings and 70% for partitions higher than 60 in. (1.54 m) in daylight areas.	ASHRAE 189.1-2009, 8.4.1.1b Part 2
		Visible light reflectances of opaque interior ceiling surfaces:	Not provided at this level of detail.
		Visible light reflectances of opaque interior partitions higher than 60 in. (1.54 m):	Not provided at this level of detail.
		Exceptions §8.4.1.1:  1) Spaces with programming that requires dark conditions (e.g., photographic processing).  2) Spaces with toplighting in compliance with Section 8.3.4.  3) Daylight zones where the height of existing adjacent structures above the window is at least twice the distance between the window and the adjacent structures, measured from the top of the glazing.	
√		§8.4.1.2: Each west-, south-, and east-facing façade of office spaces, has been designed with a shading projection whose PF is not less than 0.5.	
		1 ) West-facing façade shading PF: 0.62	Design Analysis, Appendix F: ANSI/ASHRAE Standard 189.1 Compliance
		1) West-facing facade shading interior PE:	
		West-facing façade shading interior PF:     South-facing façade shading PF: 0.62	Design Analysis, Appendix F: ANSI/ASHRAE Standard 189.1 Compliance
		or	103.1 Compliance
		South-facing façade shading interior PF:	

	l	ndoor Environmental Quality (IEQ) Compliance	<b>Documentation – Prescriptive</b>
Proj	ect N	Name: U.S. Army Criminal Investigations CommandRA 5-9	<u> </u>
Proj	ect A	Address:	Date: 12 September 2012
Des	igne	r of Record:	Telephone:
Con	tact	Person:	Telephone:
City			
		Prescriptive Option	
Complies	Not applicable	Requirement	Document Reference
		3) East-facing façade shading PF: 0.62  or  3) East-facing façade shading interior PF:	Design Analysis, Appendix F: ANSI/ASHRAE Standard 189.1 Compliance
<b>√</b>		§8.4.1.2a and b: Office spaces use one or more of the following shading devices:  a. Louvers, sun shades, light shelves, and any other permanent device.  b. Building self-shading through roof overhangs or recessed windows	

D:	Indoor Environmental Quality (IEQ) Compliance Documentation – Prescriptive				
		Jame: U.S. Army Criminal Investigations CommandRA 5-9	Date: 12 September 2012		
		r of Record:	Telephone:		
		Person:	Telephone:		
City:		i etsoti.			
Oity.		Prescriptive Option			
	Φ	Trocompanie opiion			
Complies	Not applicable	Requirement	Document Reference		
_	.1:	Daylighting by Sidelighting Cont.			
	<b>√</b>	§8.4.1.2a: A vertical fenestration that employs a combination of interior and external shading has been separated into multiple segments for compliance purposes. Each segment complies with the requirements for either external or interior PF. Attach additional sheets following a format similar to below:			
		Segment A: 1) West-facing façade shading PF:			
		Segment B:			
		1) West-facing façade shading interior PF:			
		Segment C:			
		1 ) West-facing façade shading interior PF:			
		Segment D:			
		2) South-facing façade shading PF:			
		Segment E:			
		2) South-facing façade shading interior PF:			
		Exceptions §8.4.1.2:  1) Translucent panels and glazing systems with a measured haze value greater than 90%, tested according to ASTM D1003 (notwithstanding its scope) or other test method approved by the AHJ, and that are entirely 8 ft (2.5 m) above the floor, do not require external shading devices.  2) Vertical fenestration that receives direct solar radiation for less than 250 hours per year because of shading by permanent external buildings, existing permanent infrastructure, or topography.			
		Materials			
		§8.4.2: Reported emissions or VOC contents of materials specified below are from a representative product sample and conducted with each product reformulation or at a minimum every three years.	Not provided at this level of detail.		
		§8.4.2: Products certified under third-party certification programs as meeting the specific emission or VOC content requirements listed below are exempted from this three-year testing requirement but shall meet all the other requirements listed below.	Not provided at this level of detail.		
		§8.4.2.1: Adhesives and Sealants			
		§8.4.2.1: All adhesives and sealants used on the interior of the building (defined as inside of the weatherproofing system and applied on site) comply with the requirements of either Section 8.4.2.1.1 or 8.4.2.1.2. (Include document reference to specifications.)	Not provided at this level of detail.		
		§8.4.2.1.1: Emissions of adhesives and sealants have been determined according to CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350) and comply with the limit requirements for either office or classroom spaces, regardless of the space type. (Attach			
		a separate summary sheet and insert document reference.)	Not provided at this level of detail.		

	Indoor Environmental Quality (IEQ) Compliance Documentation – Prescriptive			
Proj	Project Name: U.S. Army Criminal Investigations CommandRA 5-9			
Proj	Project Address:		Date: 12 September 2012	
Desi	igne	r of Record:	Telephone:	
		Person:	Telephone:	
City:	•			
		Prescriptive Option		
Complies	Not applicable	Requirement	Document Reference	
88.4	2.	Materials Cont.		
90.4	<u>z:</u>	§8.4.2.1.2: VOC content complies with and has be determined according to the following limit requirements: (Attach a separate summary sheet and insert document reference.)  a. Adhesives, sealants and sealant primers: SCAQMD Rule 1168. HVAC duct sealants have been classified as "Other" category within the SCAQMD Rule 1168 sealants table.  b. Aerosol adhesives: Green Seal Standard GS-36.		
		Exceptions §8.4.2.1: Not required to meet the emissions or the VOC content requirements:  1) Cleaners, solvent cements, and primers used with plastic piping and conduit in plumbing, fire suppression, and electrical systems.  2) HVAC air duct sealants when the air temperature of the space in which they are applied is less than 40°F (4.5°C).	Not provided at this level of detail.	
			Not provided at this level of detail.	
		§8.4.2.2: Paints and Coatings		
		§8.4.2.2: Paints and coatings used on the interior of the building (defined as inside of the weatherproofing system and applied on site) comply with either Section 8.4.2.2.1 or 8.4.2.2.2. (Include document reference to specifications.)	Not provided at this level of detail.	
		§8.4.2.2.1: Emissions of paints and coatings have been determined according to CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350) and comply with the limit requirements for either office or classroom spaces, regardless of the space type. (Attach a separate summary sheet and insert document reference.)	Not provided at this level of detail.	
		or		
		§8.4.2.2.2: VOC content complies with and has be determined according to the following limit requirements: (Attach a separate summary sheet and insert document reference.) a. Architectural paints, coatings, and primers applied to interior surfaces: Green Seal Standard GS-11. b. Clear wood finishes, floor coatings, stains, sealers, and shellacs: SCAQMD Rule 1113.		
			Not provided at this level of detail.	
		§8.4.2.3: Floor Covering Materials		
		§8.4.2.3a: Carpet has been tested in accordance with and shown to be compliant with the requirements of CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350). Products that have been verified and labeled to be in compliance with Section 9 of the CA/DHS/EHLB/R-174 comply with this requirement. (Include document reference to specifications. Attach a separate summary sheet and insert document reference.)		
			Not provided at this level of detail.	
		§8.4.2.3b: Hard surface flooring in office spaces and classrooms has been tested in accordance with and shown to be compliant with the requirements of CA/DHS/EHLB/R-174	Not provided at this level of detail.	
		§8.4.2.4: Composite Wood, Wood Structural Panel, and Agrifiber Products		
		§8.4.2.4: All composite wood, wood structural panel, and agrifiber products contain no added urea-formaldehyde resins. (Include document reference to specifications. Attach a separate summary sheet and insert document reference.)	Not provided at this level of data!	

	Indoor Environmental Quality (IEQ) Compliance Documentation – Prescriptive				
Pro	ject l	Name: U.S. Army Criminal Investigations CommandRA 5-9			
Pro	ject /	Address:	Date: 12 September 2012		
Des	signe	r of Record:	Telephone:		
Cor	ntact	Person:	Telephone:		
City	<b>'</b> :				
	Prescriptive Option				
Complies	Not applicable	Requirement	Document Reference		
_					
		§8.4.2.4: All laminating adhesives used to fabricate on-site and shop-applied composite wood and agrifiber assemblies contain no added urea-formaldehyde resins. (Include document reference to specifications. Attach a separate summary sheet and insert document reference.)	Not provided at this level of detail		

Proi	ect /	Address:	Date: 12 September 2012
Designer of Record:			Telephone:
Con	tact	Person:	Telephone:
City	City:		
		Prescriptive Option	
Complies	Not applicable	Requirement	Document Reference
<b>88.4</b>	2:	Materials Cont.	
		§8.4.2.4: If the no-added-urea-formaldehyde requirement cannot be met for a specific product (noted below), the project complies with one of the following (attach additional sheets if	Not provided at this level of detail.
		<ul> <li>□ California Air Resource Board's (CARB) regulation "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products," as shown through third-party certification approved by CARB.</li> <li>□ CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350) and shall comply with the limit requirements for either office or classroom spaces regardless of the space type.</li> </ul>	
		☐ Exception §8.4.2.4: Structural panel components such as plywood, particle board, wafer board, and oriented strand board identified as "EXPOSURE 1," "EXTERIOR," or "HUD-APPROVED" are considered acceptable for interior use.	
		§8.4.2.5: Office Furniture Systems and Seating	
		§8.4.2.5: All office furniture systems and seating installed prior to occupancy have been tested according to ANSI/BIFMA Standard M7.1.	Not provided at this level of detail.
		§8.4.2.5: At least 95% of total number of installed office workstations and 95% of total number of seating units installed meet either the emissions concentration limits in Standard M7.1's Table E1.1 or the emission factors in Table E1.2.	Not provided at this level of detail.
		§8.4.2.5: At least 50% of the total number of installed office workstations and 50% of the total number of seating units installed meet the VOC concentration limits of Table E1.3.	Not provided at this level of detail.
		§8.4.2.6: Ceiling and Wall Systems	
		§8.4.2.6: Emissions of all ceiling and wall systems have been determined according to CA/DHS/EHLB/R-174 (commonly referred to as California Section 01350) and comply with the limit requirements for either office or classroom spaces regardless of the space type. (Include document reference to specifications. Attach a separate summary sheet and insert document reference.)	
		<u> </u>	Not provided at this level of detail.
		The proposed and baseline buildings comply with the mandatory requirements of ANSI/ASHRAE/USGBC/IES Standard 189.1-2009 and meet the Prescriptive Option requirements. Individual certifying authenticity of the data provided in this analysis:	
		Signature: Date:	
		Printed Name: License/Registration #:	
		Liconos, Negionalion m.	

	Energy Efficiency Compliance Documentation – Mandatory				
Proj	ect N	Name: U.S. Army Criminal Investigations CommandBattalion Headquarters	-		
Proj	ect A	Address:	Date: 12 September 2012		
Desi	igne	r of Record:	Telephone:		
Con	tact	Person:	Telephone:		
City:					
		Mandatory Provisions			
Complies	Not applicable	Requirement	Document Reference		
		·			
-	.1:	General			
		§7.3.1: The building project has been designed to comply with Sections 5.4, 6.4, 7.4, 8.4, 9.4, and 10.4 of ANSI/ASHRAE/IESNA Standard 90.1.			
§7.3	.2:	On-Site Renewable Energy Systems			
		§7.3.2: The building project provides for the future installation of on-site renewable energy systems with a minimum rating of 3.7 W/ft <sup>2</sup> or 13 Btu/h-ft <sup>2</sup> (40 W/m <sup>2</sup> ) multiplied by the total roof area in ft <sup>2</sup> (m <sup>2</sup> ).			
		§7.3.2: The building project design shows allocated space and pathways for installation of onsite renewable energy systems and associated infrastructure.			
		Exception: The building project has an annual daily average incident solar radiation (available to a flat plate collector oriented due south at an angle from horizontal equal to the latitude of the collector location) of less than 4.0 kW/m²-day, accounting for existing buildings, permanent infrastructure that is not part of the building project, topography, or trees.			
§7.3	.3:	Energy Consumption Management			
		§7.3.3.1: Measurement devices with remote communication capability have been provided to collect energy consumption data for each energy supply source to the building (including gas, electricity, and district energy) that exceeds the thresholds listed in Table 7.3.3.1A. Measurement devices have the capability to automatically communicate energy consumption data to a data acquisition system.	Not provided at this level of detail.		
		§7.3.3.1: For all buildings that exceed the thresholds in Table 7.3.3.1A, measurement devices with remote capability (including current sensors or flow meters) have been provided to measure energy consumption data of each subsystem for each use category that exceeds the thresholds listed in Table 7.3.3.1B. Measurement devices have the capability to automatically communicate energy consumption data to a data acquisition system.	Not provided at this level of detail.		
		§7.3.3.2: All building measurement devices have been configured to automatically communicate energy data to the data acquisition system.	Not provided at this level of detail.		
		§7.3.3.2: All building measurement devices provide daily data and record hourly energy profiles. The hourly energy profiles are capable of being used to assess building performance at least monthly.	Not provided at this level of detail.		
		§7.3.3.3: The data acquisition system is capable of electronically storing the data from the measurement devices and other sensing devices for a minimum of 36 months, and creating user reports showing hourly, daily, monthly, and annual energy consumption.	Not provided at this level of detail.		
		Exception: Portions of buildings used as residential.  The proposed and baseline buildings comply with the mandatory requirements of ANSI/ASHRAE/USGBC/IES Standard 189.1-2009. Individual certifying authenticity of the data provided in this analysis:			
		Date: Printed Name:			
		License/Registration #:			
		Company Name:			

		Energy Efficiency Compliance Documentation – Pres	criptive
		Name: U.S. Army Criminal Investigations CommandBattalion Headquarters	<u> </u>
		Address:	Date: 12 September 2012
		r of Record:	Telephone:
		Person:	Telephone:
City:			
		Prescriptive Option	
Complies	Not applicable	Requirement	Document Reference
_		General	
		§7.4.1: When a requirement is provided below, it supersedes the requirement in ANSI/ASHRAE/IESNA Standard 90.1. For all other criteria, the building project complies with the requirements of ANSI/ASHRAE/IESNA Standard 90.1.	
§7.4	.1.1:	On-Site Renewable Energy Systems	
<b>√</b>		§7.4.1.1: The building project contains on-site renewable energy systems that together provide annual energy production equivalent to not less than 6.0 KBtu/ft² (20 kWh/m²) of conditioned space.	Design Analysis, Appendix E: Energy Modeling
		Exception: The building demonstrates compliance with both of the following and is not required to have an on-site renewable energy system:  1. An annual daily average incident solar radiation available to a flat plate collector oriented due south at an angle from horizontal equal to the latitude of the collector location of less than 4.0 kW/m²-day, accounting for existing buildings, permanent infrastructure that is not part of the building project, topography, and trees.	
		2. Purchase of renewable electricity products complying with the Green-e Energy National Standard for Renewable Electricity Products of at least 7 kWh/ft² (75 kWh/m²) of conditioned space each year until the cumulative purchase totals 70 kWh/ft² (750 kWh/m²) of conditioned space.	
§7.4	.2:	Building Envelope	
		§7.4.2: The building envelope complies with Section 5 of ANSI/ASHRAE/IESNA Standard 90.1 with the	
<b>√</b>		following modifications and additions.  §7.4.2.1: The building envelope complies with the requirements in Tables A-1 to A-8 in Normative Appendix A. These requirements supersede the requirements in Tables 5.5-1 to 5.5-8 of ANSI/ASHRAE/IESNA Standard 90.1.  □ Exception: Buildings that comply with Section 8.3.4 regardless of building area are exempt from the	Design Analysis, Appendix A: Project Tracking Sheet
		SHGC criteria for skylights.	Design Analysis Annandiy A
<b>V</b>		§7.4.2.2: Roofs comply with the provisions of Section 5.3.2.3 and Tables A-1 to A-8 of this standard. Section 5.5.3.1.1 of ANSI/ASHRAE/IESNA Standard 90.1 and Table 5.5.3.1 of ANSI/ASHRAE/IESNA Standard 90.1 were not used.	Design Analysis, Appendix A: Project Tracking Sheet
	✓	§7.4.2.3: Single-rafter roofs comply with the requirements in Table A-9 in Normative Appendix A. These requirements supersede the requirements in Section A2.4.2.4 of ANSI/ASHRAE/IESNA Standard 90.1. Section A2.4.2.4 and Table A2.4.2 of ANSI/ASHRAE/IESNA Standard 90.1 were not used.	
<b>√</b>		§7.4.2.4: The total vertical fenestration area is less than 40% of the gross wall area. This requirement supersedes the requirement in Section 5.5.4.2.1 of ANSI/ASHRAE/IESNA Standard 90.1.	Design Analysis, Appendix A: Project Tracking Sheet
		§7.4.2.5: For climate zones 1–5, the vertical fenestration on the west, south, and east is shaded by permanent projections that have an area-weighted average PF of not less than 0.50.	Design Analysis, Appendix F: ANSI/ASHRAE Standard 189.1 Compliance
		Exception: Vertical fenestration that receives direct solar radiation for fewer than 250 hours per year because of shading by permanent external buildings, existing permanent infrastructure, or topography.	

	Energy Efficiency Compliance Documentation – Prescriptive				
H	Project Name: U.S. Army Criminal Investigations CommandBattalion Headquarters				
H		Address:	Date: 12 September 2012		
_	<u> </u>	r of Record:	Telephone:		
		Person:	Telephone:		
City	:				
	1	Prescriptive Option	T		
Complies	Not applicable	Requirement	Document Reference		
§7.4	.2:	Building Envelope Cont.			
<b>√</b>		§7.4.2.6: For SHGC compliance, the methodology in exception (b) to Section 5.5.4.4.1 of ANSI/ASHRAE/IESNA Standard 90.1 were applied (provided that the SHGC multipliers in Table 7.4.2.6 are used). This requirement supersedes the requirement in Table 5.5.4.4.1 of ANSI/ASHRAE/IESNA Standard 90.1. Table 5.5.4.4.1 of ANSI/ASHRAE/IESNA Standard 90.1 was not applied.	Design Analysis, Appendix F: ANSI/ASHRAE Standard 189.1 Compliance		
<b>√</b>		§7.4.2.6: The vertical fenestration is north-oriented and has a maximum SHGC of 0.10 greater than that specified in Tables A-1 through A-8 in Normative Appendix A. Separate calculations were performed for these sections of the building envelope, and these values were not averaged with any others for compliance purposes.	A-603, Window Schedule		
<b>√</b>		§7.4.2.7: For vestibules, the exceptions to Section 5.4.3.4 of ANSI/ASHRAE/IESNA Standard 90.1 were applied (provided that climate zone 4 is deleted from exception (e) to Section 5.4.3.4 of ANSI/ASHRAE/IESNA Standard 90.1 and that climate zone 4 is added to exception (f) to Section 5.4.3.4 of ANSI/ASHRAE/IESNA Standard 90.1).			
<b>√</b>		§7.4.2.8: The building envelope trade-off option in Section 5.6 of ANSI/ASHRAE/IESNA Standard 90.1 was not applied (unless the procedure incorporates the modifications and additions to ANSI/ASHRAE/IESNA Standard 90.1 noted in Section 7.4.2).			
<b>√</b>		§7.4.2.9a: To reduce solar gains from the east and west in climate zones 1 through 4, the fenestration area and SHGC complies with the calculation in 7.4.2.9a.	173133A_CIC_BTH_Architectural: Schedule: ASHRAE 189.1-2009, 7.4.2.9a Part 1/2		
	✓	§7.4.2.9b: To reduce solar gains from the west in climate zones 5 and 6, the fenestration area and SHGC complies with the calculation in 7.4.2.9b.  Exceptions 7.4.2.9:  □ a. Vertical fenestration that complies with the exception to Section 5.5.4.4.1 (c) of ANSI/ASHRAE/IESNA Standard 90.1.  □ b. Buildings that have an existing building or existing permanent infrastructure within 20 ft (6 m) to the south or north that is at least half as tall as the proposed building.  □ c. Buildings with shade on 75% of the west- and east-oriented vertical fenestration areas from existing buildings, existing permanent infrastructure, or topography at 9 a.m. and 3 p.m. on the summer solstice.  □ d. Alterations and additions with no increase in vertical fenestration area.			
<b>√</b>		§7.4.2.10: The building envelope was designed and constructed with a continuous air barrier that complies with Normative Appendix B to control air leakage into, or out of, the conditioned space. All air barrier components of each envelope assembly are clearly identified on construction documents and the joints, interconnections, and penetrations of the air barrier components are detailed.  □ Exception: Building envelopes of semiheated spaces provided that the building envelope complies with Section 5.4.3.1 of ANSI/ASHRAE/IESNA Standard 90.1.	Sheet A-311: This requirement is partially fulfilledthe remainder of the documentation requirements are not provided at this level of detail.		

		Energy Efficiency Compliance Documentation – Pres	criptive	
Project Name: U.S. Army Criminal Investigations CommandBattalion Headquarters				
Pro	ject /	Address:	Date: 12 September 2012	
Des	signe	r of Record:	Telephone:	
Cor	ntact	Person:	Telephone:	
City	<i>'</i> :			
		Prescriptive Option		
Complies	Not applicable	Requirement	Document Reference	
<b>§7.</b>	4.3:	Heating, Ventilating, and Air Conditioning		
<u></u>		§7.4.3: The heating, ventilating, and air conditioning complies with Section 6 of ANSI/ASHRAE/IESNA Standard 90.1 with the following modifications and additions.		
		§7.4.3.1: The Project complies with one of the following:  a. EPAct baseline. Products comply with the minimum efficiencies addressed in the National Appliance Energy Conservation Act (NAECA), Energy Policy Act (EPAct), and the Energy Independence and Security Act (EISA), or  b. Higher Efficiency. Products comply with the greater of the ENERGY STAR requirements in Section 7.4.7.3 and the values in Normative Appendix C. These requirements supersede the requirements in Tables 6.8.1A to 6.8.1J of ANSI/ASHRAE/IESNA Standard 90.1. The building project complies with Sections 7.4.1.1 and 7.4.5.1 with the following modifications:  1. The on-site renewable energy systems required in Section 7.4.1.1 shall provide an annual energy	Not provided at this level of detail.	
		production of not less than 4.0 kBtu/ft2 (13 kWh/m2).  2. The peak load reduction systems required in Section 7.4.5.1 shall be capable of reducing electric peak demand by not less than 5% of the projected peak demand.		
		§7.4.3.2: DCV is used for densely occupied spaces. This requirement supersedes the occupant density threshold in Section 6.4.3.9 of ANSI/ASHRAE/IESNA Standard 90.1.		
		§7.4.3.2: The DCV system is designed to be in compliance with ANSI/ASHRAE Standard 62.1. Occupancy assumptions are shown in the design documents for spaces required to have DCV. All CO2 sensors used as part of a DCV system or any other system that dynamically controls outdoor air shall meet requirements a through d as listed in 7.4.3.2.		
		§7.4.3.3: For duct sealing, Seal Level A was be used. This requirement supersedes the requirements in Table 6.4.4.2A of ANSI/ASHRAE/IESNA Standard 90.1.	Not provided at this level of detail.	
		§7.4.3.4: Systems have economizers meeting the requirements in Section 6.5.1 of ANSI/ASHRAE/IESNA 90.1 except as noted in 1 through 4 of 7.4.3.4.   Exception: All the exceptions in Sections 6.5.1 and 6.5.1.3 of ANSI/ASHRAE/IESNA Standard 90.1 apply except as noted in 1 through 3 in 7.4.3.4 Exceptions.	Not provided at this level of detail.	
		§7.4.3.5: Exception (a) to Section 6.5.2.1 of ANSI/ASHRAE/IESNA Standard 90.1 have been replaced by the following: zones for which the volume of air that is reheated, re-cooled, or mixed is not greater than the larger of (1) the design outdoor airflow rate for the zone, or (2) 15% of the zone design peak supply rate.	Not provided at this level of detail.	
		§7.4.3.6: Systems have fan power limitations 10% below limitations specified in Table 6.5.3.1.1A of ANSI/ASHRAE/IESNA Standard 90.1. This requirement supersedes the requirement in Section 6.5.3.1 and Table 6.5.3.1.1A of ANSI/ASHRAE/IESNA Standard 90.1. All exceptions in Section 6.5.3.1 of ANSI/ASHRAE/IESNA Standard 90.1 shall apply.	Not provided at this level of detail.	
		§7.4.3.7a: DX systems with a capacity greater than 65,000 Btu/h (19 kW) have a minimum of two stages of cooling capacity.	Not provided at this level of detail.	
	<b>✓</b>	§7.4.3.7b: Air-handling and fan-coil units with chilled-water cooling coils and supply fans with motors greater than or equal to 5 hp have their supply fans controlled by two-speed motors or variable-speed drives. At cooling demands less than or equal to 50%, the supply fan controls are able to reduce the airflow to no greater than the larger of the following:  1. Two-thirds of the full fan speed, or  2. The volume of outdoor air required to meet the ventilation requirements of ANSI/ASHRAE Standard 62.1.		

		Energy Efficiency Compliance Documentation – Pres	criptive
Proj	ect N	Name: U.S. Army Criminal Investigations CommandBattalion Headquarters	
Proj	ect A	Address:	Date: 12 September 2012
Des	igne	r of Record:	Telephone:
Con	tact	Person:	Telephone:
City	:		
		Prescriptive Option	
Complies	ot applicable		
ပိ	Not	Requirement	Document Reference
§7.4	.3:	Heating, Ventilating, and Air Conditioning Cont.	
		§7.4.3.7c: All air-conditioning equipment and air-handling units with direct expansion cooling and a cooling capacity at AHRI conditions greater than or equal to 110,000 Btu/h (32.2 kW) that serve single zones have their supply fans controlled by two-speed motors or variable-speed drives. At cooling demands less than or equal to 50%, the supply fan controls are able to reduce the airflow to no greater than the larger of the following:  1. Two-thirds of the full fan speed, or 2. The volume of outdoor air required to meet the ventilation requirements of ANSI/ASHRAE Standard 62.1.	Not provided at this level of detail.
		<ul> <li>§7.4.3.7d: d. All DX and chilled-water VAV units are equipped with variable-speed fans that result in less than 30% power at 50% flow.</li> <li>Exception 7.4.3.7: When air ventilation rates or air exchange rates require constant volume fan operation.</li> </ul>	Not provided at this level of detail.
		§7.4.3.8: Each fan system has an energy recovery system when the system's supply airflow rate exceeds the value listed in Table 7.4.3.8 based on the climate zone and percentage of outdoor air at design condi-tions. Where a single room or space is supplied by multiple units, the aggregate supply cfm (L/s) of those units was used in applying this requirement.	Not provided at this level of detail.
		§7.4.3.8: Energy recovery systems required by this section have at least 60% energy recovery effectiveness. Sixty percent energy recovery effectiveness shall mean a change in the enthalpy of the outdoor air supply equal to 60% of the difference between the outdoor air and return air enthalpies at design conditions. Provisions have been made to bypass or control the energy recovery system to permit air economizer operation as required by Section 7.4.3.4.	Not provided at this level of detail.
	<b>√</b>	§7.4.3.9: In addition to the requirements in Section 6.5.7.1 of ANSI/ASHRAE/IESNA Standard 90.1, commercial kitchen Type I and Type II hood systems have variable-speed control for exhaust and makeup air fans to reduce hood airflow rates at least 50% during those times when cooking is not occurring and the cooking appliances are up to temperature in a standby, ready-to-cook mode. All exceptions in Section 6.5.7.1 of ANSI/ASHRAE/IESNA Standard 90.1 shall apply.	
		§7.4.3.10: Duct insulation complies with the minimum requirements in Tables C-9 and C-10 in Normative Appendix C. These requirements supersede the requirements in Tables 6.8.2A and 6.8.2B of ANSI/ASHRAE/IESNA Standard 90.1.	Not provided at this level of detail.
		§7.4.3.11: Pipe insulation complies with the minimum requirements in Table C-11 in Normative Appendix C. These requirements supersede the requirements in Table 6.8.3 of ANSI/SHRAE/IESNA Standard 90.1. The exceptions a through e in Section 6.4.4.1.3 of ANSI/ASHRAE/IESNA Standard 90.1 shall apply.	Not provided at this level of detail.
	<b>√</b>	§7.4.3.12: In hotels and motels with over 50 guest rooms, the lighting switched outlets, television, and HVAC equipment serving each guest room are automatically controlled such that the lighting, switched outlets, and televisions will be turned off and the HVAC setpoint raised at least 5°F (3°C) in the heating mode whenever the guest room is unoccupied.	

		Energy Efficiency Compliance Decumentation - Bree	orintivo		
Б.	Energy Efficiency Compliance Documentation – Prescriptive				
		Name: U.S. Army Criminal Investigations CommandBattalion Headquarters	Date: 12 September 2012		
		Address: r of Record:	Telephone:		
	_	Person:	Telephone:		
City		reisui.	reiepriorie.		
Oity	•	Prescriptive Option			
	Ф	1 Toompave Option			
	applicable				
Complies	ppli				
omp	Not a	Requirement	Document Reference		
0	Z	Requirement	Doddinent Neierende		
§7.4	.4:	Service Water Heating			
		§7.4.4: The service water heating complies with Section 7 of ANSI/ASHRAE/IESNA Standard 90.1 with the following modifications and additions.			
		§7.4.4.1: Equipment complies with the minimum efficiencies in Table C-12 in Normative Appendix C. These	Not provided at this level of detail.		
		requirements supersede the requirements in Table 7.8 of ANSI/ASHRAE/IESNA Standard 90.1.			
			Not provided at this level of detail.		
		§7.4.4.2: Pipe insulation complies with Section 7.4.3.11. These requirements supersede the requirements in Section 7.4.3 of ANSI/ASHRAE/IESNA Standard 90.1.			
		Occion 7.4.5 of ANOMAGNIKAL/ILGIVA Glandard 50.1.			
	<b>√</b>	§7.4.4.3: Pools heated to more than 90°F (32°C) have side and bottom surfaces insulated on the exterior with			
		a minimum insulation value of R-12 (R-2.1).			
§7.4	.5:	Power			
		§7.4.5: The power complies with Section 8 of ANSI/ASHRAE/IESNA Standard 90.1 with the following			
		modifications and additions.	Not provided at this level of detail.		
		§7.4.5.1: The Building project contains automatic systems, such as demand limiting or load shifting, that are	Not provided at this level of detail.		
		capable of reducing electric peak demand of the building by not less than 10% of the projected peak demand. Standby power generation is not used to achieve the reduction in peak demand.			
§7.4	.6:	Lighting			
٦	П	§7.4.6: The lighting complies with Section 9 of ANSI/ASHRAE/IESNA Standard 90.1 as modified by			
_	] [	Addendum i and the following modifications and additions.	172122A CIC RTH Floatrical nut		
*		§7.4.6.1: The lighting power allowance is a maximum of 0.9 multiplied by the values determined in accordance with Sections 9.5 and 9.6. This requirement supersedes the requirements in Sections 9.5 and 9.6 of	Schedule: ASHRAE 189.1 Lighting		
		ANSI/ASHRAE/IESNA Standard 90.1.	LPD		
		\$7.4.0.0. Offices 250.60 (25 = 20) or analles places are af an aim leature training an acceptional resume of	Not provided at this level of detail.		
		§7.4.6.2: Offices 250 ft2 (25 m2) or smaller; classrooms of any size; lecture, training, or vocational rooms of less than 1000 ft2 (100 m2); multipurpose rooms of less than 1000 ft2 (100 m2); conference rooms and			
		meeting rooms less than 1000 ft2 (100 m2); and meeting centers are equipped with occupant sensor(s) to			
		automatically turn lighting OFF within 30 minutes of all occupants leaving a space and allow "manual OFF" control. In addition, all occupancy sensor controls are either "manual ON" or bi-level "automatic ON"			
		programmed to a low light level combined with multi-level circuitry and "manual ON" switching for higher light			
		levels. Where such occupancy sensors are utilized within a daylit area and daylighting controls are utilized, the occupancy sensors work in conjunction with the daylighting controls complying with Section 7.4.6.5.			
		§7.4.6.3: The lighting in the areas listed in 7.4.63 are controlled by an occupant sensor with multi-level	Not provided at this level of detail.		
		switching or dimming system that reduces lighting power a minimum of 50% when no persons are present.			
		☐ Exception: Areas lit by HID lighting with a lighting power density of 0.8 W/ft2 or less.			
			Design Analysis, Appendix F:		
_	_	§7.4.6.4: Lighting in any area within a building that is required to be continuously illuminated for reasons of building security or emergency egress does not exceed 0.1 W/ft2 (1 W/m2). Any additional egress and security	ANSI/ASHRAE Standard 189.1		
		are controlled by an automatic control device that turns off the additional lighting.	Compliance		

		Energy Efficiency Compliance Documentation – Pres	criptive		
Proj	ect l	Name: U.S. Army Criminal Investigations CommandBattalion Headquarters			
Proj	ect /	Address:	Date: 12 September 2012		
Des	igne	r of Record:	Telephone:		
Cor	tact	Person:	Telephone:		
City	:				
-	,	Prescriptive Option			
	ple				
Se	applicable				
Complies	арр				
Co	Not	Requirement	Document Reference		
\$7 <i>(</i>	16.	Limbing Cont			
97.4	1.6:	Lighting Cont.	Not provided at this level of detail.		
		<ul> <li>§7.4.6.5: Lighting in all daylight zones, including daylight zones under skylights and daylight zones adjacent to vertical fenestration, where the combined daylight zone per enclosed space is greater than 250 ft2 (25 m2), are provided with controls that automatically reduce lighting power in response to available daylight by either: <ul> <li>a. Continuous daylight dimming, or</li> <li>b. A combination of stepped switching and daylight-sensing automatic controls, which are capable of incrementally reducing the light level in steps automatically and turning the lights off automatically.</li> </ul> </li> <li>Exceptions: <ul> <li>1. Window display and exhibition lighting.</li> <li>2. Conference rooms greater than 250 ft2 (25 m2) that have a lighting control system with at least four scene options.</li> <li>3. Lighting in conference rooms that is dimmable and controlled by dimming controls that are located within the space and accessible to the space occupants.</li> <li>4. Saunas, steam rooms, and spaces containing swimming pools or spa pools.</li> <li>5. Spaces where medical procedures are performed.</li> <li>6. Spaces within dwelling units.</li> <li>7. Spaces within hotel and motel guest rooms and suites.</li> <li>8. Daylight zones where the height of existing adjacent structures above the window is at least twice the distance between the window and adjacent structures, measured from the top of the glazing.</li> </ul> </li> </ul>	·		
		§7.4.6.6: Occupancy sensors have "manual ON", "automatic OFF" controls.	Not provided at this level of detail.		
		☐ Exception: Occupancy sensor controls required in Section 7.4.6.3.			
		\$7.4.6.7: All outdoor lighting controls comply with Section 9 of ANSI/ASHRAE/IESNA Standard 90.1 with the following modifications and additions. For lighting of building facades, parking lots, garages, canopies (sales and non-sales), and all outdoor sales areas, automatic controls are installed to reduce the sum of all lighting power (in watts) by a minimum of 50% one hour after normal business closing and to turn off outdoor lighting within 30 minutes after sunrise.  Exceptions:  1. Lighting required by a health or life safety statute, ordinance, or regulation, including but not limited to, emergency lighting.  2. Lighting that is controlled by a motion sensor and photocontrol.  3. Lighting for facilities that have equal lighting requirements at all hours and are designed to operate conti-nuously.  4. Temporary outdoor lighting.  5. Externally illuminated signs and signs that are internally illuminated or have integral lamps.	Not provided at this level of detail.		

		Energy Efficiency Compliance Documentation – Pres	criptive			
H	Project Name: U.S. Army Criminal Investigations CommandBattalion Headquarters					
Proj	ect A	Address:	Date: 12 September 2012			
Des	igne	r of Record:	Telephone:			
Con	tact	Person:	Telephone:			
City	:					
		Prescriptive Option				
Complies	Not applicable	Requirement	Document Reference			
		-				
§7.4	l.7:	Other Equipment				
		§7.4.7: All other equipment complies with Section 10 of ANSI/ASHRAE/IESNA Standard 90.1 with the following modifications and additions.				
		§7.4.7.1: Motors comply with the minimum requirements in Table C-13 in Normative Appendix C. These requirements supersede the requirements in Section 10.4.1 and Table 10.8 of ANSI/ASHRAE/IESNA Standard 90.1.	Not provided at this level of detail.			
		§7.4.7.2: Supermarkets with a floor area of 25,000 ft <sup>2</sup> (2500 m <sup>2</sup> ) or greater recover waste heat from the condenser heat rejection on permanently installed refrigeration equipment meeting <i>one</i> of the following criteria:  1. 25% of the refrigeration system full load total heat rejection.  2. 80% of the space heat, service water heating and dehumidification reheat.	Not provided at this level of detail.			
		§7.4.7.2: If a recovery system is installed in the refrigeration system, the system does not increase the saturated condensing temperature at design conditions by more than 5°F (3°C) and does not impair other head pressure control/energy reduction strategies.	Not provided at this level of detail.			
		\$7.4.7.3: The following equipment within the scope of the applicable Energy Star program complies with the relevant criteria required to achieve the Energy Star label, if installed prior to the issuance of the certificate of occupancy (see Section 7.4.7.3 a—h for a complete equipment list):  a. Appliances b. Heating and cooling equipment c. Electronics d. Office equipment e. Water heaters f. Lighting g. Commercial food service equipment h. Other products  Exception: Products with minimum efficiencies addressed in the Energy Policy Act (EPAct) and the	Not provided at this level of detail.			
		Energy Independence and Security Act (EISA), if the project complies with Section 7.4.3.1a.				
	<b>√</b>	§7.4.7.4a: Commercial refrigerators and freezers comply with the minimum efficiencies in Table C-14 in Normative Appendix C.				
	<b>V</b>	§7.4.7.4a: There are no prohibited open refrigerated display cases not covered by strips or curtains.				
		§7.4.7.4a: Lighting loads for commercial reach-in refrigerator/freezer display cases, including all power supplies or ballasts, do not exceed 42 watts per door for case doors up to 5 ft (1.5 m) in height and 46 watts per door for case doors greater than 5 ft (1.5 m) in height.				
	<b>√</b>	§7.4.7.4b: Commercial clothes washers comply with the minimum efficiencies in Table C-15 in Normative Appendix C.				

	Energy Efficiency Compliance Documentation – Prescriptive					
Pro	Project Name: U.S. Army Criminal Investigations CommandBattalion Headquarters					
Pro	ject /	Address:	Date: 12 September 2012			
Des	signe	r of Record:	Telephone:			
Cor	ntact	Person:	Telephone:			
City	<b>'</b> :					
		Prescriptive Option				
Complies	Not applicable Requirement		Document Reference			
§7.	4.8:	Energy Cost Budget				
<b>√</b>		§7.4.8: The Energy Cost Budget option in Section 11 of ANSI/ASHRAE/IESNA Standard 90.1 was not used.				
The proposed and baseline buildings comply with the mandatory requirements of ANSI/ASHRAE/USGBC/IES Standard 189.1-2009 and meet the Prescriptive Option requirements. Individual certifying authenticity of the data provided in this analysis:						
		Signature: Date:				
		Printed Name: License/Registration #:				
Company Name:						

	Water Use Efficiency Compliance Documentation – Prescriptive				
Project Name: U.S. Army Criminal Investigations CommandRA 5-9					
Proj	ect A	Address:	Date: 12 September 2012		
Des	igne	r of Record:	Telephone:		
Contact Person:			Telephone:		
City	:				
		Prescriptive Option			
Complies	Not applicable	Requirement	Document Reference		
§6.4	l.1:	Site Water Use Reductions			
		§6.4.1: Golf courses and driving ranges use only municipally-reclaimed water and/or alternate on-site sources of water; in other landscaped areas, a maximum of one third of <i>improved landscape</i> area is irrigated with potable water – all other irrigation is provided from alternate on site sources or municipally reclaimed water.			
		§6.4.1: Athletic fields have been excluded from the calculation of <i>improved landscape</i> for schools, residential common areas, and public recreational facilities.			
		§6.4.1: Potable water has been temporarily used on newly installed landscape during the landscape establishment period.			
		$\S6.4.1$ : The amount of potable water used during the landscape establishment period does not exceed 70% ET $_{\rm o}$ for turfgrass and 55% ET $_{\rm o}$ for other plantings.			
		§6.4.1: Municipally reclaimed water is available at a water main within 200 ft (60 m) of the project site and has been used in lieu of potable water during the landscape establishment period.			
		§6.4.1: Once the landscape establishment period ended, irrigation water use complied with the requirements listed in §6.3.1 and §6.4.1.			
§6.4	l.2:	Building Water Use Reductions			
		§6.4.2.1a: For cooling tower makeup water having < 200 ppm (200 mg/L) of total hardness (expressed as calcium carbonate), at least 5 cycles of concentration have been achieved.	Not provided at this level of detail.		
		§6.4.2.1b: For cooling tower makeup water having > 200 ppm (200 mg/L) of total hardness (expressed as calcium carbonate), at least 3.5 cycles of concentration have been achieved.	Not provided at this level of detail.		
		Exception: Where the total dissolved solids concentration of the discharge water exceeds 1500 mg (1500 ppm/L), or silica exceeds 150 ppm (150 mg/L), measured as silicon dioxide, before the above cycles of concentration are reached.			
	✓	§6.4.2.2a: Commercial food service operations use high-efficiency pre-spray valves per §6.4.2.2.			
	✓	§6.4.2.2b: Commercial food service operations use dishwashers that are ENERGY STAR certified.			
	<b>√</b>	§6.4.2.2c: Commercial food service operations use boilerless/connectionless food steamers that consume no more than 2.0 gal/h (7.5 L/h).			
	<b>√</b>	§6.4.2.2d: Commercial food service operations use combination ovens that consume no more than 10 gal/h (38 L/h).			
	<b>√</b>	§6.4.2.2e: Commercial food service operations use air-cooled ice machines that are ENERGY STAR certified.			
	<b>√</b>	§6.4.2.2f: Commercial food service operations are equipped with hands-free faucet controllers within the food preparation area of the kitchen and dish room, including pot sinks and washing			
	<b>√</b>	§6.4.2.3a: Medical and lab facilities use only water-efficient steam sterilizers.			
	<b>✓</b>	§6.4.2.3a: Steam sterilizers use water-tempering devices that only allow water to flow when the discharge of condensate or hot water from the sterilizer > 140°F.			
	<b>√</b>	\$6.4.2.3a: Vacuum sterilizers use mechanical vacuum equipment in place of Venturi-type vacuum systems.			
	✓	§6.4.2.3b: Medical and lab facilities use film processor water recycling units where large frame X-ray films of more than 6 inches are processed. Small dental X-ray equipment is exempt from this requirement.			

	Water Use Efficiency Compliance Documentation – Prescriptive				
Pro	ject l	Name: U.S. Army Criminal Investigations CommandRA 5-9			
Pro	ject /	Address:	Date: 12 September 2012		
Des	igne	r of Record:	Telephone:		
Cor	ntact	Person:	Telephone:		
City	<b>'</b> :				
		Prescriptive Option			
Complies	Not applicable	Requirement	Document Reference		
	<b>√</b>	§6.4.2.3c: Where the digital networks are installed, medical and lab facilities use digital imaging and radiography systems.			
	<b>✓</b>	§6.4.2.3d: Medical and lab facilities use a dry-hood scrubber system. For projects that determine wet scrubber systems are necessary, the scrubber is equipped with a water recirculation system.			
	<b>√</b>	§6.4.2.3d: For medical and lab facilities that include hood washdown systems, the hood is equipped with self-closing valves			

		Water Use Efficiency Compliance Documenta	ntion – Prescriptive					
Proj	ect N	Name: U.S. Army Criminal Investigations CommandRA 5-9						
Proj	ect A	Address:	Date: 12 September 2012					
Des	igne	r of Record:	Telephone:					
Con	tact	Person:	Telephone:					
City								
Prescriptive Option								
Complies	t applicable							
ပိ	Not	Requirement	Document Reference					
Building Water Use Reductions Cont.								
	✓	§6.4.2.3e: Medical and lab facilities use only dry vacuum pumps, unless fire and safety codes						
	<b>√</b>	require a liquid ring pump. §6.4.2.3f(1): For filtration processes in medical and lab facilities, pressure gauges are used to						
	•	determine and display when to backwash or change cartridges.						
	<b>√</b>	§6.4.2.3f(2): For ion exchange and softening processes in medical and lab facilities, recharge cycles have been set by volume of water treated or based upon conductivity or hardness.						
	✓	§6.4.2.3f(3): For reverse osmosis and nanofiltration equipment in medical and lab facilities with a capacity > 100 L/hour, reject water does not exceed 60% of the feed water and is used as scrubber feed water or for other beneficial uses on the project site.						
	<b>√</b>	§6.4.2.3f(4): For medical and lab facilities, simple distillation has not been used as a means of water purification.						
	<b>√</b>	§6.4.2.3g: Food service operations that are located within medical or lab facilities comply with §6.4.2.2.						
	<b>√</b>	§6.4.3a: Ornamental fountains are supplied either by alternate on-site sources of water or municipally reclaimed water.						
	✓	§6.4.3a: Fountains are equipped with makeup water meters.						
	✓ ✓	§6.4.3a: Fountains are equipped with leak detection devices that shut off water flow if a leak of more than 1 gallon per hour is detected.  §6.4.3a: Fountains are able to recirculate, filter, and treat all water for reuse within the system.						
<b>J</b>		Exception: For fountains where alternate on-site sources of water or municipally reclaimed water are not available with 500 ft (150 m) of the building project site, potable water is allowed to be used for water features with less than 10,000 gal (38,000 L) capacity.						
	<b>√</b>	§6.4.3b(1): Pools and spas must recover filter backwash water for reuse on landscaping or other applications, or treat and reuse backwash water within the system.						
	<b>√</b>	§6.4.3b(2): For pools and spas that use removable cartridges, only reusable cartridges and systems are used.						
	<b>√</b>	equipment has been used that includes a pressure drop gauge to determine when the filter needs to be backwashed and a sight glass enabling the operator to determine when to stop the backwash cycle.						
	✓	§6.4.3b(3): If pool and spa splash troughs are provided, they drain back into the pool or spa.						
		The proposed and baseline buildings comply with the mandatory requirements of ASHRAE/USGBC/IES Standard 189.1-2009 and meet the Prescriptive Option requirements. Individual certifying authenticity of the data provided in this analysis:						
		Signature: Date:						
		Printed Name: License/Registration #:						
		Company Name:						



Subject: ASHRAE 189.1-2009 Projection Factor Calculation/SHGC Multiplier

CIDC RA 5-9

Page:	1	of	1			
Made by:	: JPB					
Date:	10-Sep-2	2012				
Checked by:						
Date:			<b></b>			

The minimum projection factor requirement is 0.5

PF = P/(D+H) P = 44 in.

D= 11 in.


PF= 0.62 H= 60 in.

Check:

0.62 ≥ 0.50

 $0.62 \rightarrow SHGC$  multiplier of 0.92 is allowed for E, S, W orientations.

SHGC multiplier of 0.96 is allowed for N orientation.



## PARSONS BRINCKERHOFF Computation Sheet

page 1 of 1	
made by BAGNI SINH	4
date 03.12.2012	
checked by	
date	

subject RA 5-9 LPD CALCULATIONS

EMERGENCY LIGHTS : (2) 1W LED LAMP FIXTURE